	PIPING SYMBOLS —					
	IFING SIMBOLS	WAIER FLOW DATA				
———DR———	DRAIN RISER	HAZARD CLASSIFICATION: LIGHT HAZARD				
———DS———	DRY PIPE SPRINKLER SYSTEM	OBTAIN LATEST FLOW TEST RESULTS FROM OWNER FOR USE WITH NEW				
—— F ——	FIRE MAIN, DISTRIBUTION PIPING	HYDRAULIC CALCULATIONS.				

PREACTION SPRINKLER SYSTEM

WET STANDPIPE SYSTEM
WET SPRINKLER SYSTEM

PIPING TO BE DEMOLISHED

DIRECTION OF FLOW

<del>////////</del>


ID	TYPE	SYMBOL	DESCRIPTION	TEMP RATING	K FACTOR	ORIFICE	AREAS OF USE
Α	CONCEALED	0	QUICK RESPONSE	155 F	5.6	1/2"	LIGHT/ORDINARY HAZARD
В	RECESSED PENDENT	•	QUICK RESPONSE	155 F	5.6	1/2"	LIGHT/ORDINARY HAZARD
С	SIDEWALL	◁	QUICK RESPONSE	155 F	5.6	1/2"	LIGHT/ORDINARY HAZARD
D	EXPOSED PENDENT		STANDARD RESPONSE	155 F	5.6	1/2"	EXPOSED AREAS
Е	DRY PENDENT	<b>●</b> DP	STANDARD RESPONSE	165 F	5.6	1/2"	COLD ROOMS
F	EXPOSED PENDENT		STANDARD RESPONSE	200 F	5.6	1/2"	MECH/ELEC ROOMS
G	EXPOSED PENDENT		STANDARD RESPONSE	286 F	5.6	1/2"	ELEV MACHINE ROOMS
Н	ESFR UPRIGHT	0	FAST RESPONSE	165 F	25	1"	WAREHOUSE AREA
[	EXPOSED UPRIGHT	0	QUICK RESPONSE	155 F	5.6	1/2"	POOL AREA
J	PENDENT		STANDARD RESPONSE	155 F	8.0	3/4"	ORDINARY HAZARD

*	TYPE I HEAD	SHALL HAVE	TEFLON/F	POLYESTER	COATING F	OR	CORROSION	RESISTANCI


	FIRE PROTECTION SYMBOLS —	,	ABBREVIATIONS —————
<u>SYMBOL</u>	DESCRIPTION	<u>ABBREVIATION</u>	<u>DESCRIPTION</u>
$\otimes$	DRY STANDPIPE RISER	ACV	ALARM CHECK VALVE
0	WET STANDPIPE RISER	AFF BFP	ABOVE FINISHED FLOOR BACKFLOW PREVENTER
		BOP	BOTTOM OF PIPE
0	DRAIN RISER	BV	BUTTERFLY VALVE
	ANGLE VALVE / FIRE HOSE VALVE (SIZE AS INDICATED)	CFM	CUBIC FEET PER MINUTE
	RECESSED CABINET (FEC), (FHC), (FHCC), (FHEC), OR (FHVC)	CL	CLEAN AGENT
		CLG	CEILING
	SEMI-RECESSED CABINET (FEC), (FHC), (FHCC), (FHEC), OR (FHVC)	COMP CO2	COMPRESSOR CARBON DIOXIDE
	SURFACE MUNTED CABINET (FEC), (FHC), (FHCC), (FHEC), OR (FHVC)	CV	CHECK VALVE
FS	WATER FLOW SWITCH	DL	DRY CHEMICAL
$\bowtie$	SYSTEM CONTROL VALVE (REFER TO SPECIFICATIONS FOR DESCRIPTION)	DIPS	DOUBLE INTERLOCKED PREACTION SYSTE
Ø T	PRESSURE GAUGE	DN	DOWN
•		DR DSP	DRAIN RISER DRY STANDPIPE
	CHECK VALVE	DS	DRY SPRINKLER SYSTEM
	CHECK VALVE WITH BALL DRIP	(E)	EXISTING
	DOUBLE CHECK VALVE BACKFLOW PREVENTER	(ER)	EXISTING TO BE RELOCATED
		FCP	FIRE ALARM CONTROL PANEL
	RPZ BACKFLOW PREVENTER	FD FDC	FLOOR DRAIN FIRE DEPARTMENT CONNECTION
raket	NON-RISING STEM VALVE (NON-INDICATING)	FDV	FIRE DEPARTMENT VALVE
$\stackrel{lack}{\swarrow}$	PRESSURE REGULATING VALVE	FDVC	FIRE DEPARTMENT VALVE CABINET
1	PRESSURE RELIEF VALVE	FE	FIRE EXTINGUISHER
<b>\tau</b>	PRESSURE RELIEF VALVE	FEC	FIRE EXTINGUISHER CABINET
<b>*</b>	PRESSURE DETECTOR	FH FP	FIRE HYDRANT FIRE PUMP
•		FPC	FIRE PUMP CONTROLLER
	ALARM CHECK VALVE	FS	FLOW SWITCH
$\bowtie$	DRY PIPE VALVE	GPM	GALLONS PER MINUTE
00	FLUSH MOUNTED (FDC) OR (WH)	GV	GATE VALVE
<u></u> →	SURFACE MOUNTED (FDC) OR (WH)	HC	HOSE CABINET
	, , , , , , , , , , , , , , , , , , ,	HP JP	HORSE POWER JOCKEY PUMP
	SIDEWALK MOUNTED FIRE DEPARTMENT CONNECTION OR TEST HEADER	JPC	JOCKEY PUMP CONTROLLER
<del>io</del> đ ∤∱∿	SURFACE MOUNTED ROOF HYDRANT RO TEST HEADER	MTD	MOUNTED
igt 🖍	ROOF MOUNTED HYDRANT	(N)	NEW
	OUTSIDE SCREW & YOKE VALVE	NC NIC	NORMALLY CLOSED
	COTSIDE SOILEW & TOKE WILVE	NIC NO	NOT IN CONTRACT NORMALLY OPEN
φ	YARD HYDRANT	NRS	NON-RISING STEM VALVE
PIV	POST INDICATOR VALVE	NTS	NOT TO SCALE
WPIV		OS & Y	OUTSIDE SCREW & YOKE VALVE
90	WALL POST INDICATOR VALVE	PIV	POST INDICATOR VALVE
Ø	PRESSURE RECORDER	PSI PSIG	POUNDS PER SQUARE INCH POUNDS PER SQUARE INCH GAUGE
	SPRINKLER VALVE (PLAN)	PR	PREACTION SPRINKLER SYSTEM
$\overset{\bullet}{\boxtimes}$	WET PIPE SPRINKLER VALVE (ELEVATION)	PS	PULL STATION
	· · · · ·	(ER)	EXISTING TO BE REMOVED
	DRY PIPE SPRINKLER VALVE (ELEVATION)	RPM	REVOLUTIONS PER MINUTE
	DELUGE SPRINKLER VALVE (ELEVATION)	SIPS SD	SINGLE INTERLOCKED PREACTION SYSTEM SMOKE DETECTOR
	PREACTION SPRINKLER DELUGE VALVE (ELEVATION)	SQFT	SQUARE FEET FOOT
	PREACTION CONTROL PANEL	SPKR	SPRINKLER
	THE ROTTON CONTINUE TABLE	SR	SPRINKLER RISER
<b>→</b> D	WATER MOTOR GONG	TH	TEST HEADER
$pprox \bigcirc$	ELECTRIC ALARM BELL	TS TYP	TAMPER SWITCH TYPICAL
$\boxtimes$	SPRINKLER WITH GUARD	UNO	UNLESS NOTED OTHERWISE
		WB	WATERFLOW BELL
ЮН	DRAIN AND TEST VALVES/FITTING	WF	WATER FLOW DETECTOR/SWITCH
<u> </u>	PIPE RISE	WH	WALL HYDRANT
<del></del>	PIPE DROP	WM	WATER MIST
<b>→</b>	CLEAN AGENT STORAGE CONTAINER	WSP WS	WATER STANDPIPE WET SPRINKLER SYSTEM
	OLD NA MOLINE OFFICIAL CONTINUEN	WT	WATER TANK
<del></del>	PIPE HANGER	ZV	SPRINKLER ZONE VALVE


## - EQUIPMENT DESIGNATION

------ SPRINKLER HEAD SCHEDULE



## SPRINKLER SYSTEM DESIGN CRITERIA -





----- GENERAL DEMOLITION NOTES -

— DRAWING LOG -

- 1. EXISTING WORK WHICH IS TO BE DEMOLISHED IS SHOWN DASHED. ALL OTHER WORK SHOWN ON THE DEMOLITION PLAN IS EXISTING TO REMAIN.
- 2. REMOVE EXISTING EQUIPMENT, FIXTURES AND PIPING TO THE EXTENT INDICATED, AND DISPOSE OF IT OFF-SITE IN A SAFE AND LEGAL MANNER WHERE SUCH WORK IS INDICATED TO BE "DEMOLISHED."
- 3. THE PURPOSE OF DEMOLITION DRAWINGS IS TO INDICATE THE SCOPE OF THE DEMOLITION WORK TO PERMIT THE INSTALLATION OF NEW WORK INDICATED ON SUBSEQUENT PLANS. COORDINATE ACTUAL DEMOLITION WORK WITH BOTH THE NEW WORK INDICATED AND THE ACTUAL FIELD CONDITIONS ENCOUNTERED.
- 4. ANY SHUTDOWNS OF EXISTING MECHANICAL SYSTEMS SHALL BE BRIEF AND OCCUR WHEN USAGE IS NONEXISTENT OR VERY LIGHT, OR METHODS SHALL BE EMPLOYED WHICH PERMIT SYSTEMS TO STAY IN OPERATION AVOIDING SHUTDOWNS ALTOGETHER. THE OWNER SHALL DETERMINE WHEN AND IF AN EXISTING MECHANICAL SYSTEM MAY BE SHUT DOWN.
- 5. ALL EQUIPMENT INDICATED TO BE DEMOLISHED SHALL FIRST BE OFFERED TO THE OWNER FOR HIS RETENTION. THE SCOPE OF DEMOLITION WORK, HOWEVER, SHALL INCLUDE THE DISPOSAL OF ALL DEMOLISHED EQUIPMENT OFF—SITE IN A SAFE AND LEGAL MANNER, REGARDLESS OF WHETHER THE OWNER EVENTUALLY DECIDES TO RETAIN ANY EQUIPMENT.
- 6. PIPING WHICH SERVES OTHER AREAS, ENTERING AND PASSING THROUGH THE AREA WHERE DEMOLITION WORK IS INDICATED, SHALL REMAIN.
- 7. CAP ANY EQUIPMENT, DUCTWORK OR PIPING ABANDONED IN PLACE AIR/WATER TIGHT. UNLESS NOTED OTHERWISE,
- 8. PIPING INDICATED TO BE DEMOLISHED SHALL BE DEMOLISHED BACK TO THE NEAREST ACTIVE MAIN. THE MAIN, OR OTHER TERMINATION POINT, SHALL BE CAPPED AIR/WATER TIGHT. PIPING WITHIN WALLS, WHICH IS TO REMAIN WITHIN THE WALLS, SHALL BE CAPPED FAR ENOUGH INSIDE THE WALL TO ALLOW FOR PATCHING AND FINISHING OF THE WALL.
- 9. WHERE EXISTING CEILINGS REMAIN, CAREFULLY REMOVE AND REINSTALL EXISTING CEILING TILES, AS REQUIRED, IN ORDER TO GAIN ACCESS TO DEMOLITION WORK.
- 10. REFER TO AND COORDINATE FIRE PROTECTION DEMOLITION WORK WITH THAT OF OTHER DISCIPLINES AS SHOWN ON ARCHITECTURAL, MECHANICAL, PLUMBING AND ELECTRICAL.
- 11. IF ANY MATERIAL IS UNCOVERED WHICH THE CONTRACTOR, SUBCONTRACTOR OR TRADESMAN SUSPECTS TO BE ASBESTOS, THEN WORK IN THE AREA SHALL CEASE UNTIL THE OWNER'S REPRESENTATIVE IS CONTACTED FOR A DETERMINATION OF WHETHER THE MATERIAL IS SAFE, SHOULD BE TESTED, OR SHOULD BE REMOVED.
- 12. CAP THE OPEN END OF EXISTING TO REMAIN PIPING AND EQUIPMENT IMMEDIATELY AFTER OPENING PIPE/EQUIPMENT CONNECTIONS TO PREVENT DEBRIS FROM CONTAMINATING EXISITING TO REMAIN ITEMS.
- 13. ALL EXISTING PIPING THAT IS TO BE REMOVED SHALL BE CAPPED OR PLUGGED BACK AT MAIN. REMOVED ALL UNUSED PIPING, LEAVING NO DEAD LEGS.

## ---- GENERAL NOTES -

- 1. NOT ALL SYMBOLS AND ABBREVIATIONS ARE NECESSARILY USED ON THIS PROJECT.
- 2. ENTIRE AREA SHALL BE PROVIDED WITH HYDRAULICALLY CALCULATED WET PIPE AUTOMATIC SPRINKLERS IN ACCORDANCE WITH ALL APPLICABLE CODES, STANDARDS, AND REGULATIONS LISTED: NFPA 13, 14, 20, 24, 25, 70, 72, AND 101, INTERNATIONAL BUILDING CODE, INTERNATIONAL FIRE PREVENTION CODE, AND OWNER'S INSURANCE CARRIER.
- 3. WATER FOR THE SPRINKLERS SHALL BE SUPPLIED FROM WET STANDPIPES OR FROM HORIZONTAL FIRE PROTECTION MAIN AS INDICATED ON DRAWINGS.
- 4. SPRINKLER CONTROL VALVES WITH SUPERVISION, FLOW SWITCH, AND DRAIN AND TEST ASSEMBLY TO BE PROVIDED AT EACH LEVEL AT EACH SPRINKLER ZONE.
- 5. SAFETY MARGIN OF AT LEAST 10 PSI SHALL BE INCLUDED IN HYDRAULIC CALCULATION FOR ALL ZONES. WATER
- VELOCITY IN PIPING SHALL NOT EXCEED 20 FEET PER SECOND.

  6. ALL SPRINKLERS INSTALLED IN AREAS WITH SUSPENDED CEILINGS SHALL BE LOCATED ON THE CENTER LINE OF THE
- TILE AND NOT LESS THAN 12" FROM EDGE OF THE CEILING TILE.

  7. SPRINKLERS OR SPRINKLER PIPING INSTALLED IN ELECTRICAL EQUIPMENT ROOMS SHALL NOT BE LOCATED DIRECTLY
- OVER SWITCHGEAR, ELECTRICAL CONTROL PANELS, OR OTHER ELECTRICAL EQUIPMENT.

  8. LOCATION OF SPRINKLERS AND SPRINKLER LINES AND HEADS SHOWN ON FIRE PROTECTION PLANS ARE APPROXIMATE.
- 9. SPRINKLER PIPING SHALL NOT PASS THROUGH ELECTRICAL ROOMS OR CLOSETS, COMMUNICATIONS CENTERS, ELEVATOR HOISTWAYS OR ELEVATOR MACHINE ROOMS OR STAIRS TO SERVE OTHER AREAS.
- 10. CONTRACTOR SHALL INSTALL SPRINKLERS IN STAIRS AT EACH FLOOR LANDING AND AT TOP OF STAIRS. IF STAIRS ARE OPEN AT THE LOWER LEVEL SPRINKLERS SHALL BE INSTALLED BELOW LOWEST LANDING.
- 11. INSPECTOR TEST CONNECTIONS THAT DISCHARGE OUTSIDE OF THE BUILDING SHALL NOT DISCHARGE IN AN EGRESS LOCATION. OUTSIDE DISCHARGE DRAIN SHALL DRAIN TO A SPLASH BLOCK IN AN AREA APPROVED BY ARCHITECT AND ENGINEER. THIS CONTRACTOR SHALL COORDINATE LOCATION WITH ARCHITECT AND ENGINEER.
- 12. ALL SPRINKLER DEVICES AND APPURTENANCES SHALL BE FM APPROVED AND UL LISTED.
- 13. ALL PIPING, FITTINGS AND HANGING MATERIALS SHALL BE IN ACCORDANCE WITH NFPA 13.
- 14. SPRINKLER HEADS LOCATED FOR REFERENCE ONLY. PROVIDE ALL REQUIRED HEADS PER NFPA 13.

CONTRACTOR TO COORDINATE LOCATION OF LINES WITH THE WORK OF ALL OTHER TRADES.

- 15. SPRINKLER HEADS AND PIPING SIZES ARE SHOWN FOR PRICING AND CLARITY. FIRE PROTECTION CONTRACTOR IS RESPONSIBLE FOR HYDRAULIC CALCULATIONS OF ENTIRE ZONE WITHIN WORK AREA. HEADS, LOCATIONS AND SIZES WILL BE BASED ON HYDRAULIC CALCULATIONS.
- 16. REFER TO HVAC MECHANICAL DRAWINGS FOR LAYOUT OF DUCTWORK FOR SPRINKLER COVERAGE UNDER DUCTWORK AS REQUIRED BY CODE.
- 17. WHERE HEAD LOCATIONS ARE NOT INDICATED, PROVIDE COORDINATED LAYOUT WITH ARCHITECTURAL CEILING PLAN AND OTHER TRADES. WHERE HEAD LOCATIONS ARE INDICATED, PROVIDE AT SHOWN LOCATIONS AS A MINIMUM. IF ADDITIONAL HEADS ARE REQUIRED TO CONFORM WITH THE AUTHORITY HAVING JURISDICTION OR CODES, COORDINATE BEFORE SHOP DRAWING SUBMITTALS.
- 18. SHOP DRAWINGS: CONTRACTORS SHALL PROVIDE SHOP DRAWINGS FOR ALL SPECIFIED EQUIPMENT. CONTRACTOR SHALL PROVIDE COORDINATED SHOP DRAWINGS FOR PIPING AND SHEETMETAL, SHOWING COORDINATION WITH OTHER DISCIPLINES. NO EQUIPMENT, PIPING OR DUCTWORK SHALL BE INSTALLED WITHOUT AN APPROVED SHOP DRAWING. WORK OR EQUIPMENT INSTALLED WITHOUT ENGINEER'S APPROVAL WILL BE SUBJECT TO REMOVAL AND REWORK PER THE ENGINEERS SOLE DISCRETION REGARDLESS OF DESIGN DOCUMENTS. ALL COST WILL BE THE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR SHALL ALLOW TEN (10) BUSINESS DAYS FOR ENGINEERS REVIEW. ALL WORK SHALL BE INSTALLED PER THE APPROVED SHOP DRAWING. FIELD MODIFICATIONS TO THE APPROVED SHOP DRAWING SHALL BE SUBMITTED FOR ENGINEER APPROVAL PRIOR TO INSTALLATION.

Restorix Healt

DENNIS NOSKIN A





IOHN ZABILOWICZ, P.E.
ROFESSIONAL ENGINEER
LICENSE NO.: 13662

AINE MEDICAL CENTER
BRIGHTON CAMPUS
WOUND CARE AND
YPERBARIC MEDICINE
335 BRIGHTON AVENUE
PORTLAND, ME 04103

KEY PLAN: GROUND FLOOR

ISSUE DATES:	ISSUE DATES:				
✓ JANUARY 2	26, 2015				
	ROVALS				
✓ MARCH 20	, 2015				
BLDG. DEF	PT. REVIEW				
$\wedge$					
$\wedge$					
$\wedge$	$\land$				
DDAWN DV.	FOLL				
DRAWN BY:	ECH				
CHECKED BY:	BF				
OFFICINED DT.	ы				
SCALE:	AS NOTED				
PROJECT NO.:	P14110				

SHEET TITLE:

FIRE PROTECTION

COVER SHEET

FP-0