

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that
MMC REALTY CORP

Located at
335 Brighton Ave

PERMIT ID: 2015-00310 **ISSUE DATE:** 04/10/2015 **CBL:** 121 C009011

has permission to **Alterations of existing ground floor medical space, reconfiguration of interior walls and ceilings, cut slab-on-grade for new plumbing locations, new equipment** provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ David Petruccelli

/s/ Jeanie Bourke

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Hospital and medical offices

Building Inspections

Use Group: I-2 **Type:** 1B
Institutional - Hospital
Occupant Load this suite only = 19
NFPA 13 Sprinkler System
Ground (Hyperbaric Suite)
MUBEC/IBC 2009

Fire Department

Classification:
Health Care
ENTIRE

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Close-in Plumbing/Framing w/Fire & Draft Stopping

Electrical Close-in w/Fire & Draftstopping

Above Ceiling Inspection

Final - Commercial

Final - Electric

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2015-00310	Date Applied For: 02/23/2015	CBL: 121 C009011
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: Maine Medical Center - Brighton Campus Ground Floor RestorixHealth - Wound Treatment (Hyperbaric Suite)		Proposed Project Description: Alterations of existing ground floor medical space, reconfiguration of interior walls and ceilings, cut slab-on-grade for new plumbing locations, new equipment		
Dept: Zoning	Status: Approved	Reviewer: Tammy Munson	Approval Date: 03/11/2015	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
Dept: Building Inspecti	Status: Approved w/Conditions	Reviewer: Jeanie Bourke	Approval Date: 03/27/2015	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				
2) Penetrations through fire resistance rated assemblies shall be protected by an approved penetration firestop system installed as tested in accordance with ASTM E814 or UL 1479				
3) Equipment shall be installed in compliance with the manufacturer's specifications and the UL listing.				
4) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				
Dept: Engineering DPS	Status: Not Applicable	Reviewer:	Approval Date: 03/05/2015	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) This approval is non-applicable to Engineering DPS as it relates to approval for Grease Control Equipment for the Fats, Oil, and Grease Program. If approval is needed for this project by the Engineering Department of Public Services for any other reason than FOG, please contact David Margolis-Pineo at 207-874-8850 or dmp@portlandmaine.gov				
Dept: Fire	Status: Approved w/Conditions	Reviewer: David Petruccelli	Approval Date: 04/10/2015	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) Fire walls, fire barriers, fire partitions, smoke barriers and smoke partitions or any other wall required to have protected openings or penetrations shall be effectively and permanently identified with signs or stenciling in accessible concealed floor, floor-ceiling or attic spaces at intervals not exceeding 30 feet with lettering not less than 0.5 inches in height.				
2) Application requires State Fire Marshal approval.				
3) Street addresses shall be marked on the structure and shall be as approved by the City E-911 Addressing Officer.				
4) A separate Fire Alarm Permit is required for new systems; or for work effecting more than 5 fire alarm devices; or replacement of a fire alarm panel with a different model. This review does not include approval of fire alarm system design or installation.				
5) Compliance with NFPA 1, Fire Code, Annex O for In-building Public Safety Radio Enhancement Systems shall be verified by an RF Engineer.				
6) A separate Suppression System Permit is required for all new suppression systems, including standpipe systems, and for sprinkler work effecting more than 20 heads. This review does not include approval of system design or installation.				
7) Fire department connection type and location shall be approved in writing by Fire Prevention Bureau.				
8) A firefighter Building Marking Sign is required.				
9) Fire extinguishers are required per NFPA 1.				

PERMIT ID: 2015-00310

Located at: 335 Brighton Ave

CBL: 121 C009011

- 10 All means of egress to remain accessible at all times.
- 11 Construction or installation shall comply with City Code Chapter 10.
- 12 Any cutting and welding done will require a Hot Work Permit from Fire Department.
- 13 Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.
- 14 Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.
- 15 **The fire alarm system design shall be evaluated for the renovated areas by an NICET IV certified interior fire alarm designer or a licensed engineer for compliance with the code. A compliance letter is required prior to the final inspection.**
A current inspection sticker from an approved fire alarm inspection company is required prior to the final inspection.
- 16 The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.
- 17 Installation and operations shall comply with NFPA 99 Ch. 20 Hyperbaric Facilities
- 18 Emergency lights and exit signs are required. Emergency lights and exit signs are required to be labeled in relation to the panel and circuit and on the same circuit as the lighting for the area they serve.