

ARCHITECTURAL EQUIPMENT PLAN

ATTENTION:


CASEWORK & ACCESSORY NOTES

ALL CASEWORK IS EITHER EXISTING OR IS TO BE DESIGNED, DETAILED, FURNISHED AND INSTALLED BY THE CUSTOMER AND/OR CONTRACTOR. FOLLOW DESIGN RECOMMENDATIONS INCLUDED HEREWITH, AS THEY ARE ESSENTIAL FOR THE SUCCESSFUL INSTALLATION & OPERATION OF THE SIEMENS EQUIPMENT. THE SOUND SYSTEM AND INTERCOM BETWEEN THE EXAMINATION AND CONTROL ROOMS ARE TO BE LOCATED, FURNISHED AND INSTALLED BY THE CUSTOMER/CONTRACTOR. ALL FURNITURE (CHAIRS, ETC.) FOR THE CONTROL ROOM ARE TO BE PROVIDED BY THE CUSTOMER.

STATE AGENCY REVIEW

PRIOR TO SIEMENS EQUIPMENT INSTALLATION, APPROVAL OF CONSTRUCTION OR STRUCTURAL MODIFICATIONS UTILIZING X-RAY FOR DIAGNOSTIC OR THERAPEUTIC PURPOSES, MUST BE OBTAINED BY THE CUSTOMER FROM THE APPROPRIATE STATE AGENCY, IF APPLICABLE.

- THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.



SCALE: 1/4" = 1'-0

OPERATION OF THE WIRELESS DETECTOR CAN BE AFFECTED BY OTHER WLAN DEVICES IN THE VICINITY OF THIS INSTALLATION. TO AVOID ANY CONFLICTS, THE CUSTOMER MUST PROVIDE A LIST OF EXISTING WLAN CHANNELS (FREQUENCIES) OR THE SPECIFIC CHANNEL (FREQUENCY) THEY DESIRÈ TO BE USED FOR THE WIRELESS DETECTOR.

WIRELESS DETECTOR CONNECTION

THE WIRELESS CONNECTION IS ENCRYPTED (WPA2) AND IS BASED ON TWO WLAN STANDARDS, WITHIN WHICH SEVERAL CHANNELS (FREQUENCIES) ARE AVAILABLE:

1) 11G STANDARD - OPERATES AT 2.5 GHz 2) 11A STANDARD - OPERATES AT 5 AND 6 GHz

CUSTOMER'S NETWORK.

THE STANDARD (11G OR 11A) CAN BE SET BY SIEMENS SERVICE VIA THE SERVICE SOFTWARE INSTÁLLED ON THE IMAGING SYSTEM. THE WIRELESS CONNECTION IS ONLY USED TO TRANSFER DATA BETWEEN SIEMENS EQUIPMENT AND IS NOT USED TO SEND DATA TO THE

REV 0

SITE READINESS GUIDELINES

THE FOLLOWING GENERAL CONDITIONS ARE NECESSARY TO HAVE THE STATUS OF "READY SITE":

- PROPER POWER AVAILABLE AT SIEMENS EQUIPMENT POWER CABINET LOCATION AND ALL POWER OUTLETS FUNCTIONING. AIR CONDITIONING/HUMIDIFICATION SYSTEMS COMPLETE, TESTED, AND
- FUNCTIONING PROPERLY ACCORDING TO SIEMENS SPECIFICATIONS. PROPER LIGHTING INSTALLED AND FUNCTIONING.
- PLUMBING COMPLETE EXCEPT FOR ANY FINAL CONNECTIONS TO SIEMENS EQUIPMENT. ALL CABLE TRAYS/DUCTS/CONDUITS CORRECTLY SIZED, LOCATED,
- AND INSTALLED ACCORDING TO THE SIEMENS DRAWINGS.
- ALL REINFORCEMENT PLATES/UNISTRUT INSTALLED AS REQUIRED. ROOM FOR EQUIPMENT INSTALLATION AND IMMEDIATE VICINITY IS DUST-FREE AND IS TO REMAIN SO FOR THE DURATION OF THE
- INSTALLATION. A SECURE AREA (APPROXIMATELY 10' x 10') IS AVAILABLE AT EQUIPMENT DELIVERY FOR PARTS AND INSTALLATION TOOLS.
- CUSTOMER APPROVAL FOR SIEMENS REMOTE SERVICES (SRS) CONNECTION, AND CUSTOMER'S I.T. CONTACT INFORMATION AND
- O) WALLS TO BE PRIMED AND PAINTED, FLOORS TO BE TILED EXCEPT IN AREAS OF THE EQUIPMENT BASE PLATES.

IP ADDRESSES ESTABLISHED.

THESE CONDITIONS ARE NOT MET, THE SIEMENS PROJECT MANAGER AND THE DESIGNATED SIEMENS INSTALLATION SUPERVISOR SHALL RESCHEDULE THE INSTALLATION START DATE. NOTE: ADDITIONAL COST MAY BE INCURRED BY THE CUSTOMER/CONTRACTOR AND DELIVERY DATES MAY NEED TO BE RESCHEDULED, WHEN THE SIEMENS SITE READINESS GUIDELINES ARE NOT MET.

EQUIPMENT LEGEND DESCRIPTION SMS | WEIGHT | BTU/HR | DIMENSIONS (INCHES) REMARKS (LBS) TO AIR 1) | CONTROL ROOM MODULE 4 3/4 10 1/16 3 3/16 ON CUSTOMER'S COUNTER) | IMAGING SYSTEM - KEYBOARD AND MOUSE ON CUSTOMER'S COUNTER 3) | CONTROL ROOM MONITOR (LIVE IMAGE) ON CUSTOMER'S COUNTER 17 3/8* | 32 1/2* 110 1,468 (4) | IMAGING SYSTEM (UNDER COUNTER) *INCLUDES 5 1/8" BEHIND, 4" ABOVE AND ALONG CONTAINER. 5) | POLYDOROS F80 (80 kW) GENERATOR CABINET 838 2,048** 17 1/8 | 86 3/4 | **DURING OPERATION, 1,195 31 1/2 IN STANDBY MODE ***DURING OPERATION, 512 3,793 2,900*** (6) | LUMINOS AGILE (+90/-20) TABLE 83 IN STANDBY MODE 7) DCS-1 IC-DVI FLAT DISPLAY & TOUCH DISPLAY ON 167 1/8 | 27 7/8 419 512 *A - 63"MIN. AND 102" CEILING SUSPENSION (8) YSIO MAX WALL STAND WITH MOBILE DETECTOR (LEFT 551 819 37*A │ *A − MAX. IN HORIZONTAL LOADING) (9) ACCESS POINT (TOP OF GENERATOR) 5 1/2*A *A 12 1/4, *B 9" INCLUDING ANTENNAE 3 1/2 | SIZE AND WEIGHT PER RAIL 0) | CEILING RAILS FOR FULLY SYNCHRONIZED TUBE STAND 59 167 3/8 4M TRANSVERSE BRIDGE AND X-RAY TUBE STAND 816 853 172 1/2 6 7/16 | 21 11/16 | SUGGESTED LOCATION) | GRID HOLDER FOR AGILE (WALL MOUNTED) 25 1/16 34 13/16 79 1/4 | FOR ORTHO OPTION) | ORTHO SUPPORT (FOR ORTHO OPTION) 29 1/2 14) DVD FOR FLUORO RECORDING INSIDE FL-C CONTAINER CHARGING STATION FOR MAX DETECTORS 12 1/2 6 3/4 2 ON CUSTOMER'S COUNTER 4 EATON UPS 5P 850G FOR IMAGING SYSTEM ONLY 135 13 5/8 9 1/4 LOCATED WITH CONTROL 22 EQUIPMENT

CEILING STAND TECHNICAL DATA

TRANSPORTING INFORMATION

		SIZE	WEIGHT	
TRANSVERSE BRIDGE	3 M	126"L x 32"W x 10"H	419#	
TRANSVERSE BRIDGE	4 M	174"L x 32"W x 10"H	512#	
LONGITUDINAL RAILS	4 M	167"L x 3"W x 4"H	59# EACH	
ECHOHODINAL TAILS	5 M	197"L x 3"W x 4"H	82# EACH	
DCS-1/2 4 M		167"L x 3"W x 3"H	441#	
X-RAY TUBE STAND (FULLY SYNCHRONIZED)	67"L x 41"W x 53"H	827#		
WALL STAND WITH MOBILE DETE (WITH PACKING)	35"L x 93"W x 41"H	898#		
MINIMUM DOOR OPENING:		3'-5 3/8"		
MINIMUM CORRIDOR WIDTH:		6'-11"		


ENVIRONMENTAL CONDITIONS

ENVIRONMENTAL CONDITIONS			
	IN OPERATION	TRANSPORT	
PERMISSIBLE AMBIENT TEMPERATURE (WITH WIRELESS DETECTOR)	59°F TO 82°F	-4°F TO 131°F	
PERMISSIBLE RELATIVE HUMIDITY	20% TO 75%	5% TO 95% REV 3	

SIEMENS REMOTE SERVICE

TO ENSURE THE UPTIME OF YOUR SYSTEM DURING THE WARRANTY PERIOD (AND BEYOND WITH A SERVICE AGREEMENT), SIEMENS REMOTE SERVICES (SRS) REQUIRES REMOTE LOCAL AREA NETWORK ACCESS TO SIEMENS SYSTEMS.

THE PREFERRED CONNECTION METHOD IS (VPN) VIRTUAL PRIVATE NETWORK (WHERE THE CUSTOMER HAS AVAILABLE A VPN CAPABLE FIREWALL OR OTHER VPN APPLIANCE). THIS METHOD PROVIDES THE POSSIBILITY FOR REMOTE SYSTEM DIÁGNOSTICS WITHOUT ADDITIONAL HARDWARE. PLEASE CONTACT SIEMENS REMOTE SERVICES (800-888-SIEM) TO DETERMINE IF THIS METHOD IS SUITABLE FOR



Project Milestones To Be Completed Before Equipment Delivery	Reference Sheet	Date Completed	Date Reviewed	
Storage area available for storing items during installation	A-101			
Lead shielding (walls, doors, windows) complete	A-101			
Climate control functioning 24 hours a day, 7 days a week	A-101			
Delivery path verified	A-101			
Casework complete in exam and control rooms	A-101			
Room lighting complete and functioning	A-101			
Network drop active and IP addresses obtained for Siemens Remote Services (SRS)	A-102			
Nothing hanging below ceiling in area shaded on drawing.	A-102			
Floor levelness verified and within specifications	S-101			
Floor thickness verified and within specifications If not, approved Alt. Anchor Solution available	S-101			
All conduits, troughs, and core drills are outside of table or wallstand anchor locations	S-101			
Any in-floor pull boxes outside of table or wallstand anchor locations	S-101			
Ceiling/Unistrut height verified (check minimum ceiling height)	S-102			
Correct number of unistrut installed in correct location.	S-102			
Cable runs checked to ensure maximum length not exceeded	E-101			
X-Ray warning light and wiring installed	E-101			
Breakers installed	E-102			
Contractor supplied electrical cabling / pigtails installed	E-102			
EPO's installed and functioning	E-102			
Cable inlets installed in locations per plans	E-102			

ARCHITECTURAL NOTES

) ALL PRELIMINARY EQUIPMENT LAYOUTS SUBMITTED BY SIEMENS HEALTHCARE ARE BASED ON THE RECOMMENDED SPACE NECESSARY FOR THE OPERATION AND SERVICEABILITY OF THE EQUIPMENT BEING PROPOSED. SIEMENS WILL NOT SUBMIT AN EQUIPMENT LAYOUT THAT IS NOT IN THE BEST INTEREST OF BOTH THE CUSTOMER AND SIEMENS. ALL EQUIPMENT LAYOUTS ARE BASED EITHER ON AN ACTUAL SITE SURVEY OR ARCHITECTURAL DRAWINGS SUPPLIED TO SIEMENS. SIEMENS WILL NOT BE RESPONSIBLE FOR ANY ALTERATIONS THAT ENCROACH WITHIN DESIGNATED SAFETY AND SERVICE CLEARANCE ZONES AS INDICATED ON DRAWINGS (I.E., PIPE CHASES, VENTILATION DUCTS, CASEWORK, AND SOFFITS, ETC.) MADE BY THE CUSTOMER OR REQUIRED BY A CUSTOMER'S ARCHITECTURAL FIRM ONCE PRELIMINARY DRAWINGS HAVE BEEN SUBMITTED AND APPROVED. DO NOT ALTER ANY SPECIFICATIONS AND/OR DIMENSIONS WITHOUT CONTACTING AND RECEIVING WRITTEN CONFIRMATION FROM SIEMENS PROJECT MANAGER. 2) SIEMENS HEALTHCARE IS NOT AN ARCHITECTURAL OR ENGINEERING FIRM. DRAWINGS SUPPLIED BY SIEMENS ARE NOT CONSTRUCTION DRAWINGS. THEREFORE, THESE DRAWINGS ARE TO BE USED ONLY FOR INFORMATION TO COMPLEMENT ACTUAL CONSTRUCTION DRAWINGS AVAILABLE FROM A CUSTOMER APPOINTED ARCHITECTURAL REPRESENTATIVE OR A CUSTOMER'S ENGINEERING DESIGN GROUP. THE CUSTOMER'S ARCHITECT AND GENERAL CONTRACTOR SHALL BE ULTIMATELY RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE CODES AND PROFESSIONAL DESIGN REQUIREMENTS INCLUDING OSHA/NEC SAFETY CLEARANCE REQUIRMENTS IN ADDITION TO SIEMENS-REQUIRED SAFETY/SERVICE CLEARANCES SHOWN.

3) THE CUSTOMER IS RESPONSIBLE FOR ALL ROOM AND AREA PREPARATION COSTS, PROFESSIONAL FEES, PERMITS, REPORTS, AND INSPECTION FEES.

4) EQUIPMENT WARRANTIES, EXPRESSED OR IMPLIED ON THE PART OF SIEMENS SHALL BE CONTINGENT UPON STRICT COMPLIANCE WITH THE ARCHITECTURAL, STRUCTURAL, ELECTRICAL, MECHANICAL AND RECOMMENDATIONS AND REQUIREMENTS CONTAINED IN THESE DRAWINGS, UNLESS SPECIFIED OTHERWISE.

5) ALL DIMENSIONS SHOWN ARE FROM FINISHED SURFACES UNLESS SPECIFIED OTHERWISE. 6) THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING

IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST. ACTUAL PROTECTION REQUIREMENTS SHALL BE SPECIFIED BY A REGISTERED RADIATION PHYSICIST AT CUSTOMER'S ENGAGEMENT AND EXPENSE. RESPONSIBILITY FOR ALL INFORMATION AS TO THE ROOM LOCATION, USE, AND NUMBER OF ANTICIPATED EXAMINATIONS TO BE PERFORMED PER TIME PERIOD SHALL BE PROVIDED TO THE PHYSICIST BY THE CUSTOMER. THE CUSTOMER SHALL FURTHER TAKE ALL RESPONSIBILITY IN THE COMMUNICATION AND COORDINATION OF ACTIVITIES OF THE RADIATION PHYSICIST AND THE ARCHITECTURAL REPRESENTATIVE.

REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER

7) SIEMENS HEALTHCARE SHALL BE RESPONSIBLE FOR SIEMENS EQUIPMENT INSTALLATION, CALIBRATION, CONNECTION AND INSTALLATION OF SIEMENS PROVIDED CABLES. THE CUSTOMER/ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR TERMINATIONS OF CUSTOMER/ELECTRICAL CONTRACTOR-SUPPLIED CABLES TO SIEMENS EQUIPMENT. IN THE EVENT THAT SPECIFIC TRADE RULES OR LICENSE REQUIREMENTS PROHIBIT THIS. THE CUSTOMER SHALL INITIATE THE SERVICES OF APPROVED OTHER CONTRACTORS AND PAY FOR SELECTED, APPROVED PARTIES TO PERFORM THIS WORK WITH SUPERVISION PROVIDED BY SIEMENS. CALIBRATION WHEN ACCOMPLISHED OUTSIDE OF NORMAL INSTALLATION SEQUENCES DUE TO CONTRACTOR OR TRADE RULE ACTIONS OR REQUIREMENTS SHALL BE SUPPORTED BY, CHARGED TO, AND ACCEPTED BY THE CUSTOMER AS AN ADDITIONAL INSTALLATION EXPENSE.

8) THE CUSTOMER SHALL COORDINATE WITH SIEMENS PROJECT MANAGER THE LOCATIONS AND TRAVEL OF ALL ANCILLARY EQUIPMENT TO BE CEILING OR WALL MOUNTED (I.E.: O.R. LIGHTS, MEDICAL GAS COLUMNS, PHYSIOLOGICAL MONITORING INJECTORS, CRT PLATFORMS, SPRINKLER HEADS, SMOKE DETECTORS, ELECTRICAL OUTLETS, HVAC GRILLES, SPEAKERS, AND GENERAL ROOM LIGHTING, ETC.).

9) THE GENERAL CONTRACTOR/CUSTOMER SHALL BE RESPONSIBLE FOR ALL FINAL PAINT, TOUCH-UP AND ANY COSMETIC OR TRIM WORK WHICH NEEDS TO BE OR IS REQUIRED TO BE COMPLETED AFTER THE INSTALLATION OF THE SIEMENS EQUIPMENT AND ANY ASSOCIATED SUPPORT APPARATUS.

TABLE TECHNICAL DATA

ENVIRONMENT:	59°F - 95°F OPERATING ROOM TEMPERATURE (NOTE: MAXIMUM 82°F WITH WIRELESS DETECTOR) 20% - 75% PERMISSIBLE RELATIVE AIR HUMIDITY (NON-CONDENSING)			
TRANSPORTING/ RIGGING:	UNIT BASE WEIGHT: 1,901 LBS. WITH PACKING 1,610 LBS. WITHOUT PACKING (WITH TRANSPORT CARRIAGE) DIMENSIONS WITH PACKING: 53"L X 36"W X 67"H			
	UNIT SUPPORT WEIGHT: 2,095 LBS. WITH PACKING 1,517 LBS. WITHOUT PACKING (WITH TRANSPORT CARRIAGE) DIMENSIONS WITH PACKING: 97"L X 52"W X 56"H DIMENSIONS WITHOUT PACKING (WITH TRANSPORT CARRIAGE): 116"L X 32"W X 60"H (WHEELS OUTSIDE) 95"L X 32"W X 60"H (ALL WHEELS INSIDE) 107"L X 32"W X 60"H (TWO WHEELS INSIDE) MINIMUM DOOR OPENING FOR TRANSPORT CARRIAGE: 34"W WITH MINIMUM 8'-3" CORRIDOR WIDTH			

RESOURCE LIS	ST (SMS	USE ONL	(Y)
DESIGNATION	F	G NUMBER	DATE
LUMINOS AGILE	XPD1-32	20.891.01.XX.02	
LUMINOS AGILE MAX	XPD1-32	25.891.01.XX.02	

48"W WITH MINIMUM 6'-1" CORRIDOR WIDTH

LUMINOS AGIL

CEILING	RECOMMENDED		PROJECT MANAGER: RICH DEISTER TEL: (207) 712-3205 VMAII: FXT:
HEIGHT WITHOUT	CEILING HEIGHT		VMAIL: EXT: FAX: (207) 929-3776 EMAIL: RICH.DEISTER@SIEMENS.COM
RESTRICTION	¬ —		BRIGHT
SEE RM HT REQMTS	9'-6"		

SIEMENS HON MEDICAL CENTER 335 BRIGHTON AVE., PORTLAND, ME 04102

FLUORO ROOM - LUMINOS AGILE MAX THE USE OR REPRODUCTION OF PROJECT #: THIS TITLE BLOCK WITHOUT

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.

- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES. THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

MINIMUM

CEILING

HEIGHT

W/RESTRICTION

SEE RM HT REQMTS

DESCRIPTION -ISSUE BLOCK-

R-101 VERSION A; DATED 04/07

APPROVED BY CUSTOMER FOR FINALS

RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW. ALL RIGHTS ARE RESERVED. CALE: AS NOTED REF. #: 1—FFKJUW.

SIEMENS AUTHORIZATION WILL

1601355 D. CAPSTICK 10/21/16