



**LINE LEGEND:**  
 - - - - - EXISTING TO REMAIN  
 - - - - - EXISTING TO BE REMOVED

**DEMOLITION NOTES:**

- ALL DEVICES SHOWN ARE EXISTING TO BE REMOVED, UNLESS OTHERWISE INDICATED. SEE LINE LEGEND ABOVE.
- FOR GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS SEE DRAWING E-0.
- THE WORK HEREIN CONSISTS OF PROVIDING EQUIPMENT, MATERIALS, LABOR AND SERVICES, AND PERFORMING OPERATIONS REQUIRED TO DEMOLISH EXISTING ELECTRICAL SYSTEMS SERVING SPACES TO BE RENOVATED. REMOVALS SHOWN ON THE DRAWINGS GIVE GENERAL INDICATION ONLY, AND MAY NOT INDICATE FULL EXTENT OF REMOVALS WHICH ARE REQUIRED TO COMPLETE THE WORK. ALL REMOVALS SHALL INCLUDE REMOVAL OF ALL WIRING AND RACEWAYS BACK TO THE SOURCE.
- INCLUDED HEREAFTER, EVEN THOUGH NOT SPECIFICALLY DETAILED OR DESCRIBED, IS THE PROVIDING OF EQUIPMENT, LABOR AND SERVICES TO ENABLE CONTINUED FUNCTIONING OF SERVICES PASSING THROUGH, OR ORIGINATING IN, THIS PROJECT AREA, BUT SERVING AREAS OUTSIDE THE PROJECT AREA WHICH ARE TO REMAIN IN OPERATION.
- DEMOLITION WORK SHALL BE SUBJECT TO DIRECTION AND APPROVAL OF THE OWNER OR THE OWNER'S REPRESENTATIVE, AND SHALL NOT INTERFERE WITH ACTIVITIES IN OTHER BUILDING AREAS. REMOVED MATERIALS, UNLESS OTHERWISE SPECIFICALLY DESIGNATED, SHALL BE PROMPTLY REMOVED. SHUTDOWNS OR SERVICE INTERRUPTIONS REQUIRED SHALL BE COORDINATED WITH AND APPROVED BY THE OWNER BEFORE THEY ARE IMPLEMENTED. A MINIMUM OF TWO (2) WEEKS ADVANCE NOTICE MUST BE PROVIDED TO THE OWNER.
- COORDINATE ELECTRICAL DEMOLITION WORK WITH OTHER DISCIPLINES.
- ANY BRANCH CIRCUIT PASSING THROUGH OR TERMINATING WITHIN THE RENOVATED AREA REQUIRING POWER AFTER DEMOLITION SHALL BE POWERED FROM EXISTING PANELS, AS DIRECTED BY OWNERS REPRESENTATIVE AT NO ADDITIONAL COST. IF A SERVICE PASSES THROUGH VERTICALLY FROM FLOOR-TO-FLOOR INSIDE WALLS, THIS SERVICE SHALL BE RELOCATED TO NEAREST CONVENIENT COLUMN OR WALL AND RE-FED AS DIRECTED BY OWNER'S REPRESENTATIVE, ALSO AT NO ADDITIONAL COST.
- CONTRACTOR SHALL FOLLOW PHASED DEMOLITION AS OUTLINED BY CONSTRUCTION MANAGER. WHERE DEMOLITION OF ONE PHASE INTERFERES WITH ELECTRICAL SERVICE TO DEVICES AND/OR EQUIPMENT IN ANOTHER PHASE, E.C. SHALL PROVIDE TEMPORARY SERVICE, AS REQUIRED, TO THE AFFECTED EQUIPMENT. ALL TEMPORARY SERVICES SHALL BE APPROVED BY THE OWNER.
- WHERE LUMINAIRES ARE CUT OFF FROM AN EXISTING FEED, THEY SHALL BE RE-FED FROM ANOTHER DIRECTION. PROVIDE NEW CONDUIT AND WIRE AS NECESSARY, AS DIRECTED BY OWNER'S REPRESENTATIVE AT NO ADDITIONAL COST.
- CONTRACTOR SHALL COORDINATE REMOVAL OF ALL COMMUNICATION LINES WITH OWNER. ANY COMMUNICATION LINES TO REMAIN SHALL BE RETAINED AND ADEQUATELY PROTECTED DURING CONSTRUCTION.
- ALL LIGHT FIXTURES WITHIN THE CONTRACT LIMITS ARE TO BE REMOVED AS SHOWN, UNLESS NOTED OTHERWISE. RETAIN EXISTING CIRCUIT(S) FOR REUSE WITH NEW LIGHTING IN THE AREA AS SHOWN ON NEW WORK PLAN. PROVIDE NEW WIRING AND SWITCHES AS SHOWN ON NEW WORK PLAN. ALL FIXTURES EXISTING TO BE RELOCATED SHALL BE CLEANED AND RELAMPED.
- FOR SYSTEMS AND DEVICES TO BE RELOCATED, PULL BACK WIRE FOR CONSTRUCTION AND REINSTALL TO NEW LOCATION AS SHOWN. REMOVE ALL ASSOCIATED RACEWAY(S) AND SUPPORTS AS NECESSARY TO ACCOMMODATE DEMOLITION AND PROVIDE NEW RACEWAY(S) AND SUPPORTS TO NEW LOCATION AS REQUIRED. ALL WORK SHALL COMPLY WITH NATIONAL ELECTRICAL CODE REQUIREMENTS.
- FIELD VERIFY ALL CIRCUITING TO REMAIN. WHERE CIRCUITS FEED AREAS BOTH INSIDE AND OUTSIDE THE CONTRACT AREA, DETERMINE SUITABLE BREAK POINT TO MAINTAIN POWER TO AREA(S) OUTSIDE THE CONTRACT AREA WHILE DEMOLITION IS COMPLETED.
- CONTRACTOR SHALL COORDINATE DEMOLITION OF ELECTRICAL CIRCUITS AND RETAIN EXISTING CIRCUIT(S) MADE AVAILABLE DUE TO DEMOLITION FOR REUSE AS SHOWN.

P2GE (EQ) (EXST)  
 XFMR (EQ) (EXST)  
 P4GE (EQ) (EXST)  
 L2GC (EM) (EXST)  
 XFMR (EQ) (EXST)  
 L4GC (EM) (EXST)  
 L2GN (NORM) (TO BE REPLACED)  
 XFMR (EQ) (EXST)  
 L4GN (NORM) (EXST)

**RestorixHealth**  
 Excellence in Wound Care

**DENNIS NOSKIN ARCHITECTS**  
 1000 BROADWAY, SUITE 1000  
 PORTLAND, ME 04103

**Z&F CONSULTING**  
 MECHANICAL, ELECTRICAL, PLUMBING  
 FIRE PROTECTION  
 80 WHEAT AVENUE  
 PORTLAND, ME 04103  
 www.zandf.com

**JOHN ZABLOWICZ, P.E.**  
 PROFESSIONAL ENGINEER  
 LICENSE NO.: 13062

STATE: MAINE  
**JOHN ZABLOWICZ, P.E.**  
 PROFESSIONAL ENGINEER  
 LICENSE NO.: 13062

**MAINE MEDICAL CENTER**  
 BRIGHTON CAMPUS  
**WOUND CARE AND**  
**HYPERBARIC MEDICINE**  
 333 BRIGHTON AVENUE  
 PORTLAND, ME 04103

KEY PLAN: GROUND FLOOR

ISSUE DATES:  
 JANUARY 26, 2015  
 STATE APPROVALS  
 MARCH 20, 2015  
 BLDG. DEPT. REVIEW

DRAWN BY: ARE  
 CHECKED BY: JZ  
 SCALE: 1/4" = 1'-0"

PROJECT NO.: P14110  
 SHEET TITLE:  
**ELECTRICAL**  
**DEMOLITION**  
**PLAN**

DRAWING NO.:  
**E-1**  
 ©2014