Inspections Division

Date: 06/15/16

Scale: ¼" = 1'

| | | | |
|---|---|---|---|
| Northern Pool & Spa<br>291 Harold L Dow Hwy<br>Eliot, ME 03903 | **Phone:** 207-439-6800<br>**Fax:** 207-439-4443 | **Designed by:**<br>Peter Paul<br>**5/12/2016** | **Designed for:** Rob Mitchell<br>Civiello Job |

Plunge Pool
A – 49
P – 28
(1) Handrail
Custom Stairs
(2) Main Drains w/Anti Entrapment Lids
(1) LED Light
3'6" to 4' Deep

Spa
A – 35
P – 24
(4) Main Drains w/ Anti Entrapment Lids
(1) LED Light
4' Deep

**LIGHT INSTALLATION**
(IF APPLICABLE)

NOTE: LIGHT IS A SEALED UNIT WITH WATERPROOF CORD ATTACHED

**POOL BEAM WITH CANTILEVER DECK**

| GENERAL SPECIFICATIONS | | | | | |
|---|---|---|---|---|---|
| SIZE 7 x 7 | DEPTH TO **3'6" to 4'** | BACKWASH TO **Sanitary Sewer** | | LADDER S/STL. | SUPPORTS |
| SHAPE **Square** | CODE | HEATER **Pentair 400Btu** | SIZE BTU | No. SLIDE | WATER CONNECTION |
| TILE SIZE **6 X 6** | COLOR | FUEL LINES: BY OTHERS | VENTED: BY OTHERS | ROPE RINGS | W/ ROPE FLOATS |
| TEMPLATE NO. | 12" COPING | LIGHT **Pentair (2)** | GFI | SPA BATH **Yes 5x7** | |
| PUMP **Pentair Whisperflow** | MOTOR H.P. | CLOCK: | BADU-JET: | APPROXIMATE ELEVATION OF POOL TO BE DETERMINED BEFORE DAY OF EXCAVATION | |
| FILTER **Pentair FNS36** | SQ.FT. | ELECTRIC BY: OTHERS | | | |
| TURNOVER | HRS. | ELECTRIC BONDING BY: OTHERS | | GRADING | STUB PLUMB YES NO |
| RETURN INLETS | | CLEANING TOOLS **Yes** | TEST KIT **Yes** | DECK BY: OTHERS | |
| MAIN DRAIN W/ HYDROSTATIC RELIEF **Pentair** | | VAC SET **Yes** | HOSE **Yes** | TREES and STUMPS BY: OTHERS | |
| SKIMMER – MODEL **Pentair** | | BOARD | SUPPORTS | APPROXIMATE GALLONS **1,359 Spa 936** | |

2 - #3 bars, 30" long, thru both rails

**GRAB RAIL INSTALLATION**