

Notes to Sheet A3:

- (1) Load-bearing wall labelled (A) will be removed and a beam will be installed in accordance with the Framing Plan and Notes in Sheets A1 and A2.
- (2) Non load-bearing walls labelled (B) and (C) will be removed.
- (3) Non load-bearing walls (D), (E) and (F) will be removed and replaced with guards around all three exposed sides of the basement stairs, which will be no less than 34" high and the openings between the vertical members will be less than 4".