

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

WOODFORDS CONGREGATIONAL PARISH/TBA

Located at

186-202 WOODFORD ST

PERMIT ID: 2013-00940

ISSUE DATE: 07/23/2013

CBL: 124 J005001

has permission to **Place panel antenna inside lantern section of steeple, equipment room in basement of church, outside diesel generator on 4'x8' concrete pad.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ Chris Pirone

/s/ Jeanie Bourke

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Woodfords Congregational Church and
Portland Conservatory of Music

Building Inspections

Use Group: A-3 **Type:** 5B
Assembly - Place of Worship
w/Accessory Uses
ENTIRE
MUBEC/IBC 2009

Fire Department

Classification:
Assembly
ENTIRE
2009 NFPA

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Footings/Setbacks

Electrical Close-in

Framing Only

Above Ceiling Inspection

Final - Electric

Final - Commercial

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2013-00940	Date Applied For: 05/09/2013	CBL: 124 J005001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: same: Church & Portland Conservatory of Music		Proposed Project Description: Place panel antenna inside lantern section of steeple, equipment room in basement of church, outside diesel generator on 4'x8' concrete pad.		
Dept: Zoning	Status: Approved w/Conditions	Reviewer: Marge Schmuckal	Approval Date: 05/14/2013	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) the exterior generator shall be tested during week days between 10:00 am and 3:00 pm to avoid noise disruption.				
Dept: Building	Status: Approved w/Conditions	Reviewer: Jeanie Bourke	Approval Date: 06/26/2013	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				
2) Permit approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				
Dept: Fire	Status: Approved w/Conditions	Reviewer: Chris Pirone	Approval Date: 07/23/2013	Ok to Issue: <input checked="" type="checkbox"/>
Note: IBC analysis but no NFPA				
Conditions:				
1) Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.				
2) Street addresses shall be marked on the structure and shall be as approved by the City E-911 Addressing Officer. Contact Michelle Sweeney at 874-8682 for further information.				
3) A separate Fire Alarm Permit is required for new systems; or for work effecting more than 5 fire alarm devices; or replacement of a fire alarm panel with a different model. This review does not include approval of fire alarm system design or installation.				
4) A separate Suppression System Permit is required for all new suppression systems, including standpipe systems, and sprinkler work effecting more than 20 heads. This review does not include approval of system design or installation.				
5) Fire extinguishers are required per NFPA 1.				
6) All means of egress to remain accessible at all times.				
7) Emergency lights and exit signs are required. Emergency lights and exit signs are required to be labeled in relation to the panel and circuit and on the same circuit as the lighting for the area they serve.				
8) Any cutting and welding done will require a Hot Work Permit from Fire Department.				
9) Construction or installation shall comply with City Code Chapter 10.				
10 Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.				
11 **The fire alarm system design shall be evaluated for the renovated areas by an NICET IV certified interior fire alarm designer or a licensed engineer for compliance with the code. A compliance letter is required prior to the final inspection.**				
A current inspection sticker from an approved fire alarm inspection company is required prior to the final inspection.				
12 The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.				

- 13 The single stair enclosure in the Parish house shall be signed and labeled as an Exit from the Second and Third Floors. The stair should also be verified as being protected with 1-hour fire resistance rated construction for an existing exit enclosure per 2009 NFPA 101 7.1.3.2.1 (2) (a).
- 14 All vegetation shall be removed in order to provide occupants safe exit discharge conditions from the East fire escape stair and exterior stair leading from the Chapel per 2009 NFPA 101 7.7.1.1.
- 15 The telecommunications room shall be properly signed with contact information for Verizon Wireless.
- 16 The telecommunications room shall be properly signed as notification for Fire department.
- 17 Fire walls, fire barriers, fire partitions, smoke barriers and smoke partitions or any other wall required to have protected openings or penetrations shall be effectively and permanently identified with signs or stenciling in accessible concealed floor, floor-ceiling or attic spaces at intervals not exceeding 30 feet with lettering not less than 0.5 inches in height.