

CITY OF PORTLAND  
FIRE PREVENTION BUREAU  
380 Congress Street, Portland, Maine 04101  
fireprevention@portlandmaine.gov  
(207) 874-8400

**NOTICE OF VIOLATION AND ORDER TO CORRECT**

September 20, 2017

<b>Responsible Party 1:</b> Howell Holland R 747 E Main St Yarmouth, ME 04096		
<b>Location</b> 41 REVERE ST	<b>CBL</b> 124 J015001	<b>Inspection Date</b> 9/5/2017
<b>Inspector</b> Daniel Dyer	<b>Inspection Type</b> FP Routine Inspection	<b>Status</b> Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

**You must send this form to the Fire Prevention Bureau no later than 10/15/2017.**

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

<b>Violation</b>	<b>Proposed Date of Completion</b>
<b>NFPA 101- 7.2.1.8.1 FIRE DOOR(S) MUST SELF-CLOSE;</b> A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. Need self closer 2nd floor front	
<b>NFPA 70- 590.6 EXTENSION CORDS;</b> Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities. Red extension cord in basement to first floor used for permanent wiring	___ / ___ / ____
<b>NFPA 70 MISSING BOX COVERS;</b> Refer to NFPA 70, National Electrical Code, on standards for missing box covers. basement	___ / ___ / ____
<b>NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED;</b> Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. From basement entrance to rear egress	___ / ___ / ____
<b>FINAL DATE OF COMPLETED VIOLATION(S)</b>	___ / ___ / ____
<b>FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)</b>	___ / ___ / ____

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

**VIOLATOR CERTIFICATION**

*I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.*

*I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.*

*If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.*

---

Date

---

Responsible Party

---

Date

---

Responsible Party

**SEEN AND AGREED**

---

Date

---

Fire Prevention Bureau