

CITY OF PORTLAND  
 FIRE PREVENTION BUREAU  
 380 Congress Street, Portland, Maine 04101  
 fireprevention@portlandmaine.gov  
 (207) 874-8400

**NOTICE OF VIOLATION AND ORDER TO CORRECT**

SULAN CHAU  
 105 FALMOUTH ST  
 PORTLAND ME 04103

October 13, 2017

<b>Location</b> 112 WOODFORD ST	<b>CBL</b> 125 N013001	<b>Inspection Date</b> 9/21/2017
<b>Inspector</b> Mark Stewart	<b>Inspection Type</b> FP Re-Inspection	<b>Status</b> Unable to Gain Entry

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

**You must send this form to the Fire Prevention Bureau no later than 10/30/2017.**

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

<b>Violation</b>	<b>Proposed Date of Completion</b>
<b>NFPA 720- 5.5.6.1 CO ALARMS REQUIRED;</b> The performance, location, and mounting of notification appliances used to initiate or direct action, evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with the requirements of Chapter 6. CO Alarm needed in basement.	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.
<b>NFPA 1 EXCESSIVE/DISORDERLY STORAGE;</b> Reference NFPA 1 for excessive fuel-load. Trash on third floor rear landing.	
<b>NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS;</b> Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating. 220 volt Dryer outlet missing cover.	
<b>NFPA 80- ANNEX D.4 1-HOUR FIRE DOORS ASSEMBLIES REQ;</b> Listings are provided for floor fire door assemblies that are installed in fire-rated floor-ceiling or roof-ceiling assemblies that have been tested in accordance with the methods described in NFPA 288. The listing indicates the fire-rated assembly and the hourly rating (3 hours, 2 hours, 1.5 hours, 1 hour, .75 hours) for which the door can be permitted to be used so that access to the space above the ceiling or to the floor above can be provided without adversely affecting the fire resistance rating of the entire assembly. The listing provides limitations on the maximum size of an individual door opening and the total area of all door openings permitted for each 100 square feet of floor or ceiling. Rated door required to Basement and both front and rear door to Unit #2 on the first floor.	

Violation	Proposed Date of Completion
<b>NFPA 101- 7.2.8.5.1 HANDRAILS REQUIRED ON STAIRS;</b> All fire escape stairs shall have walls or guards and handrails on both sides in accordance with 7.2.8.4.1 (b). Railing on third floor front stair needs to be installed.	
<b>NFPA 101- 8.2.3 FIRE RATING NOT MAINTAINED;</b> The fire resistance of structural elements and building assemblies shall be determined in accordance with test procedures set forth in NFPA 251, ASTM E 119, ANSI/ UL 263, or other approved test methods, or analytical methods approved by the authority having jurisdiction. Materials used to construct fire resistance-rated elements and assemblies shall be limited to those permitted in this code. Second unused door to Unit #3 on second floor in front needs to be removed and sheetrocked.	
<b>N.F.P.A. 101 CHP. 31.3.3.2 HOLE IN CEILING NEEDS REPAIR;</b> InteriorWall and Ceiling Finish Interior walls and ceiling finish materials complying with 10.2 shall be permitted as follows: 1) Exit enclosures -- Class A or class B 2) Lobbies and corridors--Class A or Class B 3) Other spaces Class A, orClass B, or Class C Scuttle in rear stairwell needs to be closed in.	
<b>FINAL DATE OF COMPLETED VIOLATION(S)</b>	____ / ____ / ____
<b>FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)</b>	____ / ____ / ____

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

**VIOLATOR CERTIFICATION**

*I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.*

*I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.*

*If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.*

\_\_\_\_\_  
Date Responsible Party

\_\_\_\_\_  
Date Responsible Party

**SEEN AND AGREED**

\_\_\_\_\_  
Date Fire Prevention Bureau