

Reference #	Classification	Dimensions	Square Footage	2009 IBC Max Occupancy per Person	Gross Occupants	Net Occupants
1	Commercial Kitchen	20' x 16'	320	200	2	2
2	Restroom	5.41666' x 7.6667'	41.52778	0	0	0
3	Restroom	Irregular	98.21528	0	0	0
4	Business Area	7.20866' x 16'	115.3333	100	1	1
5	Accessory Storage Area	6' x 16'	96	300	0	0
6	Accessory Storage Area	6' x 15'	90	300	0	0
7	Restaurant without fixed seats unconcentrated (tables	Aggregate Seating (Not Including Drink Rail)	274	15	18	18
7a	Drink Rail	16' x 2'	32	7	5	5
7b	Drink Rail	29 x 2'	58	7	8	8
7c	Drink Rail	9' 7" x 2'	19.16666	7	3	3
7d	Table Seating Area	9' x 8'	72	-	-	-
7e	Table Seating Area	9' x 8'	72	-	-	-
7f	Low-Top Seating	15' x 8'	120	-	-	-
7g	Bar Seating	5' x 2'	10	7	1	1
7h	Seating	10' x 10'	100	-	-	-
8	Accessory Storage Area	17.354' x 8.64583'	150.0412	300	1	0
9	Corridor / Shared Egress	20.22917 x 8.6458'	174.898	0	0	0
10	Walking Path	Irregular	744.651	0	0	0
11	Stairs Egress	9 x 7	63	0	0	0
				Occupancy Load		38