Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/20/15

STRUCTURAL FOUNDATION NOTES:
8" POURED CONCRETE FOUNDATION WALL ON 16" X 10" FOOTING

HORIZONTAL REINFORCEMENT #4 REBAR AT TOP OF WALL AND 48" DOWN. VERTICAL REINFORCEMENT #4 REBAR @ 48" O.C.

FOOTINGS (PRESUMED SOIL BEARING PRESSURE = 200 PSF TO BE VERIFIED IN FIELD.

CONCRETE SLAB ON GRADE SHALL BE 300 PSI (PC) CONCRETE STRENGTH W/ 6x6 W 1.4 x W1.4 WWF 5/8" CLR FROM TOP OF SLAB. JOINTS 3/4" WIDE x 5/8" DEEP) @ MAX. 12'x15' (225 SF, MAX). TYP.

1 Basement Floor Plan
Scale: 1/8" = 1'-0"

DATE: 11.17.2014
DRAWN BY: BB

A1.2

FLOOR PLANS
CABOT

PROSPECT
DESIGN
58 FORE ST. PORTLAND, ME
www.prospectdesign.me
T: 207 - 749 - 7400