Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 01/20/15

2 STAIR DETAIL
3/8" = 1'-0"

EXTERIOR STAIR NOTES:
PROVIDE ADD/ALTERNATE FOR REPLACING SIDE STAIRS TO SUNROOM
STAIRS SHALL HAVE PT FRAMING WITH MARANTE TREADS.
STAIR NOSING SHALL EXTEND ¾" BEYOND RISER.
STAIR LANDING SHALL BE 36" MIN.
PROVIDE PAINTED WOOD HANDRAIL 34" ABOVE NOSING.
PROVIDE RAILING ON LANDING @ 36" AFF
RAILING SHALL BE PAINTED BALUSTERS @4" ON CENTER WITH HARDWOOD CAP

IRC Sec R311.7.4.3 requires the nosing to be a minimum of 3/4" and a max 1-1/4"

Frost protection shall be provided as per the typical footing detail below

1 STOOP LEDGER ATTACHMENT
1" = 1'-0"

FOAM INSULATION NOTE:
PROVIDE A THERMAL BARRIER OF MINIMUM 1/2 INCH (12.7 MM) GYPSUM WALLBOARD OR A MATERIAL THAT IS TESTED IN ACCORDANCE WITH AND MEETS THE ACCEPTANCE CRITERIA OF BOTH THE TEMPERATURE TRANSMISSION FIRE TEST AND THE INTEGRITY FIRE TEST OF NFPA 275.

1 STAIR DETAIL
3/8" = 1'-0"

0 1'-4" 2'-8"

SCALE: 3/8" = 1'-0"

PROSPECT
DESIGN
58 FORE ST. PORTLAND, ME
www.prospectdesign.me
T: 207 - 749 - 7400

DATE: 1.16.2015
DRAWN BY: BB

A3.2

SECTIONS
CABOT