53 CLIFTON STREET DECK REPLACEMENT

1X4 PREMIUM DOUGLAS FIR CLEAR KILN DRIED DECKING W/ 1/8" GAP & SS RING SHANK NAILS INTO P.T. 2X8 @ 16" C/C OVER DROP BEAM TO CANTELEVER 2'.

5'-3"

MATCH EXISTING DECK WIDTH

DEMO + MATCH EXISTING DECK WIDTH 7'-0" +/-

(NEW WOOD DECKING TO MATCH SIDE PORCH)

3'-0"

NEW 36" H. IRON RAIL W/ 4" VERTICAL BALUSTER SPACING (TYP. WHERE INDICATED

DROP BEAM ON (3) SONOTUBES BELOW FROST

REMOVE/REPLACE COLUMNS & BOXED COLUM SUPPORTS TO MATH ORIGINAL DETAILING EXCEPT TALLER TO RECEIVE 36" TALL IRON RAILINGS

2'-3"

ALIGN CANTILEVER W/ INSIDE FACE OF BOXED COLUMN SUPPORTS

1'-6"

2'

CANTE-LEVER

5'-0"

2'-2"

NEW IRON RAILS TO BOTTOM OF STAIRS B.S.

REMOVE EXISTING STRAIRS & DECK COMPLETE & DISPOSE OF ALL DEMO & SCRAP.

9'-1" SLOPED

9'-1" SLOPED

(8) 10" TREADS (CONFIRM

4'-8"

1'-2"

REPLACE EXISTING WOOD W/ IRON RAILING TO MATCH NEW RAILINGS @ FRONT PORCH. PROVIDE 90° EXTENSION TOWARD DRIVEWAY.

DECK PLAN

1/2" = 1'-0"

(PRINT 11X17

DRAWING 2