

Scott Markowski <scottm@casco bayengineering.com>

March 13, 2014 10:46 AM

To: "Anne Callender" <anne@whipplecallender.com>, <ericd@casco bayengineering.com>

Watt Renovation

---

Anne,

I ran some numbers for the Watt Renovation headers. I tried checking the existing beam in the first floor at the kitchen opening for a new point load. The beam (assuming 6x10) does not work for the added point load. Therefore, we will have to span the entire span of ~14'-0", requiring the beam to be 5 ¼ x 14 LVL. The other 5'-0" headers can be (3)2x10. If you find you don't have the width for (3) boards we can go to a (2)2x12 header.

Let me know if you have any further questions or clarifications.

Scott Markowski, PE

Casco Bay Engineering

424 Fore St, Portland, ME 04101

207.842.2800 ext 203