DIRECTORY	KVA LOAD			CKT NO.	BKR AMPS	A B C	BKR AMPS	CKT NO.	KVA LOAD			DIRECTORY
	A	B	C						A	B	C	
				1				2				
				3			4	4				
RECEPTS – OFFICE 109			0.9	5	20		20	6				
				7				8				
				9				10				
				11				12				
				13				14				
				15				16				
				17				18				
				19				20				
				21				22				
				23				24				
SUB–TOTAL	*	*	*			NEUTRAL BUS			*	*	*	SUB–TOTAL
						GROUND BUS						
VOLTAGE: 208Y/120V 3 PHASE 4 WIRE					100 AMP BUS	TOTAL kVA	A		*			PANEL NO.
MAIN LUGS ONLY					100 AMP LUGS	TOTAL kVA	B		*			LOCATION
MOUNTING: RECESSED						TOTAL kVA	C		*			
SC RATING: *						TOTAL kVA						

NOTES: *

DIRECTORY	KVA LOAD			CKT NO.	BKR AMPS	A B C	BKR AMPS	CKT NO.	KVA LOAD			DIRECTORY
	A	B	C						A	B	C	
				1				2				
				3			20	4	*			*
RECEPTS & LTG – OFFICE 123	0.8			5	20		20	6		*		
RECEPTS & LTG – OFFICE 124		0.8		7	20		20	8				
RECEPTS & LTG – OFFICE 125			0.8	9	20		20	10				
RECEPTS – OFFICE 125	0.7			11	20		20	12				
RECEPTS – OFFICE 110 & 111				13	20		20	14				
RECEPTS – OFFICE 111 & 112				15	20		20	16				
RECEPTS – OFFICE 103				17	20		20	18				
RECEPTS – OFFICE 104				19	20		20	20				
RECEPTS – OFFICE 105				21	20		20	22				RECEPTS – OFFICE
				23	20		20	24				RECEPTS – OFFICE
				25	20		20	26				
				27	20		20	28				
				29	20		20	30				
				31	20		20	32				
				33	20		20	34				
				35	20		20	36				
				37				38				
				39				40				
				41				42				
SUB–TOTAL	*	*	*			NEUTRAL BUS			*	*	*	SUB–TOTAL
						GROUND BUS						
VOLTAGE: 208Y/120V 3 PHASE 4 WIRE					200 AMP BUS	TOTAL kVA	A		*			PANEL NO.
MAIN BREAKER:					200 AMP TRIP	TOTAL kVA	B		*			LOCATION
MOUNTING: RECESSED						TOTAL kVA	C		*			
SC RATING: *						TOTAL kVA						

NOTES: *

SHEET No.	SHEET TITLE:	SCALE:	PROJECT MANAGER:	JC/DRAWN BY:	A/E OF RECORD:	CAD FILE:	PROJECT NO:	DATE:	GRAPHIC SCALE:	REV	DESCRIPTION	DATE
EP601	PANEL SCHEDULES	NONE	SLB	CDS	DJT	EP601-09148	09148		0" 1"			

© COPYRIGHT 2010 SMRT INC.

UNIVERSITY OF SOUTHERN MAINE
RENOVATION 501 FOREST AVENUE
PORTLAND, MAINE

ISSUED FOR DESIGN DEVELOPMENT
4–12–10
CURRENT ISSUE STATUS:

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING

144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772–3846
fax. (207) 772–1070
www.smrtinc.com