



- ROOF FRAMING NOTES:**
1. See Structural Notes, Sheet S-1.
 2. Built-up headers and beams shall be spiked w/ 3 rows of 16d nails @ 12" o.c.
 3. Provide metal hangers at all flush rafter connections.
 4. Provide (2) 1 1/2" x 9 1/2" LVL header w/ 2" rigid insulation between over all exterior door and window openings unless noted on plan.
 5. See architectural drawings for wall layout and dimensions.
 6. Connect all Rafters to wall plate with Simpson H2.5 Seismic & Hurricane Ties per Manufacturer's instructions.

ROOF FRAMING PLAN

Scale: 1/4" = 1'-0"

