DOOR #	SIZE	DOOR MATERIAL	DOOR TYPE	DOOR FINISH	FRAME MATERIAL	FRAME TYPE	FRAME JAMB	FRAME HEAD	FRAME FINISH	FRAME LABEL	KICK PLATE SIZE	KICK PLATE MOUNTING LOCATION	HARDWARE SET No.	KEY SIDE	KEY SCHEDULE KEY NUMBER	NOTES
109A	3'-0" X 7'-0"	HM	C	PT-03	HM	1	J1	H1	PT-02	-	10" X 34"	SALES SIDE OF DOOR	3	III	KEY #4	PHARMACY DOOR WITH FLOOR STOP.
109B	3'-0" X 7'-0"	WD	F	PL-1	HM	1	J1	H1	PT-03	-	10" X 34"	SALES SIDE OF DOOR	3	112	KEY #4	CONSULTATION ACCESS DOOR: DOOR TO BE PL-8 PIONITE WM 791-5 HARD ROCK MAPLE FINISH-TEXTURED OR NEVAMAR SANTA ROSA PLUM TREE WZ2001T G.C. TO PURCHASE DOOR #109B THROUGH "LOCKNET", ROBERT OWEN (800) 887-4307, Rob@locknet.com
114B	3'-0" X 7'-0" RCM TO CONFIRM	POLYMER CELL	B	MANUF	STL	1	J2	H2	PT-04	-	N/A		MANUF		NONE	CHASE-DURUS MODEL #NW 3011, BI-PARTING DOORS - COLOR: CHOCOLATE BROWN

G.C. TO PURCHASE DOOR #109B THROUGH "LOCKNET", ROBERT OWEN (800) 887-4307, Rob@locknet.com

SPACE RESERVED FOR CITY OF PORTLAND, MAINE ELECTRONIC STAMP

REFER TO RITE AID'S SEGMENTATION MANUAL SECTION SEG13 (DATED 10-10-2011) FOR PRIVACY BLINDS (AND HOLD DOWN CLIPS) FOR DOOR AND WINDOW BETWEEN PHARMACY AND NEW CONSULTATION ROOM. GC TO PROVIDE.

DOOR SCHED. & NOTES

2 / A-2

SCALE: NOT TO SCALE

ENLARGED FLOOR PLAN

1 / A-2

SCALE: 1/4" = 1'-0"

1.1 MATERIALS FOR WF-2 PLEXIGLASS AT DOOR TYPE "F"

A. Uncoated Monolithic Cell-Cast Acrylic Sheet: ASTM D 4802, Category A-1, Type UVF (UV filtering), Finish 1 (smooth or polished).

1. Products:

a. CYRO Industries; Acrylite G P-95

2. Nominal Thickness: ¼ inch.

B. Translucent Color: White, with visible light transmittance of not more than 50 percent for 0.117-inch- (2.9-mm-) thick sheet, measured per ASTM D 1003.

KEY SET #2 & #4 IS TO HAVE 6 COPIES. THESE ARE SUPPLIED BY THE GC

- ALL OF THE LOCKSETS FOR THE KEY SETS WHICH ARE SUPPLIED BY THE GC ARE TO BE TURNED OVER TO RITE AID PER THE DIRECTION OF THE RITE AID CONSTRUCTION MANAGER.

- THE GC IS TO SUPPLY ONE BLANK KEY FOR EACH LOCKSET.

A5 REQ.

HARDWARE SET NUMBER 3
1 FLOOR BUMPER 406 1/2 X PA 28 X HB-IVES
1-1/2 PAIR BUTTS, 4-1/2 X 4-1/2 STANLEY FBB 191 X US 26D NRP
1 CLOSER, CORBIN-RUSSWIN DC 6210X 689 X M54
1 LOCK, CORBIN-RUSSWIN CL 3357 NZD X 626 X 2 3/4" B.S. (STOREROOM)
1 LOCK/LATCH GUARD-IVES LG13 US32D
1 KICK PLATE, 10" X 34" SERIES 8400 (NOT FOR #109B).

HARDWARE SET NUMBER 2 (#104)
1 FLOOR BUMPER 406 1/2 X PA 28 X HB-IVES
1-1/2 PAIR BUTTS, 4-1/2 X 4-1/2 STANLEY FBB 191 X US 26D NRP
1 CLOSER, CORBIN-RUSSWIN DC 6210X 689 X M54
1 LOCK, CORBIN-RUSSWIN CL 3357 NZD X 626 X 2 3/4"
B.S. (STOREROOM); NOT FOR DOOR #103
1 LOCK/LATCH GUARD-IVES LG13 US32D

NOTE: CONSTRUCT WALL PER TEMPLATE PROVIDED BY RITE AID'S CABINET SHOP TO ASSURE TOP CAP FITS

WALL ELEVATION

1

A — AS SHOWN

A6 — AS SHOWN

B — AS SHOWN

WALL TYPES

5 / A-2

SCALE: 1 1/2"=1'-0"

PARTITION TYPES

- NEW METAL STUD/GPDW PARTITION (SEE SHEET A-2)
- NEW LOW HEIGHT METAL STUD/GPDW PARTITIONS (UNLESS OTHERWISE NOTED)
- EXISTING PARTITIONS TO BE REMOVED
- EXISTING PARTITIONS TO REMAIN

ADA SIGNAGE

6 / A-2

NOT TO SCALE

NOTES

1. CHARACTERS AND SYMBOLS SHALL CONTRAST WITH THEIR BACKGROUND.
2. IDENTIFICATION SYMBOLS ARE TO BE ON WALL ADJACENT DOOR 60" ABOVE FLOOR AND ARE TO BE DISTINCTLY DIFFERENT FROM DOOR AND WALLIN COLOR AND CONTRAST.
3. PROVIDE ROOM IDENTIFICATION SIGN ON LATCH SIDE OF DOOR.
4. LETTERS & NUMBERS ON SIGNS SHALL BE RAISED 1/32" MIN., SHALL BE A MIN. OF 5/8" HIGH & SHALL BE SANS-SERIF UPPERCASE CHARACTERS. A.D.A. SIGNAGE ACCOMPANIED BY GRADE 2 BRAILLE.
5. REGULATORY SIGNS TO BE TYPICALLY ADA COMPLIANT TACTILE 3-D PLAQUES PER CODE REQUIREMENTS.
6. SIGNS TO BE A TYPICAL ONE PIECE INJECTION MOLDED FABRICATION WITH RAISED SECOND SURFACE GRAPHICS.
7. STANDARD BLUE ADA SIGN PROVIDED BY GENERAL CONTRACTOR. MODEL # MEN ADA 304, AND MODEL # WOMEN ADA 305. DIMENSIONS: 6"x9".
8. BRAILLE SHOWN IS FOR PLACEMENT ONLY. USE CORRECT BRAILLE FOR SIGN PRODUCTION.
9. THE ADA SIGNAGE CAN BE OBTAINED FROM EMEDCO CORPORATION. CONTACT INFO. PH# 1-800-273-3984 (Ext.7502)

WAITING AREA PLAN

3 / A-2

SCALE: 1/4"=1'-0"

NOTES FOR SUBSTRATE (DRYWALL) TREATMENT/REPAIR AT WALL AREA TO RECEIVE NEW "GREEN LEAVES" WALL GRAPHIC:

1. MARLITE ON THE ENTIRE FRONT WALL TO BE REMOVED. DRYWALL WILL NEED TO BE REMOVED AND REPLACED AS NECESSARY DUE TO THE DAMAGE LEFT BEHIND FROM MARLITE ADHESIVE TEARING THE DRYWALL FACE.
2. RX EXISTING FRONT WINDOW TRIMS (SALES SIDE) ARE INSTALLED ON TOP OF THE MARLITE WALL PANELS IN SOME INSTANCES (GC TO REVIEW). INSIDE FRAME THAT THE CASING IS ATTACHED TO MUST BE REMOVED AND CUT BACK BY 1/4", AND THEN RE-INSTALLED AS HELL AS THE BUILD-OUTS AND THE CASING TRIM.
3. FILL / SAND / PRIME / PAINT WOOD TRIMS FOR NEAT, FINISHED APPEARANCE AS REQUIRED.
4. THE PRE-WALL COVERING APPLICATION IS INTENDED TO PREP THE WALL TO RECEIVE WALL COVERING PASTE AND IS NOT INTENDED TO SEAL OR COVER THE EXISTING PAINT. INSL-X SUPERIOR SPECIALTY COATINGS HP 3001 & SHERWIN WILLIAMS LATEX PRIMER SEALER B51 THAT IS WHITE IN COLOR TO BE USED TO SEAL OLD PAINT COLOR AND CREATE A WHITE BACKGROUND.
5. REMOVE EXISTING MARLITE OR ANY WALL COVERING AND PREPARE SURFACE FOR NEW RX WALL MURAL COVERING BY BLOCKING, SHEET ROCK, PRIME, TAPE AND PASTE, ETC.

EXECUTION

1.1 EXAMINATION

A. EXAMINE SUBSTRATES AND CONDITIONS, WITH INSTALLER PRESENT, FOR COMPLIANCE WITH REQUIREMENTS FOR LEVELNESS, WALL PLUMBNESS, MAXIMUM MOISTURE CONTENT, AND OTHER CONDITIONS AFFECTING PERFORMANCE OF WORK.

B. PROCEED WITH INSTALLATION ONLY AFTER UNSATISFACTORY CONDITIONS HAVE BEEN CORRECTED.

1.2 PREPARATION

A. COMPLY WITH MANUFACTURER'S (WALL MURAL) WRITTEN INSTRUCTIONS FOR SURFACE PREPARATION. INCLUDE APPLICATION OF SEALER.

B. SHERWIN WILLIAMS PRE-WALLCOVERING PRIMER.

1 GYPSUM BOARD ASSEMBLIES

A. GENERAL: APPLY JOINT TREATMENT AT GYPSUM BOARD JOINTS (BOTH DIRECTIONS); FLANGES OF CORNER BEAD, EDGE TRIM, AND CONTROL JOINTS; PENETRATIONS; FASTENER HEADS, SURFACE DEFECTS, AND ELSEWHERE AS REQUIRED TO PREPARE GYPSUM BOARD SURFACES FOR DECORATION AND LEVELS OF GYPSUM BOARD FINISH INDICATED.

B. PRE-FILL OPEN JOINTS, ROUNDED OR BEVELED EDGES, AND DAMAGED AREAS USING SETTING-TYPE JOINT COMPOUND.

C. APPLY JOINT TAPE OVER GYPSUM BOARD JOINTS AND TO TRIM ACCESSORIES WITH CONCEALED FACE FLANGES AS RECOMMENDED BY TRIM ACCESSORY MANUFACTURER AND AS REQUIRED TO PREVENT CRACKS FROM DEVELOPING IN JOINT COMPOUND AT FLANGE EDGES.

D. LEVELS OF GYPSUM BOARD FINISH: PROVIDE THE FOLLOWING LEVELS OF GYPSUM BOARD FINISH PER GA-214.

1. LEVEL 4, INSTALL AS FOLLOWS:

A. EMBEDDING AND FIRST COAT: ALL-PURPOSE READY-MIXED JOINT COMPOUND.

B. FILL (SECOND) COAT: ALL-PURPOSE READY-MIX JOINT COMPOUND.

C. FINISH (THIRD) COAT: READY-MIX TOPPING COMPOUND.

D. ALL JOINTS AND INTERIOR ANGLE SHALL BE TAPE EMBEDDED IN JOINT COMPOUND AND THREE SEPARATE COATS OF JOINT COMPOUND APPLIED OVER ALL JOINTS, ANGLES, FASTENER HEADS AND ACCESSORIES.

E. SURFACE SHALL BE SMOOTH AND FREE OF TOOL MARKS AND RIDGES.

FINISHES MUST BE APPROVED BY RAC REPRESENTATIVE

INTERIOR ELEVATION

4 / A-2

SCALE: 1/4" = 1'-0"

SEE SHEET A-3, A-4 FINISH SCHEDULE FOR ADDITIONAL MATERIAL INFO
REFER TO FINAL DECOR PLAN FOR FINAL OUTLINE OF PAINTING SCHEDULE

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/12/14

BRUCE RONAYNE HAMILTON ARCHITECT

ARCHITECTURE
LAND PLANNING
INTERIOR DESIGN
3D VISUALIZATION

833 TURNPIKE ROAD
P.O. BOX 104
NEW IPSWICH
NEW HAMPSHIRE 03071

REGISTERED ARCHITECT BRUCE RONAYNE HAMILTON No. 1500 STATE OF MAINE

THIS DESIGN AND THE DRAWINGS THEREFORE, PREPARED FOR THIS PRO. ARE THE PROPERTY OF THE ARCHITECT BRUCE RONAYNE HAMILTON, ARCHITECT INC., AND THE DESIGN AND/OR DRAWIN MAY NOT BE USED IN WHOLE OR IN PA ORIGINAL USE OF THIS DESIGN AND/OR ORIGINAL SUBJECT PURPOSE OF THE DES AND/ OR DRAWINGS WERE PREPARED, WITHOUT THE EXPRESSED WRITTEN PERMISSION OF THE ARCHITECT, BRUCE RONAYNE HAMILTON ARCHITECTS, INC. NO BUILDING PERMIT SHALL BE ISSUED UNLESS THE ARCHITECTURAL DESIGN DOCUMENT BEARS THE ORIGINAL SEAL SIGNATURE OF THE ARCHITECT, BRUCE RONAYNE HAMILTON ARCHITECTS INC.

REV. NO.	DATE	DESCRIPTION
1	1-7-14	ISSUED FOR GC BIDDING/BUILDING PERMIT

PROJECT: RITE AID STORE #4133 PPR
701 FOREST AVENUE
PORTLAND, MAINE

SUBJECT: PHARMACY PLANS, ELEVATIONS & DETAILS

JOB NO. 13-131
SCALE: AS NOTED
DATE: 1-7-14
DRAWN BY:

SHEET NO. A-2