

Done

CROCE_1751863.pdf



Cu

Address:

Phone:

Fax:

Customer Information:

Project Name: EN

Quote Name: CF

Quote Number: 17

Order Date: Qu


PO Number:

Comments:

RO size for Flange is for standard 1x buck with precast sill. Please contact your supplier for other

ITEM & SIZES LOCATION / TAG PRODUCT DESCRIPTION

Line Item: 100-1	None Assigned	*** PRODUCT *** Row 1 1556 Double Hung - Vent - 1 Units - 40W x 59H
Quantity: 1		*** DIMENSIONS *** 40W x 59H
RO Size: 40.5" X 59.5"		*** FRAME *** East, Vinyl, Frame Type - Fin, Exterior Color - White
Unit Size: 40" X 59"		*** GLASS *** Glazing Type - Insulated, Glass Tint - Clear, Low-E, Argon Gas, Glass Strength - DSB
		*** SCREEN *** Screen - Rollform Full, Screen Mesh Type - Charcoal Fiber, Screens Packed Separately - Yes
		*** HARDWARE *** Factory Applied WOCD
		*** WRAPPING *** Extension Jambs - None, J-Channel - None
		*** NFRC *** Series 1556::DoubleHung, U-Factor::0.28, SHGC::0.27, VT::0.51
		*** Performance *** Series 1556::DoubleHung, Calculated Positive DP Rating::30.08, Calculated Negative DP Rating::30.08, DP Rule ID::1556 DH, Rating Type::DesignPressure, Structural Rating::R-PG30*, Water Rating::4.59, FL ID::N/A



1556 Double Hung - Vent - CustomCustom

