PLAN NORTH

NOTES:
1. T.O. STEEL:
   1ST FLOOR 52'-7¾" (REFERENCE 9'-0¼" ABV T.O. SLAB / 43'-7½")
   2ND FLOOR 63'-7¾" (REFERENCE 20'-0¼"ABV T.O. SLAB)
2. PROVIDE SIMPSON JOIST HANGERS AT ALL JOIST ENDS, TYP.
3. WINDOW HEADERS SHALL BE (3)-2x10's, U.N.O.
4. PROVIDE (3)-2x6 COLUMNS, U.N.O.
5. FASTEN ALL EXTERIOR INSULATED SHEATHING PANELS @ EDGES W/ TRUFAST SIP LD or TP 0.255"ø x 4½" SCREWS (OR EQUIV) @ 6"o.c. U.N.O.
6. USE TRUFAST SIP LD or TP 0.255"ø x 4½" SCREWS (OR EQUIV) @ 12"o.c. FOR MIDFIELD PANEL AREAS.
7. SEE SHEAR WALL SCHEDULE ON S.1.2 FOR ASSEMBLY REQUIREMENTS

PLAN LEGEND
- BEARING WALL
- SHEAR WALL
- BEAM
- HSS COLUMN
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

ROOF FRAMING PLAN

SCALE: 1/4"=1'-0"

PRINTED: Dec 14, 2016

Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 05/31/17

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
Kevin Moquin
Architect
PORTLAND, ME
207.615.6421

STATE OF MAINE
ERIC DUBE
No. 12630
LICENSED
PROFESSIONAL ENGINEER

23 OCEAN
23 OCEAN AVE
PORTLAND, ME

PROPOSED BUILDING

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
A	ISSUED FOR REVIEW	CD	ED	11-2-16
B	ISSUED FOR PERMIT	CD	ED	12-14-16

SHEET TITLE:
ROOF FRAMING PLAN

DESIGNED:	ED
DRAWN:	CD
DATE:	9-14-16
PROJECT NUMBER:	16-063

S1.4