Reviewed for Code Compliance
Inspection Division
Portland, Maine
Date: 05/31/17

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	PROPERTY/ROW	
	SETBACK	
	EASEMENT	
	CENTERLINE	
	MONUMENT	
	IRON PIPE/ROD	
	BUILDING	
	EDGE PAVEMENT	
	GRAVEL ROAD	
	CURBLINE	
124	CONTOURS	124
	CULVERT	SD
W	WATER	W
S	SEWER	S
SD	STORM DRAIN	SD
UGE	UNDERGROUND ELEC. & TEL.	UGE&T
OHE	OVERHEAD ELEC. & TEL.	OHE&T
	GATE VALVE	
	UTILITY POLE	
	MANHOLE	
	POTABLE WELL	
	WETLANDS	
	EDGE WETLAND	
	SIGN	
	BENCHMARK	
	SPOT GRADE	
	CHAIN LINK FENCE	
	RIPRAP	
	STOCKADE FENCE	
	ZONE LINE	

SITE PREPARATION NOTES

1. EXISTING CONDITIONS BASED ON TOPOGRAPHIC SURVEY COMPLETED BY FOUR POINTS ASSOCIATES DATED 1/13/16. FIELD CONDITIONS MAY VARY SLIGHTLY FROM WHAT IS DEPICTED ON THE PLANS.

INSTALL INLET PROTECTION FOR ALL CATCH BASINS WITHIN WORK ZONE CONSISTING OF SILT SACK OR OTHER APPROVED METHODS.

2. THE SITE SHALL BE GRUBBED AS SHOWN ON THE PLANS. EXISTING PAVEMENT SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN A LAWFUL MANNER.

3. KEEP ALL STREETS FREE OF DUST, MUD, AND DEBRIS. SURFACES MUST BE SWEPT CLEAN AT END OF EACH WORK DAY AND OTHER TIMES AS REQUIRED TO MINIMIZE TRACKING OF MUD AND CREATION OF DUST. INSTALL STABILIZED CONSTRUCTION ENTRANCE AT PRIMARY ACCESS ROUTE ONTO LANCASTER STREET AND MAINTAIN AS REQUIRED THROUGHOUT CONSTRUCTION.

4. REMOVAL OF EXISTING BUILDING BY OTHERS UNDER SEPARATE CONTRACTS WITH THE OWNER PRIOR TO CONSTRUCTION. BUILDING REMOVAL WORK SHALL INCLUDE COMPLETE DEMOLITION OF ALL ABOVE-GRADE STRUCTURES AND FOUNDATIONS, DISPOSAL OF DEMOLITION WASTE GENERATED, AND DISCONNECTION OF ELECTRICAL, WATER, SEWER, AND GAS SERVICE TO THE BUILDING.

5. CONTRACTOR SHALL INSTALL ALL EROSION CONTROL MEASURES IN ACCORDANCE WITH THE EROSION AND SEDIMENTATION CONTROL NOTES AND DETAILS.

Project Name:

23 Ocean Ave
Portland, Maine

Owner:
Steven & Roberta Cope
172 Concord Street
Portland, Maine 04103

Consultants:

Architect
Kevin Moquin, Architect
Hammond Street
Portland, Maine 04104
207.615-6421

Lanscape Architects
Carroll Associates
217 Commercial St.
Portland, ME 04101
207.772.1552

Civil Engineer
Ransom Consulting
400 Commercial St.
Portland, ME 04101
207.772.2891

Drawing Set:

No.	Date	Revision
1	12–14–16	FOR PERMIT

Drawing Set:
PERMITTING

Drawn: PAB
Checked: MAP
Approved: PC

LICENSED LANDSCAPE ARCHITECT PATRICK J. CARROLL NO. 127 STATE OF MAINE

Drawing Title:
SITE PREPARATION PLAN

Job Number:
File:
Date: 09–02–2016 Scale: AS SHOWN

Drawing Number:
L-1.0

© 2016 CARROLL ASSOCIATES