PRINTED: Dec 14, 2016

PLAN NORTH

SPREAD FOOTING SCHEDULE				
TYPE	LENGTH	WIDTH	DEPTH	REINFORCING
F4	4'-6"	4'-6"	1'-0"	(6)-#5's BOTT, EW
F6	6'-0"	6'-0"	1'-4"	(7)-#5's BOTT, EW
F11	11'-6"	11'-6"	2'-0"	(13)-#5's TOP & BOTT, EW

NOTES:
1. SEE S2.0 FOR TYPICAL SLAB-ON-GRADE AND TYPICAL WALL REINFORCING DETAILS.
2. REFERENCE TOP OF SLAB ELEVATION = 43'-7½"
3. "FX" DENOTES FOOTING TYPE, SEE SCHEDULE ON THIS SHEET FOR INFORMATION.
4. AT HOLD DOWN LOCATIONS (SEE LEGEND) PROVIDE SIMPSON HDU11-SDS 2.5 W/ 1"ø THREADED ROD W/9" MIN EMBEDMENT & HILTI HIT-HY 200 EPOXY ADHESIVE.

PLAN LEGEND
- BEARING WALL
- SHEAR WALL
- BEAM
- HSS COLUMN
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

FOUNDATION PLAN

SCALE: 1/4"=1'-0"

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
Kevin Moquin
Architect
PORTLAND, ME
207.615.6421

STATE OF MAINE
ERIC DUBE
No. 12630
LICENSED
PROFESSIONAL ENGINEER

23 OCEAN
23 OCEAN AVE
PORTLAND, ME
PROPOSED BUILDING

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
A	ISSUED FOR REVIEW	CD	ED	11-2-16
B	ISSUED FOR PERMIT	CD	ED	12-14-16

SHEET TITLE:
FOUNDATION PLAN

DESIGNED:	ED
DRAWN:	CD
DATE:	9-14-16
PROJECT NUMBER:	16-063

S1.0