


**NOTES**

- Existing 28" x 55" doublehung window on north wall of kitchen replaced with 39" x 39" double casement, U-Factor: 0.28
- Existing 36" x 36" sliding window on west wall of kitchen is removed
- Existing 2'8" x 6'8" exterior door on west wall of kitchen is replaced with 3' x 6'8" exterior door
- New door opening will be shifted ~2' to the south
- Both window and door will be framed with 3.25" x 5.5" LVL header
- Sink, dish washer, refrigerator, range, and range hood will all move from existing location
- Add R13 insulation to existing exterior wall cavity
- Existing entry stoop will be removed and replaced with new side and rear deck (see Deck Framing Detail sheet S-503)

Scale 1' = 1/4"



31' 11"

23' 10 1/2"