

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

HOME INVESTMENT LLC

Located at

732 FOREST AVE

PERMIT ID: 2017-01117

ISSUE DATE: 10/06/2017

CBL: 130 H017001

has permission to **Interior alterations - demolish 3 story rear section, build open 3 story covered porch with stairs, remove internal egress stair, rebuild 1st floor front porch (same footprint) & add 2nd & 3rd floor porches - (internal demolition under permit 2017-00666)**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.

A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ Jason Grant

/s/ Jeanie Bourke

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Six dwelling units

Building Inspections

Use Group: R-2 Type: VB
Residential apartments
NFPA 13R sprinkler system
ENTIRE
MUBEC/IBC 2009

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703
or email: buildinginspections@portlandmaine.gov

**Check the Status of Permit or Schedule an Inspection at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

REQUIRED INSPECTIONS:

Setbacks and Footings Prior to Pouring
Close-in Plumbing/Framing w/Fire & Draft Stopping
Electrical Close-in w/Fire & Draftstopping
Final - Commercial
Final - Electric
Final - Fire
Framing Only

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

City of Portland, Maine - Building or Use Permit		Permit No: 2017-01117	Date Applied For: 07/11/2017	CBL: 130 H017001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Six residential dwelling units	Proposed Project Description: Interior alterations - demolish 3 story rear section, build open 3 story covered porch with stairs, remove internal egress stair, rebuild 1st floor front porch (same footprint) & add 2nd & 3rd floor porches - (internal demolition under permit 2017-00666)			
Dept: Zoning Status: Approved w/Conditions Reviewer: Ann Machado Approval Date: 07/20/2017 Note: B-2c zone Ok to Issue: <input checked="" type="checkbox"/> building had fire on 8/30/2016 - existing rear section (majority enclosed) was 12' deep x 22' wide - proposed 3 story porch with egress is 8' deep by 22'10" wide - OK - no minimum setback for front yard so 2nd & 3rd floor porches can be added Conditions: 1) This property shall remain a six family dwelling. Any change of use shall require a separate permit application for review and approval. 2) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.				
<hr/> Dept: Building Inspecti Status: Approved w/Conditions Reviewer: Jeanie Bourke Approval Date: 10/05/2017 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions: 1) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process. 2) Window sills in locations more than 72 inches from finished grade shall be a minimum of 24 inches above the finished floor of the room, unless a window fall prevention devices is installed in accordance with section IRC Sec. R612.3 or IBC Sec. 1405.13.2. 3) Hardwired photoelectric interconnected battery backup smoke detectors shall be installed in all sleeping rooms, protecting outside these rooms, and on every level. The same is required for existing buildings undergoing alterations, hard wired to the electrical system. Interconnection is required, where permanent wiring is feasible, which shall be verified upon inspection. 4) All penetrations shall maintain the fire resistance rating of walls and ceilings with approved firestop materials, including electrical fixtures and exhaust vents per IBC Sec. 713 and IRC Sec. R302.4 5) Carbon Monoxide (CO) alarms shall be installed in each area within or giving access to sleeping rooms. That detection must be powered by the electrical service (plug-in or hardwired) in the building and battery. 6) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				
<hr/> Dept: Fire Status: Approved w/Conditions Reviewer: Jason Grant Approval Date: 09/14/2017 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions: 1) City of Portland Code Chapter 10 section 10-3 (L) all residential occupancies, and all new multiple occupancies containing attached parking structures or fuel burning appliances shall be protected in accordance with NFPA 720, Standard for the Installation of Carbon Monoxide (CO) Detection and Warning Equipment, 2009 edition. Detectors shall be provided in the following areas. 1. Outside each separate sleeping area, in the immediate vicinity of the sleeping areas 2. On each level of the dwelling unit, including basements but excluding attics and crawl spaces.				

- 2) City of Portland Code Chapter 10 section 10-3 (i) all new smoke alarm must use photoelectric technology. In existing apartment building smoke detectors must be powered by the buildings electrical service and must have a secondary power source (battery). Smoke Alarms shall be installed per NFPA 101 2009 section 9.6.2.10. Detectors are required to be installed in the following locations
1. Inside all sleeping rooms.
 2. Outside each separate sleeping area, in the immediate vicinity of the sleeping areas
 3. On each level of the dwelling unit, including basements but excluding attics and crawl spaces.
- In new construction per NFPA 101 2009 section 9.6.2.10.3 where 2 or more smoke detectors are required within a dwelling unit they shall be arranged so that the operation of any smoke alarm shall cause the alarm of all smoke alarms within the dwelling unit.
- 3) Fire extinguishers are required per NFPA 1 (2009 Edition) Table 13.6.2. The quantity, size, type and location shall be in accordance with NFPA 1, 13.6.8.
For light or ordinary hazard buildings, a 2-A rated extinguisher (5lb. Dry Chemical Ext.) is required no more than 75 feet of travel distance from anywhere in the building and at least 1 extinguisher per story.
- 4) City of Portland Code Chapter 10 section 10-18 (h) All structures with a life safety signaling system (fire alarm) or a fire suppression system (sprinkler) shall have a Knox Box. All keys required to access the building and operate the fire alarm or suppression system shall be maintained in the box.
- 5) This review has determined that your project requires fire sprinkler system. A separate City of Portland Water-Based Fire Suppression System Permit is required for all new sprinkler systems, including standpipe systems, and sprinkler work effecting more than 20 heads. This review does not include approval of system design or installation.
Sprinkler system installation shall comply with 2016 NFPA 13R.
- 6) All construction shall comply with City Code, Chapter 10.
All construction shall comply with 2009 NFPA 101 Life Safety Code, Chapter # 43 and other applicable chapters
All construction shall comply with 2009 NFPA 1, Fire Code.
This review and approval by the AHJ shall not relieve the applicant of the responsibility of compliance with this Code. NFPA 1 (section 1.14.4).
All means of egress to remain accessible at all times.
If applicable, all outstanding code violations shall be corrected prior to final inspection.