

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND BUILDING PERMIT



**This is to certify that**

CLARK BRIAN T & DEBORAH L CRIDEN-CLARK  
JTS/Portland Arts and Tec High School

**Located at**

7 FLORENCE ST

**PERMIT ID:** 2013-01015    **ISSUE DATE:** 05/29/2013    **CBL:** 131 M005001

has permission to **Replace existing Front Steps**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Jon Rioux

**Fire Official**

**Building Official**

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY  
THERE IS A PENALTY FOR REMOVING THIS CARD**

*Approved Property Use - Zoning*  
Single Family Dwelling

*Building Inspections*

*Fire Department*

**BUILDING PERMIT INSPECTION PROCEDURES**  
Please call 874-8703 (ONLY)  
or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

**REQUIRED INSPECTIONS:**

Footings/Setbacks  
Close-in Plumbing/Framing  
Electrical - Residential  
Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

<b>City of Portland, Maine - Building or Use Permit</b>		<b>Permit No:</b> 2013-01015	<b>Date Applied For:</b> 05/20/2013	<b>CBL:</b> 131 M005001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
<b>Proposed Use:</b> Single Family Home	<b>Proposed Project Description:</b> Replace existing Front Steps			
<b>Dept:</b> Zoning <b>Status:</b> Approved w/Conditions <b>Reviewer:</b> Marge Schmuckal <b>Approval Date:</b> 05/21/2013 <b>Note:</b> <b>Ok to Issue:</b> <input checked="" type="checkbox"/>				
<b>Conditions:</b>				
1) This property shall remain a single family dwelling. Any change of use shall require a separate permit application for review and approval. 2) Separate permits shall be required for future decks, sheds, pools, and/or garages. Your current application request RESTRICTS the permit to the replacement of the FRONT steps only. A separate permit is required for the replacement of the rear steps. 3) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.				
<b>Dept:</b> Building <b>Status:</b> Approved w/Conditions <b>Reviewer:</b> Jon Rioux <b>Approval Date:</b> 05/24/2013 <b>Note:</b> <b>Ok to Issue:</b> <input checked="" type="checkbox"/>				
<b>Conditions:</b>				
1) R502.6 Bearing. The ends of each joist, beam or girder shall have not less than 1.5 inches of bearing on wood or metal and not less than 3 inches on masonry or concrete except where supported on a 1-inch-by-4-inch ribbon strip and nailed to the adjacent stud or by the use of approved joist hangers. 2) A graspable handrail (34-38 inches in height) shall be provided on at least one side of each continuous run of treads or flight with four or more risers. Fall protection (36 inches) from exterior decks may be required if floor joist are at or above thirty (30) inches from grade. The maximum riser height shall be 7 3/4 inches; the minimum tread depth shall be 10 inches. 3) Frost protection must be installed per the enclosed detail as discussed w/owner/contractor (at least 4' from grade). 4) Separate permits are required for any electrical: plumbing, sprinkler, fire alarm, HVAC systems, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				