



W4	01	UL# XXXX RATING 00 MINS	<p>5/8" GWB-AR PTD (1) LAYER EACH SIDE 2 X 4 STUDS @ 16" O.C. ACOUSTIC BATT INSULATION</p> <p>NOTE: EXTEND WALL TO UNDERSIDE OF CEILING ABOVE. ATTACH TO EXISTING FRAMING. SEAL ALL OPENINGS INCLUDING COLLAR THE PENETRATION POINTS.</p>
W4	02	UL# XXXX RATING 00 MINS	<p>5/8" GWB-AR PTD (1) LAYER EACH SIDE 2 X 4 STUDS @ 16" O.C.</p> <p>NOTE: FRAME TO 4" AFF ON THE FLOOR SIDE OF RAMP. HALF WALL SUPPORT POST AT SOUTH END OF WALL.</p>
W4	03	UL# XXXX RATING 00 MINS	<p>ALIGN INFLILL WALL @ LOCATIONS OF DOOR/ FRAME REMOVAL 2 X 4 STUDS @ 16" O.C.</p> <p>NOTE: ADD STRAPPING AS NECESSARY TO MATCH THICKNESS OF EXISTING WALL.</p>
W4	05	UL# U305 RATING 60 MINS	<p>5/8" TYPE X GWB, PTD (1) LAYER @ EACH SIDE 2 X 4 WOOD FRAMING @ 16" O.C. ACOUSTIC BATT INSULATION</p> <p>NOTE: EXTEND WALL TO UNDERSIDE OF FRAMING ABOVE. FIRE SEAL ALL JOINTS AND PENETRATIONS.</p>
W6	01	UL# U305 RATING 60 MINS	<p>5/8" TYPE X GWB, PTD (1) LAYER @ EACH SIDE 2 X 6 WOOD FRAMING @ 16" O.C. ACOUSTIC BATT INSULATION</p> <p>NOTE: PROVIDE BLOCKING FOR ELEVATOR INSTALLATION AS REQUIRED.</p>

ROOM NO.	NAME	FLOOR	BASE	FINISH SCHEDULE				CEILING MATERIAL	NOTES
				WALLS NORTH	EAST	SOUTH	WEST		
002	EMR			NEW PTD GWB	NEW PTD GWB	NEW PTD GWB			
101	VESTIBULE		WALK OFF MAT (WOM)	REPAINT	REPAINT	REPAINT	REPAINT	REPAINT	
102	HOLD/PUBLIC COMPUTING		PTD WOOD BASE	REPAINT	REPAINT	REPAINT	REPAINT	NEW PTD GWB	NOTE 1, 2, 3
102B	RAMP		PTD WOOD BASE	REPAINT	REPAINT	REPAINT	REPAINT	NEW PTD GWB	NOTE 1, 3, 4
103	TOILET		EXIST. TO REMAIN	EXIST.	EXIST.	EXIST.	EXIST.	EXIST.	NOTE 8
104	STAIR		EXIST. TO REMAIN	EXIST.	REPAINT	REPAINT	REPAINT	REPAINT	NOTE 5
106A	PROCESSING		CARPET 1	RUBBER	REPAINT/PTD GWB	PTD GWB	PATCH AND REPAINT	REPAINT	NOTE 1, 4
106B	OFFICE		CARPET 1	RUBBER	NEW PTD GWB	REPAINT	NEW PTD GWB	REPAINT	NOTE 1, 4
108	CIRCULATION		CARPET 2	RUBBER	REPAINT	REPAINT	REPAINT	REPAINT	NOTE 1, 6
109A	NEW ADULT FICTION		CARPET 1	RUBBER	REPAINT	REPAINT	REPAINT	REPAINT	NOTE 1, 6, 7
109B	YOUNG ADULT(?)		CARPET 1	RUBBER	REPAINT	REPAINT	REPAINT	REPAINT	NOTE 1, 6, 7
110	CHILDRENS		CARPET 1	RUBBER	REPAINT	REPAINT	REPAINT	REPAINT	NOTE 1, 6, 7
111	YOUTH SERVICES		EXIST. TO REMAIN	EXIST. TO REMAIN	REPAINT	REPAINT	REPAINT	REPAINT	
112	HALL		CARPET 1	RUBBER	NEW PTD GWB	REPAINT	REPAINT	REPAINT	NOTE 1
113	ELEVATOR		WOM						
201	UPPER STAIR HALL		CARPET 1	RUBBER COVELESS	NEW PTD GWB	REPAINT	NEW PTD GWB	REPAINT	NOTE 6
202	ADULT NON-FICTION		EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	
203	UPPER HALL		EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	
204	CORRIDOR		EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	
205	STAFF TOILET		EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	
206	STAFF ROOM		EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	
207	COLLECTION		EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	EXISTING TO REMAIN	

GENERAL NOTES:
1. PATCH AND REPAIR WALLS AS NECESSARY AFTER REMOVAL OF CASEWORK AND SHELVING.
2. PATCH FLOOR SHEATHING AS NECESSARY AFTER REMOVAL OF CASEWORK.
3. AT EXISTING EXPOSED STRUCTURE (PTD TJ'S) INSULATE CAVITY WITH FIBERGLASS BATT INSULATION, (12") STRAP CEILING, ADD 5/8" GYPSUM BOARD CEILING, PAINT. NEW ELECTRICAL LINES TO BE FULLY CONCEALED.
4. NEW FLOOR FRAMING. PROVIDE SHEATHING AND SUBFLOOR FOR NEW CARPET.
5. AT EXISTING STAIR/ CHAIR LIFT TO BE REMOVED, PATCH WALL AND WINDOW TRIM TO MATCH ADJACENT FINISHES.
6. PATCH WALLS, FLOOR AND CEILING AS NECESSARY AFTER DEMOLITION. MATCH ADJACENT FINISHES.
7. AT CEILINGS TO REMAIN, SAND, PREP AND REMOVE PEELING PAINT, PRIOR TO NEW FINISHES.
8. REPAIR DOOR, ALL SIDES, TYP.

REFERENCES:

DESIGNED BY: AKS
DRAWN BY: KC
CHECKED BY: AKS
SCALE: AS SHOWN
DATE: 10/16/15

SCOTT R. SIMONS
NO. 2034
STATE OF MAINE

PORTLAND PUBLIC LIBRARY
BURBANK BRANCH

377 Stevens Avenue
Deering Center
Portland, Maine 04103

CITY OF PORTLAND, MAINE
Addition + Renovation for
The Burbank Branch Library
ISSUED FOR BIDDING

FIRST FLOOR PLAN

SHEET # **A101**
PLAN NUMBER

LDD PROJECT NAME: N/A
DRAWING NAME: N/A
FIELD BOOK USED: N/A

Scott Simons Architects
75 York Street, Portland, Maine 04101
www.scottsimonsarchitects.com
207.772.4656

424 Fore Street
Portland, Maine 04101
Phone: 207.842.2860
Fax: 207.842.2828
www.cascobayengineering.com