

50 ALBA ST
PORTLAND, ME 04103

50 ALBA ST
PORTLAND, ME 04103

(1/4" = 1')

DECK ELEVATION (REAR)

EXISTING HOUSE

EXISTING REAR ENTRY DOOR

HANDRAIL HEIGHT 36"
w/ 2x2 BALUSTERS
4" O.C.

STAIR RAIL GRASPABLE
HANDRAIL B/T 34-38"

STAIR RISE 7 1/4"
RUN 11"

2-2x12 @
3'

4x4 POSTS
w/ BRACKETS

10" SONOTUBES
CONCRETE @ 4' W/ FOOTING

