WINDOW SCHEDULE												
				FRAME SIZE			DETAILS					
TYPE	MANUF.	MODEL	OPERATION	WIDTH	HEIGHT	JAMB	HEAD	JAMB	SILL	SCREEN	GLAZING	NOTES
A	INTEGRITY	WOOD-ULTREX SERIES: ICA3247 E	CASEMENT	2'-9"	3'-11 5/8"	VIF	--	--	--	--	INSUL W/ARGON	MEETS EGRESS REQUIREMENTS
B	INTEGRITY	WOOD-ULTREX SERIES: IAWN2523	AWNING	2'-1"	1'-11 5/8"	VIF	--	--	--	--	INSUL W/ARGON	

NOTES:
1. GENERAL CONTRACTOR SHALL CONFIRM ALL JAMB DEPTH DIMENSIONS PRIOR TO PLACING THE WINDOW ORDER.
2. ALL GLASS TO BE TEMPERED AS REQUIRED BY CODE.
3. ALL SIZES SHOWN ARE FRAME SIZES. ALLOW 1" EXTRA IN HEIGHT AND WIDTH FOR ROUGH OPENINGS.



1 NORTH ELEVATION
SCALE: 1/4" = 1'-0"

2 EAST ELEVATION
SCALE: 1/4" = 1'-0"

3 SOUTH ELEVATION
SCALE: 1/4" = 1'-0"

4 WEST ELEVATION
SCALE: 1/4" = 1'-0"

LICENSED ARCHITECT
Matthew Ahlberg
4401
STATE OF MAINE

Inspection Division
Date: 06/02/17

REVISIONS:

PROPOSED EXTERIOR ELEVATIONS

DRAWING TITLE:
A.202

PROJECT NAME:
DONELSON + CALLANAN RENOVATION
91 BRENTWOOD STREET
PORTLAND, MAINE, 04103

DATE OF ISSUE:
MAY 31, 2017

ISSUED FOR:
PERMITTING

SCALE:
1/2" = 1'-0"

BARRETT MADE
HOMES · SPACES · DETAILS

THIS DRAWING IS THE PROPERTY OF BARRETT MADE AND IS NOT TO BE COPIED OR REPRODUCED IN WHOLE OR IN PART. 2017 © BARRETT MADE