




About Redi-Exit
who we are

Contact Us
for all your needs

Product Categories
what you can buy

 **Call us at:**
<(877) 798-9428

Egress Windows - Compact Single Hung In-Swing

Contact Us

Call 877-798-9428 for Price & Delivery

Overview

Details & Specs

Photos & Video

Install Guidelines

REDI-EXIT® Compact Series Single Hung In-swing Egress Windows are designed to meet the IRC Code requirement of 5.7 square feet of clear area and the 20" minimum width & 24" minimum height.

These vinyl double pane Compact Series Single Hung In-swing Egress Windows are typically used in rooms when space to install an egress window is limited or for Basement Egress applications.



These "Made In The U.S.A." Compact Series Single Hung In-swing Egress windows are great for replacement or new construction.

These windows are shipped with a screen for the lower sash.

Compact Series Egress Windows are designed to work with all of REDDCO'S Egress Wells.

These dual function vinyl windows operate in two ways; 1) as a normal single hung window, with the lower sash opening for ventilation; 2) in the event of an emergency, a latch in the corner of the window is opened and the top and bottom sashes hinge into the room like a door for easy escape.

REDI-EXIT® Compact Series Single Hung In-swing Egress Windows are available in four stock sizes; 28" wide x 46" high x 3 1/4" jam depth; 31" wide x 41" high x 3 1/4" jam depth; 35 1/2" wide x 36" high x 3 1/4" jam depth; and 35 1/2" wide x 53 1/2" high x 3 1/4" jam depth, in both right hinged and left hinged configurations.

The 28" wide x 46" high x 3 1/4" jam depth; 31" wide x 41" high x 3 1/4" jam depth Compact Egress Windows are stocked in both Clear Glass and Low-e Glass with Argon Gas Fill.

REDDCO'S egress windows are built with special egress style hinges, that hinge the window open at the inside edge of the window frame.

REDI-EXIT® Compact Series Single Hung In-swing Egress Windows can be special ordered in 1/4" increments to fit any size requirements with the following options: Tempered Glass, Argon Gas Filled, Low-e Glass, Nailing Fins, Obscure Glass, Grids between the glass (Muntins).

An optional Stainless Steel Security Screen and Glass Transom are available for these Egress Windows.

Subtract 7 1/2" from the width and 5" from the height to determine the net clear area of these Egress Windows.

Call REDDCO Incorporated toll free at (877) 798-9428 for Price and Delivery.

Customers who bought Compact Single Hung In-Swing Egress Windows also bought:

larger image