



GENESIS SERIES

**Power Limited Fire Alarm Cable
Part No. 4112**

Description: 16 AWG 4/C SOL FPL-CL2
Compliance: UL Standards 13 & 1424; NEC Articles 725 & 760

Construction:

Conductor 16 AWG Solid Bare Copper
No. of Conductors 4

Insulation

Type Polypropylene
Color Black, Red, Ylw, Grn
Thickness 0.006" nom.
Diameter 0.062" nom.
Lay Length 2.5" nom.

Jacket

Type PVC
Color Red
Thickness 0.015" nom.
Diameter 0.180" nom.
Legend (Ink Print) HONEYWELL P/N 4112 4C16 E175105 (UL) FPL OR CL2 SUN RES 75C (RoHS)
W/O# XXXXXX-XXXXXX XXXXX FT DEVICE/ZONE A B C D E F 1 2 3 4 5 6 7 8 9

Properties:

Temperature Rating -20 to 75 oC
Operating Voltage 300 Volts max.
Capacitance 20 pf/ft nom.
Impedance 81 Ohms nom.
DC Resistance 4.15 Ohms/M' at 20oC
Flame Rating UL 1685 Vertical Tray