



HOT WORK PERMIT

**BEFORE INITIATING HOT WORK, ENSURE PRECAUTIONS ARE IN PLACE!
MAKE SURE AN APPROPRIATE FIRE EXTINGUISHER IS READILY AVAILABLE!**

This Hot Work Permit is required for an operation involving open flames or producing heat and/or sparks. This includes, but is not limited to: Brazing, Cutting, Grinding, Soldering, Thawing Pipe, Torch-Applied Roofing², Cadwelding.

INSTRUCTIONS

- A. Verify precautions listed at right (or do not proceed with the work).
- B. Complete and retain this permit

HOT WORK BEING DONE BY

EMPLOYEE
 CONTRACTOR Foot City Mech.

DATE 8/14/18

LOCATION/BUILDING AND FLOOR
 Address 522 STEVENS AVE.

Location of worksite within building
Basement

Site Phone # 233-0518

After Hours Phone # 233-0518

DESCRIPTION OF JOB/OBJECT
Cutting out a Hot Water Tank

NAME OF PERSON DOING HOT WORK
Cluck Gregg / AW

I verify the above location has been examined, the precautions checked on the Required Precautions Checklist have been taken to prevent fire, and permission is authorized for work.

SIGNED [Signature]

PERMIT EXPIRES	DATE	TIME	
	<u>8/16</u>	<u>5</u>	<u>AM</u> <u>PM</u>

NOTE EMERGENCY NOTIFICATION ON BACK OF FORM.
USE AS APPROPRIATE FOR YOUR FACILITY.

THIS PERMIT IS GOOD FOR ONE DAY ONLY!

Fee Amount \$25.00 Payment Received: N/A

Issued By: City Dock

Katharine Cahoon

REQUIRED PRECAUTIONS CHECKLIST

- Available sprinkler, hose streams, and extinguishers are in service/operable.
- Hot work equipment in good repair.

Requirement within 35ft (11m) of work

- Flammable liquids, dust, lint, and oil deposits removed.
- Explosive atmosphere in area eliminated.
- Floors swept clean.
- Combustible floors wet down, covered with damp sand or fire-resistant sheets.
- Remove other combustibles where possible. Otherwise protect with fire-resistant tarpaulins or metal shields.
- All wall and floor openings covered.
- Fire-resistant tarpaulins suspended beneath work.

Work on walls or ceilings/enclosed equipment

- Construction is noncombustible and without combustible covering or insulation.
- Combustibles on other side of walls moved away. Danger exists by conduction of heat into another area.
- Enclosed equipment cleaned of all combustibles.
- Containers purged or flammable liquids/vapors.

Fire watch /hot work area monitoring

- Fire watch will be provided during and for 30 minutes after work, including any coffee or lunch breaks.
- Fire watch is supplied with suitable extinguishers.
- Fire watch is trained in use of this equipment and in sounding alarm.
- Fire watch may be required for adjoining areas, above, and below.
- Monitor hot work area for 30 minutes after job is completed.

Other Precautions Taken

- Confined space entry permit required.
- Is area protected with smoke or heat detection.
- Ample ventilation to remove smoke/vapor from work area.
- Lockout/tagout required.