

Deering Pavilion					Door Schedule						01/15/2015	
No.	Location	Inches			Door Material	Door Type	Frame Type	Lock Function	Hardware	Label	Notes	
		W	H	T								
Apartment Doors												
A	Apartment Entrance	36	80	1-3/4	SC flush wood	F	HM	Lockset 2	Spring hinges, viewer	20 min.	Viewers at 48 and 60"	
B	Bath	36	80	1-3/4	SC flush wood	F	HM	Privacy 2				
D	Closet	(2) 18	80	1-3/8	HC flush wood	F	Drywall		Bifold			
E	Closet	(4) 12	80	1-3/8	HC flush wood	F	Drywall		Bifold			
First Floor Doors												
101	Lobby to Dining Room	42	84	1-3/4	Aluminum	FG	Alum		Automatic Operator		Horizontal rolling entrance system	
102	Library to Office	36	80	1-3/4	SC flush wood	F	HM	Lockset 1				
103	Deleted											
104	Dining Room to Wellness	36	80	1-3/4	SC flush wood	HG	HM	Lockset 1				
105	Dining Room to Community	42	80	1-3/4	SC flush wood	HG	HM	Lockset 1	Closer			
106	Dining Room to Kitchen	36	80	1-3/4	SC flush wood	NL	HM	Lockset 1			5x20 wired glass lite	
107	Corridor to Janitor	36	80	1-3/4	SC flush wood	F	HM	Storeroom 1	Closer	45 min.		
108	Corridor to Trash	36	80	1-3/4	SC flush wood	NL	HM	Passage 1	Closer	45 min.	5x20 wired glass lite	
109	Corridor to Corridor	36	80	1-3/4	Exist hollow metal	NL	HM	Exist passage	St Steel protection plate, mag holder, closer	45 min.	5x20 wired glass lite	
110	Corridor to Maintenance	36	80	1-3/4	SC flush wood	NL	HM	Storeroom 1	Closer	45 min.	5x20 wired glass lite	
111	Corridor to Laundry	36	80	1-3/4	SC flush wood	HG	HM	Passage 1	Closer, kickplate, mag holder	45 min.	24X30 wired glass lite	
112	Corridor to Activity	36	80	1-3/4	SC flush wood	HG	HM	Passage 1	Closer, kickplate, mag holder	45 min.	24X30 wired glass lite	
113	Activity to Media Room	36	80	1-3/8	SC flush wood	HG	HM	Passage 1	Closer	45 min.		
114	Corridor to Electrical	36	80	1-3/4	SC flush wood	f	HM	Storeroom 1	Closer	45 min.		
115	Elevator Lobby to Office	36	80	1-3/8	SC flush wood	NL	HM	Lockset 1	Closer	45 min.	5x20 wired glass lite	
116	Elevator Lobby to Anteroom	36	80	1-3/4	SC flush wood	F	HM	Lockset 1				
117	Anteroom to Service Coord	36	80	1-3/4	SC flush wood	F	HM	Lockset 1				
Notes:												
1	Provide wall or floor stops at all doors											
2	Provide new locksets keyed into existing masterkey system											
3	Refurbish hardware on existing doors to remain as necessary, except where new is called for.											