



GENERAL NOTES:
ALL WINDOWS AND SURROUNDING TRIM TO BE SCRAPED, REPAIRED AND PAINTED
ALL WINDOW DIMENSIONS TO BE VERIFIED IN FIELD.
WHERE EXISTING WINDOW STOOLS <24" AFF, LIMIT BOTTOM SASH OPENING TO 4"
ALL FROSTED GLAZING IN EXISTING WINDOWS AT NEW UNIT LOCATIONS TO BE REMOVED AND REPLACED WITH CLEAR GLAZING. NEW GLAZING TO MATCH ADJACENT WINDOWS IN COLOR AND THICKNESS.
ALL EXISTING STORM WINDOWS & PLYWOOD TO BE REMOVED UNLESS NOTED OTHERWISE. ALL WINDOWS TO HAVE NEW STORM WINDOWS FOR FULL EXTENT OF GLAZING UNLESS NOTED OTHERWISE.
ALL SPRAY FOAM INSULATION IN CONTACT WITH WINDOW COMPONENTS TO BE LOW EXPANSION
PROVIDE SILL LOCKING MECHANISM AT ALL OPERABLE WINDOWS - REFERENCE SPECIFICATION
PROVIDE SCREENS AT ALL STORM WINDOWS
INSPECT AND REPAIR/REPLACE WINDOW PAN FLASHING WITH LIKE MATERIALS. PROVIDE NEW METAL FLASHING AT NEW WINDOWS.