



FOODSERVICE EQUIPMENT SCHEDULE

WK.	QTY	DESCRIPTION	ELECTRICAL			WATER		WASTE		GAS		STEAM		REMARKS						
			FLAMPS	KW	HP	VOLTS	PHASE	DIRECT	PLUG	COLD	HOT	DIRECT	INDIRECT		SIZE	MBTUH	LBS/HR	PSIG	INLET	RETURN
1	1	MOP SINK																		
2	5	SHELVING UNIT																		
3	1	WORK TABLE W/PASS THRU																		
4	1	RANGE, 4-BURNER																		
5	2	COMBI-OVEN, GAS																		
6	1	REFRIGERATOR, ROLL-IN																		
7	1	REFRIGERATOR, ROLL-IN																		
8	1	FREEZER, ROLL-IN																		
9	4	SHEET PAN RACK																		
10	2	THERM & HOLD CABINET																		
11	—	— SPARE NUMBER —																		
12	—	— SPARE NUMBER —																		
13	—	— SPARE NUMBER —																		
14	1	HAND SINK																		
15	—	— SPARE NUMBER —																		
16	1	DISHWASHER, UNDERCOUNTER																		
17	1	SINK, 3-COMPARTMENT																		
18	1	WASTE REDUCTION SYSTEM																		
19	1	SERVING COUNTER, HEATED MODULE																		
20	1	SERVING COUNTER, COLD FOOD																		
21	—	— SPARE NUMBER —																		
22	1	SERVING COUNTER, CASHIER STAND																		
23	1	SERVING COUNTER, CASHIER STAND																		
24	1	SERVING COUNTER, COLD FOOD																		
25	1	SERVING COUNTER, FLAT TOP																		
26	1	SERVING COUNTER, HOT FOOD																		
27	1	TRAY DISPENSER																		
28	1	TRAY & SILVERWARE STAND																		
29	2	MILK COOLER																		
30	2	CONDIMENT CART																		

- NOTES:
- ELECTRICAL CONTRACTOR TO RUN CONTROL WIRING BETWEEN TANKER AND FREEZER CO-ORDINATE WITH KITCHEN EQUIPMENT CONTRACTOR (K.E.C.)
 - ELECTRICAL CONTRACTOR TO INSTALL SEAL-OFF FITTINGS ON ALL CONDUIT PENETRATING WALK-IN COOLER AND FREEZER.
 - ELECTRICAL CONTRACTOR TO PROVIDE 115 VOLT W/P RECEPTACLE IN FREEZER FOR DRAIN LINE HEAT TAPE, HEAT TAPE FURNISHED AND INSTALLED BY K.E.C.
 - PLUMBING CONTRACTOR TO INSTALL VACUUM BREAKER IN COLD WATER LINE TO DISPOSER.
 - OTHER EQUIPMENT CONTRACTORS TO PROVIDE GAS REGULATING VALVES FOR ALL GAS OPERATED KITCHEN EQUIPMENT.
 - FLOOR DRAIN REQUIRES FLOW RATE OF 5 G.P.M.
 - PLUMBING CONTRACTOR TO INSTALL ALL DRAINS AND FAUCETS SUPPLIED BY KITCHEN EQUIPMENT CONTRACTOR.
 - PLUMBING CONTRACTOR TO FURNISH AND INSTALL ALL INDIRECT DRAIN INTERTRIP TO FLOOR DRAINS.
 - PLUMBING CONTRACTOR TO INSTALL GAS REGULATORS ON ALL GAS EQUIPMENT; REGULATORS BY K.E.C.
 - PLUMBING CONTRACTOR TO IGNITE ALL GAS PLOTS AND DEMONSTRATION OF EQUIPMENT.
 - ELECTRICAL CONTRACTOR TO INTERMEDIATE SOUNDO VALVE AND CONTROL PANEL TO DISPOSER.
 - GENERAL CONTRACTOR TO PROVIDE ALL REQUIRED WALL BRACING AS DIRECTED BY K.E.C.
 - GENERAL CONTRACTOR TO PROVIDE ALL REQUIRED SLEEVES THROUGH BUILDING FOR REMOTE REFRIGERATION LINES; REFRIGERATION LINES BY K.E.C.

TJM Consulting, Inc.
 273 Main Street, Suite 5
 Yarmouth, Maine 04096

REV.	DESCRIPTION	DATE
0		00.00.00
PROGRESS PRINTS		
11-05-08		
CURRENT ISSUE STATUS:		

WBRC
 ARCHITECTS - ENGINEERS
 DANFORTH, MAINE 04046
 SAUNDERS, FLORENCE 04075-280

PROJECT: OCEAN AVENUE ELEMENTARY SCHOOL
 PORTLAND, ME

SHEET TITLE: FOODSERVICE EQUIPMENT FLOOR PLAN AND SCHEDULE

SCALE: 1/4" = 1'-0"

DATE: 11-05-08

DRAWN BY: TJM

CHECKED BY: MEJ