Inspections Division
Date: 08/15/16

798 Forest Ave, ID Sign Replacement Project

Total square foot of sign to be removed:
17.5 square feet (single side)
Total square foot of sign proposed for installation:
16.75 square feet / side
Note:
Upper neon sign has been designed in shape, size and essence of the original ID sign

798 Forest Ave

Sign Permit Application
070516

Description:
The electrified sign is to be attached to the existing “original” main ID sign post. Top sign in double sided neon, colors and dimension as shown.
The lower sign will be a, 3 color, LED, Double Sided Display
The signs are to be framed in 3/16 Stainless Steel each sign frame will be separated by (2) 4” sch40 X12” SS, pipe as shown in drawing. A “slip pipe” design will accommodate attachment to existing sign mast in observance of wind and structural loads.