

INPUT DATA (DC)	Model: M250-60-230-S22	Model: M250-72-2LN-S2
Recommended input power (STC)	210 - 310 W	210 - 310 W
Maximum input DC voltage	48 V ^[Note 1]	60 V
Peak power tracking voltage	27 V - 39 V	27 V - 48 V
Operating range	16 V - 48 V	16 V - 60V
Min/Max start voltage	22 V / 48 V	22 V / 48 V
Max DC short circuit current	15 A	15 A
OUTPUT DATA (AC)		
Peak output power	258 W	258 W
Rated output power	250 W	250 W
Rated output current	1.09 A	1.09 A
Nominal voltage	230 V	230 V
Nominal frequency	50.0 Hz	50.0 Hz
Power factor	>0.95	>0.95
Maximum units per 20 A branch circuit	14 (Ph + N), 42 (3Ph + N)	14 (Ph + N), 42 (3Ph + N)
Maximum units per cable section	14 (Ph + N), 24 (3Ph + N)	14 (Ph + N), 24 (3Ph + N)
AC backfeed current to module	0 mA	0 mA
EFFICIENCY		
EN 50530 (EU) efficiency	95.7%	95.7%
Static MPPT efficiency (weighted, reference EN50530)	99.6%	99.5%
Night time power consumption	0.055 W	0.065 W
MECHANICAL DATA		
External operating temperature range (ambient)	-40°C to +65°C	
Internal operating temperature range	-40°C to +85°C	
Enclosure environmental rating	Outdoor - IP67	
Connector type	MC4	
Dimensions (WxHxD)	179 mm x 217 mm x 28 mm (with bracket)	
Weight	1.66 kg	
Cooling	Natural convection - No fans	
FEATURES		
Compatibility	60-cell PV Modules ^[Note 2]	60- or 72-cell PV Modules
Communication	Power line communication	
Monitoring	Enlighten Manager and MyEnlighten monitoring options	
Transformer design	High frequency transformers, galvanically isolated	
Compliance	AS4777, C10/11, CEI_0-21, EN50438, EN62109-1, EN62109-2, ERDF-NOI-RES_13E_V5, G59/2, G83/2, VDE-0126-1-1 + A1, VDE AR-N 4105	
Automatic disconnect	Automatic disconnect according to OVE / ÖNORM E 8001-4-712	

Note 1: Recommended maximum DC operating input voltage. The M250-60-230-S22 may be used with PV modules with Voc up to 51 V under limited circumstances. Contact Enphase Energy technical support for details and approval.

Note 2: Compatibility may be extended to modules with higher cell counts under limited circumstances. Contact Enphase Energy technical support for details and approval.

To learn more about Enphase microinverter technology, visit enphase.com/au.

