

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT

This is to certify that

BECOTTE CLAIRE E & WILLIAM W HARRISON
JTS/Dodge Oil

Located at

21 MACKWORTH ST

PERMIT ID: 2013-01934

ISSUE DATE: 09/11/2013

CBL: 139 D001001

has permission to **HVAC; install Carlin EZ Gas Burner in existing location etc.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Jon Rioux

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Close-in Plumbing/Framing

Electrical - Residential

Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2013-01934	Date Applied For: 08/27/2013	CBL: 139 D001001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Single Family	Proposed Project Description: HVAC; install Carlin EZ Gas Burner in existing location etc.			
Dept: Zoning Status: Approved Reviewer: Marge Schmuckal Approval Date: 09/09/2013		Ok to Issue: <input checked="" type="checkbox"/>		
Note:				
Conditions:				
Dept: Building Status: Approved w/Conditions Reviewer: Jon Rioux Approval Date: 09/10/2013		Ok to Issue: <input checked="" type="checkbox"/>		
Note:				
Conditions:				
1) M1804.2.6 Mechanical draft systems. Mechanical draft systems shall be installed in accordance with their listing, the manufacturer's installation instructions and, except for direct vent appliances, the following requirements:				
<ul style="list-style-type: none"> •The vent terminal shall be located not less than 3 feet above a forced air inlet located within 10 feet. •The vent terminal shall be located not less than 4 feet below, 4 feet horizontally from, or 1 foot above any door, window or gravity air inlet into a dwelling. •The vent termination point shall not be located closer than 3 feet to an interior corner formed by two walls perpendicular to each other. •The bottom of the vent terminal shall be located at least 12 inches above finished ground level. •The vent termination shall not be mounted directly above or within 3 feet horizontally of an oil tank vent or gas meter. •Power exhauster terminations shall be located not less than 10 feet from lot lines and adjacent buildings. 				
2) A Carbon Monoxide (CO) alarm shall be installed in each area within or giving access to bedrooms. That detection must be powered by the electrical service (plug-in or hardwired) in the building and battery.				
3) Separate permits are required for any electrical: plumbing, sprinkler, fire alarm, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				
4) The installation must comply with UL, the Manufacturers' Listing, MUBEC (IRC, 2009), and State of Maine Gas Regulations.				
Dept: Fire Status: Not Applicable Reviewer:		Approval Date: 09/09/2013		
Note:		Ok to Issue: <input type="checkbox"/>		
Conditions:				