



## SolarEdge Single Phase Inverters

For North America

SE3000A-US / SE3800A-US / SE5000A-US / SE6000A-US /  
SE7600A-US / SE10000A-US / SE11400A-US



INVERTERS

### The best choice for SolarEdge enabled systems

- Integrated arc fault protection for NEC 2011 690.11 compliance
- Rapid shutdown for NEC 2014 690.12
- Superior efficiency (98%)
- Small, lightweight and easy to install on provided bracket
- Built-in module-level monitoring
- Internet connection through Ethernet or Wireless
- Outdoor and indoor installation
- Fixed voltage inverter, DC/AC conversion only
- Pre-assembled Safety Switch for faster installation
- Optional – revenue grade data, ANSI C12.1



# Single Phase Inverters for North America

SE3000A-US / SE3800A-US / SE5000A-US / SE6000A-US /  
SE7600A-US / SE10000A-US / SE11400A-US

	SE3000A-US	SE3800A-US	SE5000A-US	SE6000A-US	SE7600A-US	SE10000A-US	SE11400A-US		
<b>OUTPUT</b>									
Nominal AC Power Output	3000	3800	5000	6000	7600	9980 @ 208V 10000 @ 240V	11400	VA	
Max. AC Power Output	3300	4150	5400 @ 208V 5450 @ 240V	6000	8350	10800 @ 208V 10950 @ 240V	12000	VA	
AC Output Voltage Min.-Nom.-Max. <sup>(1)</sup> 183 - 208 - 229 Vac	-	-	✓	-	-	✓	-		
AC Output Voltage Min.-Nom.-Max. <sup>(1)</sup> 211 - 240 - 264 Vac	✓	✓	✓	✓	✓	✓	✓		
AC Frequency Min.-Nom.-Max. <sup>(1)</sup>	59.3 - 60 - 60.5							Hz	
Max. Continuous Output Current	12.5	16	24 @ 208V 21 @ 240V	25	32	48 @ 208V 42 @ 240V	47.5	A	
GFDI Threshold	1							A	
Utility Monitoring, Islanding Protection, Country Configurable Thresholds	Yes							Yes	
<b>INPUT</b>									
Maximum DC Power (STC)	4050	5100	6750	8100	10250	13500	15350	W	
Transformer-less, Ungrounded	Yes								
Max. Input Voltage	500							Vdc	
Nom. DC Input Voltage	325 @ 208V / 350 @ 240V							Vdc	
Max. Input Current <sup>(2)</sup>	9.5	13	16.5 @ 208V 15.5 @ 240V	18	23	33 @ 208V 30.5 @ 240V	34.5	Adc	
Max. Input Short Circuit Current	45							Adc	
Reverse-Polarity Protection	Yes								
Ground-Fault Isolation Detection	600k $\Omega$ Sensitivity								
Maximum Inverter Efficiency	97.7	98.2	98.3	98.3	98	98	98	%	
CEC Weighted Efficiency	97.5	98	97 @ 208V 98 @ 240V	97.5	97.5	97 @ 208V 97.5 @ 240V	97.5	%	
Nighttime Power Consumption	< 2.5						< 4	W	
<b>ADDITIONAL FEATURES</b>									
Supported Communication Interfaces	RS485, RS232, Ethernet, ZigBee (optional)								
Revenue Grade Data, ANSI C12.1	Optional <sup>(3)</sup>								
Rapid Shutdown – NEC 2014 690.12	Yes								
<b>STANDARD COMPLIANCE</b>									
Safety	UL1741, UL1699B, UL1998, CSA 22.2								
Grid Connection Standards	IEEE1547								
Emissions	FCC part15 class B								
<b>INSTALLATION SPECIFICATIONS</b>									
AC output conduit size / AWG range	3/4" minimum / 16-6 AWG					3/4" minimum / 8-3 AWG			
DC input conduit size / # of strings / AWG range	3/4" minimum / 1-2 strings / 16-6 AWG					3/4" minimum / 1-3 strings / 14-6 AWG			
Dimensions with Safety Switch (HxWxD)	30.5 x 12.5 x 7.2 / 775 x 315 x 184					30.5 x 12.5 x 10.5 / 775 x 315 x 260			
Weight with Safety Switch	51.2 / 23.2		54.7 / 24.7			88.4 / 40.1		in / mm lb / kg	
Cooling	Natural Convection				Natural convection and internal fan (user replaceable)	Fans (user replaceable)			
Noise	< 25				< 50				dB(A)
Min.-Max. Operating Temperature Range	-13 to +140 / -25 to +60 (-40 to +60 version available <sup>(4)</sup> )							°F / °C	
Protection Rating	NEMA 3R								

<sup>(1)</sup> For other regional settings please contact SolarEdge support.

<sup>(2)</sup> A higher current source may be used; the inverter will limit its input current to the values stated.

<sup>(3)</sup> Revenue grade inverter P/N: SExxxxA-US000NNR2 (for 7600W inverter:SE7600A-US002NNR2).

<sup>(4)</sup> -40 version P/N: SExxxxA-US000NNU4 (for 7600W inverter:SE7600A-US002NNU4).



# RoHS