

WINDOW SCHEDULE: (LH/RH FROM OUTSIDE)
 W101 - BATH I: IMPERVIA CASE (LH) 2-4/5-0, RO: 24w x 60h SILL HEIGHT: 24" AFF.
 W102 - OFFICE: IMPERVIA CASE (LH) 2-4/5-0, RO: 28w x 60h SILL HEIGHT: 24" AFF.
 W103 - OFFICE: IMPERVIA AWNING 4-0/2-0, RO: 48w x 24h
 (I03 NOTE: SET NEXT TO W102 WITH 3" FRAMING BETWEEN. SET FLUSH ALONG TOP WITH COMMON HEADER)
 W104 - LAURIE'S BED RM: IMPERVIA AWNING 4-6/2-0, RO: 54w x 24h
 W105 - LAURIE'S BED RM: IMPERVIA 6-0/6-8 GLIDING PATIO DOOR, RO: 72w x 80h
 W106 - LAURIE'S BED RM: IMPERVIA 2-8/6-8 FIXED, RO: 32w x 80h
 W107 - BATH 2: IMPERVIA 6-0/6-8 GLIDING PATIO DOOR, RO: 72w x 80h
 W108 - BATH 2: IMPERVIA 2-8/6-8 FIXED, RO: 32w x 80h
 W109 - MIKE'S BED RM: IMPERVIA AWNING 4-6/2-0, RO: 54w x 24h
 W110 - MIKE'S BEDROOM: IMPERVIA CASE (LH) 2-4/5-0, RO: 28w x 60h SILL HEIGHT: 24" AFF
 W111 - MIKE'S BEDROOM: IMPERVIA CASE (RH) 2-4/5-0, RO: 28w x 60h SILL HEIGHT: 24" AFF
 W112 - OFFICE: IMPERVIA CASE (LH) 2-4/5-0, RO: 28w x 60h SILL HEIGHT: 24" AFF.
 W113 - OFFICE: IMPERVIA AWNING 4-0/2-0, RO: 48w x 24h
 (I13 NOTE: SET NEXT TO W102 WITH 3" FRAMING BETWEEN. SET FLUSH ALONG TOP WITH COMMON HEADER)
 W114 - DEN: IMPERVIA CASE (LH) 1-6/4-0, RO: 18w x 48h
 (W114 NOTE: AC UNIT TO BE REMOVED, SET FRAME TOP FLUSH WITH DOOR SO TRIM IS ALIGNED)
 W115 - DEN: IMPERVIA 6-0/6-8 GLIDING PATIO DOOR, RO: 72w x 80h. USE EXISTING RO.
 W116 - LIVING RM: PATIO DOOR TO MATCH EXISTING RO. FIELD VERIFY.
 (W116 NOTE: FIELD VERIFY OUTSWING LEFT HINGE (AS VIEWED FROM OUTSIDE.)
 SPEC PRIOR TO ORDER. FIELD VERIFY RO: OF 37" W X 80" H
 W117 - LIVING ROOM: IMPERVIA AWNINGS: REPLACE EXISTING TRIPLE AWNING WINDOWS. MULL TWO AWNINGS TOGETHER TO MATCH EXISTING RO.

