



17 CHESTNUT STREET
 PORTLAND, ME 04101
 PHONE: 207.761.9500
 FAX: 207.761.9595
 design@alpharchitects.com

COPYRIGHT
 Release or reproduction of the contents of
 this document is not permitted without
 the written permission of ALPHA ARCHITECTS



Walton Street 3 Unit

15 Walton Street
 Portland Maine 04103

JOB: 11024

ISSUE DATE	08-25-11
PRELIM.	Not Rec'd
CDs	10-12-11
REV. 1	-
REV. 2	-
PRINT	10-12-11

DOOR & FINISH SCHEDULES
A5.1

ROOM FINISH SCHEDULE

LEVEL	ROOM NO.	ROOM NAME	FLOOR	BASE	WALLS	CEILING	REMARKS
BASEMENT	001	STORAGE	CLEAN	NONE	CLEAN RIM JOISTS AND BRICK WALLS	BROOM CLEAN	BROOM CLEAN
	002	HALL	CLEAN	-	CLEAN RIM JOISTS AND BRICK WALLS	BROOM CLEAN	BROOM CLEAN
	003	STORAGE	CLEAN	-	CLEAN RIM JOISTS AND BRICK WALLS	BROOM CLEAN	BROOM CLEAN
FIRST FLOOR (UNIT 1)	101	FOYER	ST1/V1	PTD 6"-SEE A12	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	-
	102	KITCHEN	C11	PTD 6"-SEE A12	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	PROVIDE SOLID BLOCKING FOR CABINETS
	103	CLOSET	C11	PTD 4"-NO CAP	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	1-R00, 2- 1x12 w 1x2 HARDWOOD NOSING, PTD SEMI GLOSS
SECOND FLOOR (UNIT 2)	201	FOYER	ST1/V1	PTD 6"-SEE A12	PTD. GMB- SEMI GLOSS	PTD. GMB- FLAT	-
	202	KITCHEN	C11	PTD 6"-SEE A12	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	PROVIDE SOLID BLOCKING FOR CABINETS
	203	CLOSET	C11	PTD 4"-NO CAP	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	1-R00, 2 SHELVES- 1x12 w 1x2 HARDWOOD NOSING, PTD SEMI GLOSS
THIRD FLOOR (UNIT 3)	301	FOYER	ST1/V1	PTD 6"-SEE A12	PTD. GMB- SEMI GLOSS	PTD. GMB- FLAT	-
	302	KITCHEN	C11	PTD 6"-SEE A12	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	PROVIDE SOLID BLOCKING FOR CABINETS
	303	CLOSET	C11	PTD 4"-NO CAP	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	1-R00, 2 SHELVES- 1x12 w 1x2 HARDWOOD NOSING, PTD SEMI GLOSS
ATTIC LEVEL (UNIT 3)	401	HALL	C2	PTD 6"-SEE A12	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	-
	402	CLOSET	C2	PTD 4"-NO CAP	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	1-R00, 2 SHELVES- 1x12 w 1x2 HARDWOOD NOSING, PTD SEMI GLOSS
	403	CLOSET	C2	PTD 4"-NO CAP	PTD. GMB- EGGS SHELL	PTD. GMB- FLAT	1-R00, 2- 1x12 w 1x2 HARDWOOD NOSING, PTD SEMI GLOSS

DOOR AND FRAME SCHEDULE

32 ELLSWORTH STREET

DOOR NO.	LOCATION	DOOR			FRAME MAT.	FIRE RATING	THERMSE.	UNDER CUT	WEATHER STRIP	SP. BR. 18"	REMARKS	
		TYPE	GLASS	GLASS								
100a	BESMENT	30	68	C	-	METAL-40	60	Y	-	Y	E	KICK PLATE, SILENCERS, BALL BEARING HINGES, DOOR STOP
100b	UNIT 1 ENTRY	30	68	C	-	METAL-40	60	Y	-	Y	E	SILENCERS, FEET, BALL BEARING HINGES, KICK PLATE, DOOR STOP, CLOSER
100c	CLOSET	24	68	D	-	WOOD	-	-	1"	-	G	
100d	BEDROOM 1	28	68	D	-	WOOD	-	-	1"	-	F	DOOR STOP
100e	CLOSET	50	68	D	-	WOOD	-	-	1"	-	G	SLIDER
110a	LINEN	20	68	D	-	WOOD	-	-	1"	-	G	SLIDER
110b	BATH	26	68	D	-	WOOD	-	-	1"	-	F	PRIVACY, DOOR STOP
110c	IT	12	68	D	-	WOOD	-	-	1.5"	-	G	
113a	BEDROOM 2	28	68	D	-	WOOD	-	-	1"	-	F	DOOR STOP
114a	CLOSET	50	68	D	-	WOOD	-	-	1"	-	S	SLIDER
115a	DECK- BUILDING ENTRY	30	68	A	1/2 TOL	METAL-40	-	-	Y	-	E	KICK PLATE, AUTOLOCK, BALL BEARING HINGES, CLOSER, SILENCERS
200a	UNIT 2 ENTRY	30	68	C	-	METAL-40	60	Y	-	Y	E	SILENCERS, FEET, BALL BEARING HINGES, KICK PLATE, DOOR STOP, CLOSER
200b	UNIT 3 ENTRY	30	68	C	-	METAL-40	60	Y	-	Y	E	SILENCERS, FEET, BALL BEARING HINGES, KICK PLATE, DOOR STOP, CLOSER
200c	CLOSET	24	68	D	-	WOOD	-	-	1"	-	G	
200d	BEDROOM 1	28	68	D	-	WOOD	-	-	1"	-	F	DOOR STOP
200e	CLOSET	50	68	D	-	WOOD	-	-	1"	-	S	SLIDER
200f	BATH	26	68	D	-	WOOD	-	-	1"	-	F	PRIVACY, DOOR STOP
210a	LINEN	20	68	D	-	WOOD	-	-	1"	-	G	SLIDER
210b	BATH	26	68	D	-	WOOD	-	-	1.5"	-	G	
213a	BEDROOM 2	28	68	D	-	WOOD	-	-	1"	-	F	DOOR STOP
214a	CLOSET	50	68	D	-	WOOD	-	-	1"	-	S	SLIDER
215a	DECK	30	68	A	1/2 TOL	METAL-40	-	-	Y	-	E	KICK PLATE, BALL BEARING HINGES, CLOSER, SILENCERS
300a	CLOSET	24	68	D	-	WOOD	-	-	1"	-	G	
300b	BEDROOM 1	28	68	D	-	WOOD	-	-	1"	-	F	DOOR STOP
300c	CLOSET	50	68	D	-	WOOD	-	-	1"	-	S	SLIDER
310a	LINEN	20	68	D	-	WOOD	-	-	1"	-	G	SLIDER
310b	BATH	26	68	D	-	WOOD	-	-	1"	-	F	PRIVACY, DOOR STOP
310c	IT	12	68	D	-	WOOD	-	-	1.5"	-	G	
313a	BEDROOM 2	28	68	D	-	WOOD	-	-	1"	-	F	DOOR STOP
314a	CLOSET	50	68	D	-	WOOD	-	-	1"	-	S	SLIDER
315a	DECK	30	68	A	1/2 TOL	METAL-40	-	-	Y	-	E	KICK PLATE, BALL BEARING HINGES, CLOSER, SILENCERS
400a	BATH	26	68	D	-	WOOD	-	-	1"	-	F	
400b	DECK	(3) 30	68	B	ALL TOL	METAL	-	-	Y	-	-	CENTER SLIDER w SPECIAL HARDWARE BY MANIFR.
407a	ATTIC A	26	36	D	-	WOOD	-	-	Y	-	G	
408a	ATTIC B	26	36	D	-	WOOD	-	-	Y	-	G	
408b	ATTIC B	26	36	D	-	WOOD	-	-	Y	-	G	
408c	ATTIC B	26	36	D	-	WOOD	-	-	Y	-	G	
409a	ATTIC C	26	36	D	-	WOOD	-	-	Y	-	G	
409b	ATTIC C	26	36	D	-	WOOD	-	-	Y	-	G	

NOTE:
 REFER TO SPECIFICATION FOR ALL DOOR & HARDWARE SPECIFICS.
 DOOR TYPES, HARDWARE, ETC.
 A = FIBERGLASS 1/2 GLASS, 2 PANEL BELOW, DOOR
 B = FULL TEMPERED GLASS CENTER SLIDER
 C = MOUNTING WOOD FRAME DOOR
 D = MOUNTING WOOD FRAME DOOR
 E = ENTRY HARDWARE- ADA LEVER, DEADBOLT w THUMBTURN
 F = GENERAL HARDWARE- ORBITAL, PRIVACY
 G = CLOSET HARDWARE- ORBITAL, PASSAGE
 S = SLIDER HARDWARE- SPECIAL INSET

NOTE:
 FINISH SUPPLEMENTARY TO VENTR SF TAKE OFFS & ADD
 APPROPRIATE WASTE FACTORS.

PERMIT SET 10-12-11