

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

DEERING RUN LLC

Located at

43 GEORGE ST

PERMIT ID: 2017-01471 **ISSUE DATE:** 01/29/2018 **CBL:** 140 F008001

has permission to **Alter lot lines and construct new single-family. 1.5 Stories, 1.5 bathrooms, 2 bedrooms. 831 sf.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

| | |
|---|---|
| Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required. | A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy. |
|---|---|

/s/ Greg Gilbert

Fire Official

/s/ Greg Gilbert

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

Use Group: **Type:**

Single Family Residence

ENTIRE

2009 IRC / MUBEC

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703
or email: buildinginspections@portlandmaine.gov

**Check the Status of Permit or Schedule an Inspection at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

REQUIRED INSPECTIONS:

Final - DRC

Site VISIT

Foundation/Backfill

Setbacks and Footings Prior to Pouring

Foundation/Rebar

Close-in Plumbing/Framing

Electrical - Residential

Final - Electric

Certificate of Occupancy/Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

| | | | | |
|---|--|---------------------------------|--|----------------------------|
| City of Portland, Maine - Building or Use Permit | | Permit No: 2017-01471 | Date Applied For: 09/15/2017 | CBL: 140 F008001 |
| 389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716 | | | | |
| Proposed Use: Single-family | Proposed Project Description: Alter lot lines and construct new single-family. 1.5 Stories, 1.5 bathrooms, 2 bedrooms. 831 sf. | | | |
| <p>Dept: Zoning Status: Approved w/Conditions Reviewer: Christina Stacey Approval Date: 01/29/2018</p> <p>Note: R-3 zone Ok to Issue: <input checked="" type="checkbox"/></p> <p>Flood Zone X, Panel 7 Note: This is considered a two-story structure because of the dormering. The normal side setback for a two-story in this zone is 14', however, this can be reduced to no less than 8' provided the difference is made up on the opposite site. The plan does achieve this. Side landing OK to project in front setback, per §14-425</p> <p>Conditions:</p> <ol style="list-style-type: none"> 1) Separate permits shall be required for future decks, sheds, pools, and/or garages. 2) This property shall remain a single family dwelling. Any change of use shall require a separate permit application for review and approval. 3) Prior to the issuance of a certificate of occupancy, a copy of the recorded deed for the new lot must be submitted. 4) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work. | | | | |
| <p>Dept: Building Inspecti Status: Approved w/Conditions Reviewer: Greg Gilbert Approval Date: 01/24/2018</p> <p>Note: Ok to Issue: <input checked="" type="checkbox"/></p> <p>Conditions:</p> <ol style="list-style-type: none"> 1) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work. 2) Review and approval by the Authority having Jurisdiction shall not relieve the applicant of the responsibility of compliance with this Code 3) All construction shall comply with City Code Chapter 10. 4) Separate permits are required for any electrical: plumbing, sprinkler, fire alarm, HVAC systems, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process. | | | | |
| <p>Dept: Fire Status: Approved w/Conditions Reviewer: Greg Gilbert Approval Date: 01/24/2018</p> <p>Note: Ok to Issue: <input checked="" type="checkbox"/></p> <p>Conditions:</p> <ol style="list-style-type: none"> 1) Fire extinguishers are required per NFPA 1 (2009 Edition) Table 13.6.2. The quantity, size, type and location shall be in accordance with NFPA 1, 13.6.8. 2) All construction shall comply with City Code, Chapter 10. All construction shall comply with 2009 NFPA 101 Life Safety Code, Chapter # 43 All construction shall comply with 2009 NFPA 1, Fire Code. This review and approval by the AHJ shall not relieve the applicant of the responsibility of compliance with this Code. NFPA 1 (section 1.14.4). 3) City of Portland Code Chapter 10 section 10-3 (L) all residential occupancies, and all new multiple occupancies containing attached parking structures or fuel burning appliances shall be protected in accordance with NFPA 720, Standard for the Installation of Carbon Monoxide (CO) Detection and Warning Equipment, 2009 edition. Detectors shall be provided in the following areas. <ol style="list-style-type: none"> 1. Outside each separate sleeping area, in the immediate vicinity of the sleeping areas 2. On each level of the dwelling unit, including basements but excluding attics and crawl spaces. | | | | |

PERMIT ID: 2017-01471

Located at: 43 GEORGE ST

CBL: 140 F008001

- 4) City of Portland Code Chapter 10 section 10-3 (i) all new single-station and or multiple-station smoke alarms shall be non-ionization (photoelectric) type. Smoke Alarms shall be installed per NFPA 101 2009 section 9.6.2.10. Detectors are required to be installed in the following locations
1. Inside all sleeping rooms.
 2. Outside each separate sleeping area, in the immediate vicinity of the sleeping areas
 3. On each level of the dwelling unit, including basements but excluding attics and crawl spaces.

Dept: DRC **Status:** Approved w/Conditions **Reviewer:** Robert Wiener **Approval Date:** 01/25/2018

Note: **Ok to Issue:**

Conditions:

- 1) The Development Review Coordinator (874-8632) must be notified five (5) working days prior to date required for final site inspection. Please make allowances for completion of site plan requirements determined to be incomplete or defective during the inspection. This is essential as all site plan requirements must be completed and approved by the Development Review Coordinator prior to issuance of a Certificate of Occupancy. Please schedule any property closing with these requirements in mind.
- 2) The approved site plan, with revised grading and drainage, is dated 1/24/18.
- 3) All damage to sidewalk, curb, street, or public utilities shall be repaired to City of Portland standards prior to issuance of a certificate of occupancy.
- 4) A sewer permit is required for your project. Please contact Carol Merritt at 874-8300, ext . 8822. The Wastewater and Drainage section of Public Services must be notified five (5) working days prior to sewer connection to schedule an inspector for your site.
- 5) A street opening permit(s) is required for your site. Please contact Carol Merritt ay 874-8300, ext. 8822. (Only excavators licensed by the City of Portland are eligible.)
- 6) As-built record information for sewer and stormwater service connections must be submitted to Public Services Engineering Section (55 Portland Street) and approved prior to issuance of a Certificate of Occupancy.
- 7) All Site work (final grading, landscaping, loam and seed) must be completed prior to issuance of a certificate of occupancy.
- 8) The Development Review Coordinator reserves the right to require additional lot grading or other drainage improvements as necessary due to field conditions.
- 9) Erosion and Sedimentation control shall be established and inspected by the Development Review Coordinator prior to soil disturbance, and shall be done in accordance with Best Management Practices, Maine Department of Environmental Protection Technical and Design Standards and Guidelines. All Erosion and Sedimentation control measures must be inspected and maintained daily.
- 10) The applicant shall have a licensed surveyor install, prior to the issuance of any Certificate of Occupancy, permanent mounumentation/pins identifying property corners.
- 11) A performance guarantee will be required to cover the cost of site work not completed due to seasonal conditions ie., finish grading, loaming, seeding, mulching, installation of street trees, etc. The performance guarantee must be reviewed, approved, and accepted by the Planning Authority prior to the release of a Temporary Certificate of Occupancy.
- 12) The site shall be developed and maintained as depicted in the approved site plan, written submission of the applicant, and these written conditions of approval. The modification of the approved site plan or alteration of a parcel which was the subject of site plan approval shall require the prior approval of a revised site plan by the Planning Authority.
- 13) Two (2) City of Portland approved species and size trees must be planted on your street frontage prior to issuance of a Certificate of Occupancy.