D4 PARTITION INFILL DETAIL

SCALE: 1/2" = 1'-0"

C4 FLOOR INFILL DETAIL

SCALE: 1 1/2" = 1'-0"

C5 CLG DETAIL

SCALE: 1 1/2" = 1'-0" UL No: L503

Window Schedule

Type Mark	Type	Sill Height	Width	Height	Escape Width	Escape Height	Escape Area (SQ FT)	Meets Escape Opening Requirement	Screen	Comments
26	DH	1' - 10"	2' - 8"	5' - 8"	2' - 4"	2' - 6"	5.83 sq ft	Yes	Yes	
27	DH	2' - 0"	2' - 8"	6' - 0"	2' - 5 1/2"	2' - 6"	6.15 sq ft	Yes	Yes	
28	DH	2' - 6"	3' - 0"	4' - 6"	1' - 11"	2' - 11"	5.59 sq ft		Yes	NO NEED TO REPLACE. OTHER WINDOWS IN ROOM MEET EGRESS

DOOR SCHEDULE

Mark	Phase	Door Size Width	Door Size Height	Door Glass	Comments
101	EXIST	3' - 2"	7' - 6"	YES	
102	EXIST	5' - 0"	6' - 8"	YES	
103	EXIST	5' - 0"	6' - 8"	YES	
104A	EXIST	2' - 6"	6' - 8"	NO	
105	EXIST	2' - 8"	6' - 8"	NO	
106A	EXIST	2' - 8"	6' - 8"	NO	
106B	EXIST	2' - 8"	6' - 8"	NO	
107	EXIST	2' - 8"	6' - 8"	YES	
108	EXIST	2' - 8"	6' - 8"	YES	
109	EXIST	3' - 0"	6' - 8"	YES	
110	EXIST	3' - 0"	6' - 8"	YES	
201A	EXIST	2' - 6"	6' - 8"	NO	
203	EXIST	2' - 6"	6' - 8"	YES	
206	EXIST	2' - 8"	6' - 8"	NO	
207	EXIST	2' - 6"	6' - 6"	NO	
208	EXIST	2' - 8"	6' - 8"	NO	
208A	EXIST	2' - 6"	6' - 6"	NO	
209	EXIST	2' - 6"	6' - 6"	NO	
210	EXIST	2' - 6"	6' - 6"	NO	
302	NEW	2' - 6"	6' - 6"	NO	COORDINATE DOOR AND FRAME SIZE IN FIELD. SEE PLAN FOR ADDITIONAL NOTES
303	EXIST	2' - 4"	6' - 6"	NO	
304	EXIST	2' - 6"	6' - 6"	NO	
306	EXIST	2' - 6"	6' - 6"	NO	
307	EXIST	2' - 6"	6' - 6"	NO	

Inspection Division
Date 08/28/13

HARRIMAN

AUBURN PORTLAND MANCHESTER

Cheverus High School
77 Read Street

Portland, Maine

Harriman Project No.	13608

Key Plan

Proj North

Issues and Revisions

Mark	Date	Description
	07-30-13	ISSUED FOR PERMIT

LICENSED ARCHITECT
MARK D. LEE
#3840
STATE OF MAINE

Drawing Scales
As indicated

PA / PE: MDL
Drawn By: JDO

© 2013 Harriman Associates

SCHEDULES & DETAILS

A7

Plot Date: 8/2/2013 3:48:35 PM