



City of Portland Land Use, Code of Ordinances Chapter 14
Sec. 14-391. Nonconformity as to number of dwelling units.

(a) Purpose. The purpose of this provision is to establish a process whereby certain dwellings which contain more dwelling units than the number permitted by the applicable provisions of the Land Use Code may be recognized as legal, nonconforming uses. This provision shall not apply to rooming units.

(b) Approval by Zoning Administrator.

1. Application. Application for validation of such non-conforming dwelling units shall be on a form provided by the Division of Housing and Neighborhood Services, Inspection Services Office. The application fee will be \$300.00 for each dwelling unit which is the subject of the application, and will be accompanied by: (i) a plan, drawn to scale, which shows the location of the building(s) on the lot, parking, easements, dumpsters, fencing, public ways and any other significant feature and (ii) a floor plan for each unit in the dwelling, whether or not it is the subject of the application.

(c) Eligibility. In order for a nonconforming dwelling unit to be validated by administrative action of the Zoning Administrator as authorized herein, the Zoning Administrator must find, based on competent evidence, supported by public records, that:

1. The nonconforming dwelling units were either in existence April 1, 1995, or the structure in which they are located was originally designed to accommodate more than the number of such units presently in use.
2. The applicant neither constructed nor established the non-conforming dwelling units.
3. The nonconforming dwelling units comply with or can be made to comply with current standards of the National Fire Protection Association Life Safety Code (§16-1) and the National Fire Protection Association 1: Fire Prevention Code (§10-16), as amended.
4. Each of the nonconforming dwelling units complies with provisions of the City's Housing Code or can be made to conform with, as amended, including, but not limited to, the requirements of §6-110, Minimum Standards for Space and Occupancy and §6-111, Minimum Plumbing Standards, and §6-112 Minimum Ventilation Standards.
5. The structure containing the nonconforming dwelling units is located in the R-3, R-4, R-5, R-6 or R-7 Zones; or the B-1, B-1(b), B-2, B-2(b) or B-3 Zones.