

**UNE - Ludcke Auditorium  
Portland, Maine**

[Click Here to Return to  
Bill of Material/Index](#)

**System Narrative**

**In the event of an alarm from an actuated device, the following shall**

**occur:** (Devices reporting an alarm: Manual Station, Smoke Detector, Heat Detector, or Beam Detector)

- 1) Notify the Fire Department via the Radio Master Box;  
Notify Campus Security via Digital Communicator (DACT) and Central Station
- 2) Annunciate audibly,visually, and in plain english the active initiating device at the Fire Alarm Control Panel
- 3) Activate the exerior Strobe/Beacon
- 4) Flash all strobe appliance circuits in a synchronized manner until the FACP has been reset.
- 5) Sound a Temporal Code 3 on all horn units until silenced. If Silenced, the evacuation tone shall resound.

**In the event of a supervisory condition from an actuated device, the following shall occur:**

- 1) Notify Campus Security via Digital Communicator (DACT) and Central Station
- 2) Annunciate audibly,visually, and in plain english the active initiating device at the Fire Alarm Control Panel

**In the event of a system trouble report, the following shall occur:**

- 1) Notify Campus Security via Digital Communicator (DACT) and Central Station
- 2) Annunciate audibly,visually, and in plain english the active initiating device at the Fire Alarm Control Panel