MATERIALS KEY

FLOORING	
DESIGNATION	DESCRIPTION
CPT-1	130.00 A YARD
CPT-2	140.00 A YARD
CPT-3	150.00 A YARD
WD	SOLID HD WD FLOOR
CONC	SEALED CONC.
CT	CERAMIC TILE
RUB	RUBBER TREADS, RISERS & LANDINGS
WALL BASE	
DESIGNATION	DESCRIPTION
VB	VINYL BASE
CT	CERAMIC TILE
WD	HISTORIC WD BASE
WALLS	
DESIGNATION	DESCRIPTION
GWB	
WC	WAINSCOTT - SEE INTERIOR ELEV. FOR INFO.
CEILINGS	
DESIGNATION	DESCRIPTION
GWB	
SAT	
-	-

FINISH NOTES:

A. SEAL CONC. FLOORS
B. SEE ELEVATION FOR EXTENT OF WAINSCOT
C. REINSTALL EXIST WD BASE AND WAINSCOT- SEE ELEVATION
D. PROVIDE WD BEAD BOARD WAINSCOT AND HISTORIC WD BASE DETAIL- SEE ELEVATIONS
E. MOST WALLS ARE EXISTING FOUNDATION OR CMU THAT DO NOT REQUIRE BASE OR PTD- PROVIDE BASE AND PTD WHERE GWB WALLS
F. PROVIDE CHALK AND CORD BD WITH WD TRAY, WD TRIM, WD BEAD BD AND HISTORIC WD BASE- SEE ELEVATION
G. PROVIDE CURVED WD BEAD BD CEILING- SEE ELEVATION, SECTION AND RCP

GENERAL FINISH NOTES:

1. IN MOST PLACES THE TOP SHEATHING HAS BEEN REMOVED LEAVING ORIGINAL ROUGH SHEATHING & ONE LAYER OF ¾"± OF FINISH FLOORING - REMOVE ANY ADDITIONAL SHEATHING IF IT REMAINS
2. AT CARPET, PROVIDE ½" PLYWD UNDERLAYMENT
3. AT WD FINISH FLOORS, PROVIDE ⅛" UNDERLAYMENT
4. STRUCT LEVELING HAS BEEN ON GOING AND WILL NEED TO BE EVALUATED FOR LEVELNESS WHEN CONSTRUCTION BEGINS - WHERE THE FLOOR IS NOT LEVEL, PROVIDE LEVELING COMPOUND BEFORE FINISHES ARE APPLIED

Room Number	Room Name	Floor	Base	North		East		South		West		Ceiling		
				Material	Finish	Material	Finish	Material	Finish	Material	Finish	Material	Height	Notes
001	MECHANICAL	CONC	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	STRUCT	8'-0"	A
002	STAIR	RUB	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	STRUCT	VARIES	
003	IT	CONC	N/A	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	7'-6"	A
004	ELEC	CONC	N/A	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	7'-6"	A
005	ELEVATOR MACHINE	CONC	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	7'-6"	A
006	LOBBY	CT	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	SAT	9'-0"	E
007	WOMENS BATH	TILE	TILE	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	E
008	MENS BATH	TILE	TILE	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	C
009	JAN. CLOSET	TILE	TILE	GWB	PTD-	GWB/FRP	PTD-	GWB/FRP	PTD-	GWB/FRP	PTD-	STRUCT	8'-0"	
010	LOUNGE	CPT1	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	SAT	9'-0"	
011	STAIR	RUB	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	VARIES	
100	FOYER	WD	WD	GWB	PTD-	PTD-	PTD-	PTD-	PTD-	PTD-	PTD-	GWB	12'-2"	D
101	LOBBY	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	11'-6"	
102	STAIR	RUB	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	STRUCT	VARIES	
103	LOBBY	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	11'-6"	
104	LOBBY	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	SAT	11'-6"	
105	CONFERENCE	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
106	CLOSET	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	VARIES	
107	CONFERENCE	CPT2	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
108	LOBBY	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	9'-2"	
109	AV	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	9'-2"	
110	COAT CLOSET	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	9'-2"	
111	RECEPTION	CPT3	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	WD	12'-7"	
112	STAIR	RUB	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	VARIES	
113	STAIR	RUB	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	VARIES	
201	LOUNGE	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
202	STAIR	EXISTING TREADS	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	VARIES	
203	BATH	TILE	TILE	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	
204	LOBBY	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	
205	COPIER	WD	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	
206	OFFICE	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	
207	ADMIN	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	9'-6'	
208	CLOSET	WD	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	
209	PROVOST	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
210	BATH	TILE	TILE	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	
211	ADMIN	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
212	KITCHEN	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
213	CLOSET	WD	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	
214	CONFERENCE	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
215	PRESIDENT OFFICE	WD	WD	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
216	CLOSET	WD	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
217	BATH	TILE	TILE	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	8'-0"	
218	MECHANICAL											GWB	8'-6"	
A201	ABPLANALP LOBBY	CPT	VB	GWB	PTD-	PTD-	PTD-	PTD-	PTD-	PTD-	PTD-	GWB	10'-0"	
A202	ABPLANALP STAIR	RUB	VB	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	PTD-	GWB	10'-0"	
	ELEVATOR	CPT												

65 NEWBURY STREET
PORTLAND, ME 04101
207.761.9000
info@portcityarch.com
WWW.PORTCITYARCH.COM

REGISTERED ARCHITECT
LYTA SEBERU
NO. 2567
STATE OF MAINE

UNE
UNIVERSITY OF NEW ENGLAND

Allied Engineering
Structural Mechanical Electrical Commissioning

CONSIGLI
Est. 1905

BECKER
STRUCTURAL ENGINEERS

PERMIT SET

REVISIONS

No.	Description	Date
-	-	-

UNIVERSITY OF NEW ENGLAND
PORTLAND, MAINE

ALUMNI HALL RENOVATION

ROOM SCHEDULE

Project Number	14525
Date	May 01, 2015
Drawn by	JP TS SM AR
Checked by	LAS

A5.1

Scale AS NOTED