

ALN440/ALN445/ALN540

Towne Commonst®



- Energy Saving LED technology
- Reliable efficient operation
- Type 2, 3, 4, 5 distributions
- 0-10V dimming ready
- LifeShield® protection system
- Surge protection included
- Wide variety of custom mounting options including post-top, wall mount or pole mount arm
- IP66 optics
- wiHUBB ready configurations
- DLC pending
- Available in 3000K, 4000K and 5000K
- Powder coat finish in 13 standard colors with polymer sealer

ORDERING INFORMATION

ALN440/ALN445/ALN540 - [] - [] - [] - [] - []

MODEL	
ALN440	
ALN440	Arm or post top mount
ALN440D	Top mounted arm or pendant mount
ALN445	Arm or post top mount
ALN445D	Top mounted arm or pendant mount
ALN540PM	Arm or post top mount
ALN540D	Top mounted arm or pendant mount
UPGRADE KIT ALN440-LK, ALN440D-LK ALN445-LK, ALN445D-LK ALN540PM-LK, ALN-540D-LK	
Distribution (Class 2, 120 thru 277 volt)	
Y2, Y3, Y4, Y5	IES Type 2, 3, 4, 5, distribution
Color Temperature	
32LED-3K	Warm White 3000K diodes
32LED-4K	Neutral White 4200K diodes
32LED-5K	Bright White 5100K diodes
Ballast/Driver	
700	700 milliamp drive current, 75 watts
Bezel Finish/Color Bezel available in 13 standard finishes and premium finishes (See Colors section)	

DISTRIBUTION	
Y2	Type 2
Y3	Type 3
Y4	Type 4
Y5	Type 5

COLOR TEMPERATURE	
32LED-3K	Warm White, 3000K output
32LED-4K	Neutral White, 4000K output
32LED-5K	Bright White, 5000K output

DRIVER	
120 thru 277 volt	
700	700mA drive current, 75 watts

FIXTURE FINISH	
WH	Arctic White
BL	Black
BLT	Matte Black
DGN	Dark Green
DB	Dark Bronze
TT	Titanium
WDB	Weathered Bronze
MDB	Metallic Bronze
VBV	Verde Blue
CRT	Corten
MAL	Matte Aluminum
MG	Medium Grey
AGN	Antique Green
LG	Light Grey
RAL/ PREMIUM COLOR	Provide a RAL 4 digit color number
CUSTOM COLOR	Please provide color chip for matching

OPTIONS	
CHM	Glass chimney with polished brass holder
CND	3-lamp candelabra with polished brass holder, lamps included. For decorative use only
LDL	Lightly diffused lens
SBL	Sandblast diffused lens
HSS-L	House side shield for use with clear lens only, consists of three field installed panels attached to the inside of the lens. Installing three panels blocks 180° of the lens
MAT	Must arm adapter slips over a 2 3/8"/60mm O.D. pipe and is secured with 4 stainless steel set screws. For Top mounted arm or pendant mount only.
PMS	Pendant mount with 48"/1220mm stem and canopy with swivel. For Top mounted arm or pendant mount only.
PMC	Pendant kit includes canopy and 48"/1220mm of brass chain. Top mounted arm or pendant mount only.
PT5	Post top adaptor for a 5"/127mm O.D. pole. ALN 440 only.
PT4	Post top adaptor for a 4"/100mm O.D. pole. ALN 445 only.
SCP	Programmable motion control, factory default is 50%, requires pole.

DIMENSIONS



ALN445
HEIGHT: 36"/915mm
LENGTH: 22"/560mm
WIDTH: 22"/560mm
WEIGHT: 52 lbs.
EPA: 3.45



ALN445D
HEIGHT: 31"/800mm
LENGTH: 22"/560mm
WIDTH: 22"/560mm
WEIGHT: 48 lbs.
EPA: 3.45



ALN440
HEIGHT: 31"/790mm
LENGTH: 18"/460mm
WIDTH: 18"/460mm
WEIGHT: 40 lbs.
EPA: 2.80

ALN440



ALN440D
HEIGHT: 26"/660mm
LENGTH: 18"/460mm
WIDTH: 18"/460mm
WEIGHT: 35 lbs.
EPA: 2.59

ALN440D



ALN540PM
HEIGHT: 35"/890mm
LENGTH: 18"/460mm
WIDTH: 18"/460mm
WEIGHT: 40 lbs.
EPA: 2.80

ALN540PM



ALN540D
HEIGHT: 21"/520mm
LENGTH: 18"/460mm
WIDTH: 18"/460mm
WEIGHT: 35 lbs.
EPA: 2.59

ALN540D

SCP (Sensor Control Programmable) pole accessory is available to provide occupancy detection for outdoor applications meeting California Title 24. For complete spec sheet and ordering information, visit www.aal.net/products/sensor_control_programmable/

Please visit www.aal.net for a complete listing of our poles/arms/accessories