



GENERAL NOTES:

- ITEMS ON THIS SHEET ARE EXISTING UNLESS OTHERWISE NOTED.
- COORDINATE REMOVALS WITH STRUCTURAL, MECHANICAL AND ELECTRICAL REMOVALS DRAWINGS.

- EXISTING KEYNOTES:**
- △ CARPET FLOORING.
 - △ GYPSUM BOARD, FURRING, AND RIGID INSULATION.
 - △ EIFS SYSTEM OVER CMU. (THIS SHEET ONLY)
 - △ EPDM ROOF.
 - △ METAL PARAPET CAP.
 - △ SKYLIGHT.
 - △ ROOF DRAIN.
 - △ VENT PIPE.
 - △ SCUPPER.
 - △ CONDENSER.
 - △ DUCT.

- REMOVALS KEYNOTES: (THIS SHEET ONLY)**
- △ REMOVE CARPET, MASTIC ADHESIVE AND VINYL BASE.
 - △ REMOVE PORTION OF STUD WALL WITH GYPSUM BOARD FINISH AS REQUIRED FOR CONCRETE SAWCUTTING REMOVALS. COORDINATE WITH MECHANICAL DRAWINGS FOR ADDITIONAL STUD WALL REMOVALS AS REQUIRED FOR DUCT REMOVALS.
 - △ REMOVE 2'-6" X 7'-0" HOLLOW METAL DOOR, FRAME AND HARDWARE.
 - △ SAWCUT AND REMOVE PORTION OF CMU WALL - COORDINATE WITH STRUCTURAL DRAWINGS.
 - △ REMOVE PORTION OF EIFS SYSTEM.
 - △ REMOVE PAPER TOWEL DISPENSER SYSTEM.
 - △ REMOVE PORTION OF METAL PARAPET CAP.
 - △ REMOVE GYPSUM BOARD CEILING AND COLD-FORMED METAL CEILING FRAMING.
 - △ SAWCUT AND REMOVE CONCRETE SLAB FOR PLUMBING WORK - COORDINATE WITH MECHANICAL AND PLUMBING DRAWINGS.
 - △ SAWCUT AND REMOVE PORTION OF CONCRETE FOUNDATION WALL - COORDINATE WITH STRUCTURAL DRAWINGS.
 - △ REMOVE PORTION OF GYPSUM BOARD, FURRING AND RIGID INSULATION.
 - △ REMOVE 21"± x 21"± CEILING ACCESS DOOR.
 - △ REMOVE CEILING DIFFUSER. COORDINATE WITH MECHANICAL DRAWINGS.
 - △ REMOVE LIGHT FIXTURE AND SURFACE CONDUIT. COORDINATE WITH ELECTRICAL DRAWINGS.
 - △ REMOVE AND SALVAGE SPRINKLER HEAD AND REMOVE DETECTOR. COORDINATE WITH MECHANICAL AND ELECTRICAL DRAWINGS.
 - △ REMOVE GYP BD FINISH AS REQUIRED FOR PLUMBING REMOVALS - COORDINATE WITH MECHANICAL DRAWINGS.
 - △ SAW CUT AND REMOVE 8"X16" OPENING IN EXIST. CONC. PARAPET PER NEW SCUPPER. COORDINATE LOCATION WITH NEW SCUPPER OPENING. SEE DETAIL 4/SF201 AND 5/AE302.
 - △ SAW CUT AND REMOVE STUD WALL WITH GYPSUM BOARD FINISH. RETAIN EXIST. STUD FRAMING AND GYPSUM BOARD FOR NEW SOFFIT. SEE DETAIL 6/AE301.

