SEQUENCE OF OPERATION MATRIX

	Alarm Signal to Cari	Alarm Signal to Fire	Radio Master Box Activate Exteri	Annunciate ax F.	M Activate Horn C	Activate Elevas	Record Event ,	Supervisory Signal	Trouble Signal to C	Stral Communicator (DACT)
System Inputs	Α	В	С	D	Е	F	G	Н	I	System Inputs
Manual Pull Station	x	x	х	х	х		x			Manual Pull Station
Area Smoke Detector	х	х	х	х	х		х			Area Smoke Detector
Area Heat Detector	х	х	х	х	х		х			Area Heat Detector
Elevator Smoke Detector	х	х	х	х	х	х	х			Elevator Smoke Detector
Kitchen Hood System				х	х		х			Kitchen Hood System
Fire Alarm - AC Failure				х			х		х	Fire Alarm - AC Failure
Fire Alarm - Low Battery				х			х		х	Fire Alarm - Low Battery
Signal Line Open Circuit				х			х		х	Signal Line Open Circuit
Signal Line Ground Fault				х			х		х	Signal Line Ground Fault
Strobe Circuit Open				х			х		х	Strobe Circuit Open
Strobe Circuit Ground				х			х		х	Strobe Circuit Ground
System Ground Fault				х			х		x	System Ground Fault
	Α	В	С	D	E	F	G	Н	I	