IF THIS SHEET IS NOT 24 X 36 IT IS A REDUCED SCALE PRINT – SCALE ACCORDINGLY

DOOR SCHEDULE

			DOOR			FRAME	NOTES
NUM	DESCRIPTION	SIZE	MAT	Type	RATING	MAT	
200A	ELEVATOR A	3'-0" X 7'-0"	N/A	N/A	--	MTL	
203A	HALL TO LAB	(2) 3'-0" X 7'-0"	WD	8	--	MTL	
203B	HALL TO LAB	3'-0" X 7'-0"	WD	3	--	MTL	
204A	LAB TO PREP	3'-0" X 7'-0"	WD	2	--	MTL	
205A	HALL TO DRUG INFO	(2) 3'-0" X 7'-0" w/fix leaf	WD	8	--	MTL	
206A	HALL TO ELEC	3'-0" X 7'-0"	WD	5	1 1/2 HR	MTL	
207A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
208A	HALL TO OFF	3'-0" X 7'-0"	WD	3	--	MTL	
209A	HALL TO OFF	3'-0" X 7'-0"	WD	3	--	MTL	
210A	HALL TO STAIR	3'-0" X 7'-0"	WD	4	1 1/2 HR	MTL	
211A	HALL TO BATH	3'-0" X 7'-0"	WD	5	--	MTL	
212A	HALL TO BATH	3'-0" X 7'-0"	WD	5	--	MTL	
213A	HALL TO STAIR B	3'-0" X 7'-0"	WD	4	1 1/2 HR	MTL	
214A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
215A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
216A	HALL TO WORK	3'-0" X 7'-0"	WD	9	--	MTL	
217A	HALL TO CONF	3'-0" X 7'-0"	WD	3	--	MTL	
217B	HALL TO CONF	3'-0" X 7'-0"	WD	3	--	MTL	
218A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
219A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
220A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
221A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
222A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
223A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
224A	HALL TO HOTELLING	3'-0" X 7'-0"	WD	3	--	MTL	
225A	HALL TO DEPART	3'-0" X 7'-0"	WD	3	--	MTL	
226A	DEPART TO CHAIR	3'-0" X 7'-0"	WD	3	--	MTL	
228A	HALL TO ASST. DEAN	3'-0" X 7'-0"	WD	3	--	MTL	
230A	HALL TO STOR	3'-0" X 7'-0"	WD	3	--	MTL	
231A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
232A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
233A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
234A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
235A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
236A	HALL TO DATA	3'-0" X 7'-0"	WD	5	--	MTL	
237A	HALL TO HOTELING	3'-0" X 7'-0"	WD	3	--	MTL	
238A	HALL TO JANITOR	3'-0" X 7'-0"	WD	5	--	MTL	
239A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
240A	HALL TO STOR	3'-0" X 7'-0"	WD	5	45 MIN	MTL	
242A	HALL TO DEPART	3'-0" X 7'-0"	WD	3	--	MTL	
243A	DEPART TO CHAIR	3'-0" X 7'-0"	WD	3	--	MTL	
277A	KITCH TO HALL	3'-0" X 7'-0"	N/A	N/A	--	MTL	H
277B	KITCH TO HALL	3'-0" X 7'-0"	N/A	N/A	--	MTL	H

			DOOR			FRAME	NOTES
NUM	DESCRIPTION	SIZE	MAT	Type	RATING	MAT	
300A	HALL TO EA	3'-6" X 7'-0"	WD	2	--	MTL	B
300B	HALL TO EA	3'-6" X 7'-0"	WD	2	--	MTL	B
300C	HALL TO EA	3'-6" X 7'-0"	WD	2	--	MTL	B
301A	HALL TO STAIR	3'-0" X 7'-0"	WD	4	1 1/2 HR	MTL	
303B	HALL TO CONF	3'-0" X 7'-0"	WD	3	--	MTL	
304A	HALL TO BREAK	3'-0" X 7'-0"	WD	3	--	MTL	
305A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
307A	HALL TO STOR	3'-0" X 7'-0"	WD	5	--	MTL	
308A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
310A	HALL TO GRAD	3'-0" X 7'-0"	WD	3	--	MTL	
311A	HALL TO MENS	3'-0" X 7'-0"	WD	5	--	MTL	
312A	HALL TO GRAD	3'-0" X 7'-0"	WD	3	--	MTL	
313A	HALL TO WOMENS	3'-0" X 7'-0"	WD	5	--	MTL	
314A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
315A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
316A	HALL TO STAIR	3'-0" X 7'-0"	WD	4	1 1/2 HR	MTL	
317A	HALL TO RECYCLE	3'-0" X 7'-0"	WD	5	45 MIN	MTL	
318A	HALL TO JANITOR	3'-0" X 7'-0"	WD	5	--	MTL	
319A	HALL TO DEPART	3'-0" X 7'-0"	WD	3	--	MTL	
320A	DEPT TO CHAIR	3'-0" X 7'-0"	WD	3	--	MTL	
321A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
322A	HALL TO OFFICE	3'-0" X 7'-0"	WD	3	--	MTL	
324A	EA TO PROCEDE	3'-6" X 7'-0"	WD	2	--	MTL	
325A	EA TO PROCEDE	3'-6" X 7'-0"	WD	2	--	MTL	
326A	EA TO PROCEDE	3'-6" X 7'-0"	WD	2	--	MTL	
336A	EA TO PROCEDE	3'-6" X 7'-0"	WD	2	--	MTL	
337A	EA TO PROCEDE	3'-6" X 7'-0"	WD	2	--	MTL	
338A	EA TO PROCEDE	3'-6" X 7'-0"	WD	2	--	MTL	
339A	EA TO PROCEDE	3'-6" X 7'-0"	WD	2	--	MTL	
343A	HALL TO PROCEDE	3'-6" X 7'-0"	WD	2	--	MTL	
344A	DARKRM TO HALL	3'-6" X 7'-0"	WD	5	--	MTL	
350A	ELEVATOR B	4'-0" X 7'-0"	N/A	N/A	--	MTL	
351A	ELEVATOR A	3'-6" X 7'-0"	N/A	N/A	--	MTL	
402A	STAIR B TO MECH ATTIC	3'-0" X 7'-0"	WD	4	1 1/2 HR	MTL	

NOTES:

A. Trim out frame w/ HDWD
B. Provide security swipe card.
C. Automatic door opener
D. Sliding
E. ADD ALT #1
F. Overhead door
G. Provide blocking for future door - see add alter
H. MTL door frame only
J. Provide red film at door window

General Note: Lender cut Offices, Conf, Ballroom doors by 3/4"

PERMIT SET - NOT FOR CONSTRUCTION

PORT CITY ARCHITECTURE

65 NEWBURY STREET
PORTLAND, ME 04101
207.761.9000
fax: 207.761.2010
lita@portcityarch.com

JACOBS CONSULTANCY
GPR Laboratory Planning Practice

VANZELM ENGINEERS
VANZELM HEYWOOD & SHADFORD, INC.

BECKER structural engineers, inc.

SYTDesign CONSULTANTS
CIVIL ENGINEERING & LANDSCAPE ARCHITECTURE

ALLIED/COOK CONSTRUCTION

Favreau

Titan Mechanical

UNIVERSITY OF NEW ENGLAND

COLLEGE OF PHARMACY

716 STEVENS AVENUE, PORTLAND, ME

#	DATE	DESCRIPTION

PERMIT SET

Date Issued 01/24/08

Project Number 06506

GODDARD

SHEET NAME

SCHEDULES

Drawn By EAC & ANM

Checked By LAS

A7.2

COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of PORT CITY ARCHITECTURE PA