IF THIS SHEET IS NOT 24 X 36 IT IS A REDUCED SCALE PRINT - SCALE ACCORDINGLY

SCALE 1"=1' 1/2"=1" 3/4"=1" 1/4"=1" 1/8"=1" 1/16"=1"

ROOM FINISH SCHEDULE

			Floors		Chair Rail			Walls								Ceiling		Notes
			Floor	Base	Mater	Finish	Height	N	Finish	E	Finish	S	Finish	W	Finish	Mater	Height	
000		Hall	VCT/VIN	VB 2	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-0"	4
001		Stair A	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT	VARIES	
002		Emer Exit	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
003		Cont.	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
004		NMR	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
005		Lab	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
006		Break	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT5	GWB	PT5	GWB	PT5	GWB	PT5	SAT 1	9'-0"	4
007		Storage	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 1	9'-0"	4
008		Office	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 1	9'-0"	4
009		Waste 1	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
010		Data	VCT/VIN	CONC	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	
011		Plumbing	VCT/VIN	CONC	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	
012		Stair B	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	
013		HW	VCT/VIN	CONC	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	
014		CW	VCT/VIN	CONC	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	STRUCT	9'-0"	
015		EMR	VCT/VIN	CONC	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	STRUCT	9'-0"	
016		AHU Room	VCT/VIN	CONC	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	STRUCT	9'-0"	
017		Electric I	VCT/VIN	CONC	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	STRUCT	9'-0"	
018		Electric II	VCT/VIN	CONC	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	STRUCT	9'-0"	
021		W. Lock	TILE	TILE	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
022		Hall	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
023		Hall	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
024		Janitor	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
025		Hall	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
026		Quarantine	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
027		Quarantine	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
028		Quarantine	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
030		Quarantine	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
031		Hall	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
032		Feed	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
033		Soiled	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	10'-0"	4
034		Laundry	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
035		Clean	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	10'-0"	4
038		Bed	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
039		Hall	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
040		AHR	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
041		AHR	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
042		Procedure	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
043		AHR	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
044		Procedure	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
045		AHR	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
046		Sterl	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
047		AHR	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
048		AHR	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
049		Janitor	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	STRUCT	9'-0"	4
050		Expend	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
051		Anim. Rsc.	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
052		Prep	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
053		A.L.	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	9'-0"	4
054		M. Lock	TILE	TILE	TILE	N/A	N/A	GWB	PT4	GWB	PT4	GWB	PT4	GWB	PT4	GWB	9'-0"	4
055		Storage	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	9'-0"	4
056		Stair	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	9'-0"	
057		Shell Space	CONC	N/A	N/A	N/A	N/A	CONC	N/A	N/A	N/A	N/A	N/A	N/A	N/A	STRUCT	VARIES	
100		Hall	TILE	TILE	N/A	N/A	N/A	GWB	PT1/3	GWB	PT1/3	GWB	PT1/3	GWB	PT1/3	GWB/SATI	9'-0"	1
101		Vestibule	WM	VB	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	10'-2"	
102		Hall	CPTB	VB 2	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SATI	8'-3"	
103		Stair A	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	VARIES	
104		Hall	PT1	VB 2	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SATI	8'-3"	
105		Stair B	VCT/VIN	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	VARIES	

			Floors		Chair Rail			Walls								Ceiling		Notes
			Floor	Base	Mater	Finish	Height	N	Finish	E	Finish	S	Finish	W	Finish	Mater	Height	
106		Student Area	CPT6	VB	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SATI	9'-0"	1
107		Kitchen	TILE	WD	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	8'-3"	
108		Vestibule	WM	VB	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB	10'-2"	
109		Lecture	CPT C	WD	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	GWB/SATI	VARIES	
110		Pharm Practice	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT2	9'-6"	1
111		Mock Pharm	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT2	9'-0"	
112		Ster	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT2	8'-3"	
114		Video	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT2	8'-3"	
115		Rec/Wait	CPT A/B	VB 2	WD	POLIED	34"	GWB	PT5	GWB	PT5	GWB	PT5	GWB	PT5	SATI	8'-3"	
116		S Assist	CPT2	WD	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-3"	1
117		Conf	CPT A	WD	WD	POLIED	34"	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-3"	1
118		Dean	CPT A	WD	WD	POLIED	34"	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-3"	1
120		Assis Dean	CPT C	VB 2	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-3"	
121		Kitchen	TILE	TILE	N/A	N/A	N/A	GWB	PT5	GWB	PT5	GWB	PT5	GWB	PT5	SATI	8'-3"	1
122		Copier	TILE	TILE	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-3"	
123		Conference	CPT A	VB	WD	POLIED	34"	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-0"	
124		Men's	TILE	TILE	TILE	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	8'-0"	2
125		Woman's	TILE	TILE	TILE	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	8'-0"	2
126		Utilities	CONC	N/A	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT	8'-3"	3
127		Waste 2	CONC	N/A	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT		3
128		Hall	PT1	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-10"	
129		Waste 3	CONC	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT		
130		Prep	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	8'-3"	
131		Prep	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	8'-3"	
132		Hall	CPTB	VB 2	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 2	8'-3"	
133		Control	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 1	8'-3"	
142		Storage	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1	SAT 1	8'-3"	
143		Janitor	VCT	VB 1	N/A	N/A	N/A	GWB	PT1	GWB	PT1	GWB	PT1	GWB	PT1			
200		Hall	CPT1-4	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB/SATI	VARIES	1
201		Hall	CPT1	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	VARIES	
202		Hall	CPT1	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	VARIES	
203		Pharm Teaching Lab	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
204		Prep	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	8'-7"	1
205		Drug Info	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
206		Electric	CONC	N/A	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT		
207		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
208		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
209		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
210		Stair A	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	VARIES	
211		Men's	PT2	PT2	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	8'-7"	2
212		Women's	PT2	PT2	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	8'-7"	2
213		Stair B	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	VARIES	
214		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
215		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
216		Work	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	1
217		Conference	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
218		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
219		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
220		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
221		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
222		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
223		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
224		Hoteling	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI		
225		Depart	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8-7"	
226		Chair	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
228		Asst. Dean	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'7"	
229		Kitchen	TILE	TILE	N/A	N/A	N/A	GWB	PT5	GWB	PT5	GWB	PT5	GWB	PT5	SATI	8'-7"	
230		Storage	CONC	N/A	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
231		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
232		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	

			Floors		Chair Rail			Walls								Ceiling		Notes
			Floor	Base	Mater	Finish	Height	N	Finish	E	Finish	S	Finish	W	Finish	Mater	Height	
233		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
234		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
235		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
236		Data	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'7"	3
237		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
238		Jan	CPT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT	8'-7"	
239		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
240		Storage	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	3
242		Depart	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
243		Chair	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	8'-7"	
300		Hall	CPT1	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
301		Stair A	VCT/VIN	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	VARIES	
302		Entry	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT	PTD	
303		Conf	CPT3	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
304		Break	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
305		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
306		Copy	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
307		Storage	VCT	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
308		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
310		Grad	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
311		Men	PT2	PT	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	9'-6"	
312		Grad	CPT3	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
313		Women	PT2	PT	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	9'-6"	
314		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
315		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
316		Stair B	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	VARIES	
317		Recycle	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
318		Jan	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT	9'-6"	
319		Depart.	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
320		Chair	CPT3	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
321		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
322		Office	CPT2	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SATI	9'-6"	
323		Entry														STRUCT	PTD	
324		Procede	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
325		Procede	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
326		Procede	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
327		Lab Space	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
328		B&C	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
329		Bench	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
330		FH	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
331		FH	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
332		B&C	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
333		Bench	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
334		FH	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
335		B&C	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
336		Procede	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
337		Procede	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
338		Procede	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
339		Procede	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
340		Ster	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT	PTD	
341		CTR	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT	PTD	
342		CTR	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT	PTD	
343		Procede	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	SAT2	9'-6"	
344		Dark Room															9'-6"	
401		Mechanical Attic	VCT 142	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	STRUCT		
402		Stair B	VCT/VIN	VB	N/A	N/A	N/A	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	GWB	VARIES	

NOTES: 1. MILLWORK - SEE ELEVATIONS
2. WAINSCOT TO 34"
3. SEAL CONC
4. ADD ALT.
NOTE: HIGH IMPACT GWB IN VIVARIUM

BID SET - NOT FOR CONSTRUCTION

PORT • CITY ARCHITECTURE
65 NEWBURY STREET
PORTLAND, ME 04101
207.761.9000
fax: 207.761.2010
lita@portcityarch.com

JACOBS CONSULTANCY
GPR Laboratory Planning Practice
VANZELM ENGINEERS
VANZELM HEYWOOD & SHADFORD, INC.
BECKER structural engineers, inc.
SYTDesign CONSULTANTS
CIVIL ENGINEERING & LANDSCAPE ARCHITECTURE
ALLIED/COOK CONSTRUCTION
Favreau ELECTRIC
Titan Mechanical, Inc. Design Build Engineering - Mechanical Controlling

UNIVERSITY OF NEW ENGLAND

COLLEGE OF PHARMACY

716 STEVENS AVENUE, PORTLAND, ME

#	DATE	DESCRIPTION
		BID SET

Date Issued 01/08/08

Project Number 06506

SHEET NAME
ROOM FINISH SCHEDULE

Drawn By EC, AM, EK

Checked By LAS

A7.3

COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of PORT CITY ARCHITECTURE PA