


REMOVALS KEYNOTES

- △ REMOVE 3'-0"±x7'-0"± HOLLOW METAL DOOR, FRAME AND HARDWARE.
- △ REMOVE 6'-0"±x7'-0"± HOLLOW METAL DOOR, FRAME AND HARDWARE.
- △ REMOVE 1'-6"±x7'-0"± WOOD DOOR, FRAME AND HARDWARE.
- △ REMOVE 16'-0"±x12'-0"± OVERHEAD SECTIONAL DOOR, DOOR FRAME AND HARDWARE.
- △ REMOVE 8'-10"±x3'-0"± AND 6'-0"±x3'-0"± COILING DOOR, FRAME AND HARDWARE.
- △ REMOVE AND STORE EXISTING SLIDING DOOR, FRAME AND HARDWARE FOR REINSTALLATION.
- △ REMOVE WOOD FRAMED STAIRS, RAILING AND GUARD RAILS.
- △ REMOVE BORROWED LIGHT.
- △ REMOVE 21'-0"± HIGH METAL WIRE CAGE WALL AND METAL CAGE DOORS.
- △ REMOVE TOILET ACCESSORIES (TOILETS, URINALS, SINKS, TOILET PARTITIONS ETC.) COORDINATE WITH PLUMBING REMOVALS.
- △ REMOVE WOOD BASE CABINETS, WOOD WALL CABINETS AND PLASTIC LAMINATE COUNTERTOP.
- △ REMOVE STAINLESS STEEL 3 BAY DISH WASH SINK.
- △ REMOVE HAND WASH SINK.
- △ REMOVE 4"± CMU WALL.
- △ REMOVE 6"± CMU WALL.
- △ REMOVE 8"± CMU WALL.
- △ REMOVE BRICK 8"± WALL.
- △ REMOVE 6"± WOOD FRAMED AND WOOD PANEL WALL.
- △ REMOVE 2"x4" WOOD FRAMED WALL WITH OSB SHEATHING.
- △ REMOVE 4"± CMU WALL WITH WOOD FURRING AND GYPSUM BOARD FINISH.
- △ REMOVE WOOD FRAMED GYPSUM BOARD WALL PARTITION 9'-0"± HIGH.
- △ REMOVE WOOD BUILT-IN SHELVING UNIT.
- △ REMOVE CERAMIC TILE, GYPSUM BOARD WALL PARTITION.
- △ REMOVE METAL FRAMED WINDOW AND GLASS BLOCK.
- △ REMOVE GLASS BLOCK WINDOW.
- △ REMOVE STAINLESS STEEL SINKS AND PLASTIC LAMINATE COUNTER TOP.
- △ REMOVE 3'-0"±x7'-0"± WOOD DOOR, FRAME AND HARDWARE.
- △ REMOVE METAL ROOF LADDER.
- △ REMOVE 2'-0"±x4'-0"± SUSPENDED CEILING TILE AND GRID SYSTEM.
- △ REMOVE PLASTER CEILING.
- △ REMOVE METAL VAULT DOOR 3'-0"±x6'-8"±.
- △ REMOVE STEEL DOOR 3'-6"±x7'-0"±.
- △ REMOVE REINFORCED CONCRETE VAULT CEILING. COORDINATE WITH DRAWING SD103.
- △ SAWCUT AND REMOVE REINFORCED CONCRETE VAULT SLAB. COORDINATE WITH DRAWING SD103.
- △ REMOVE, SALVAGE AND STORE EXISTING UPPER AND LOWER CABINETS, COUNTER TOP AND FIXTURES.
- △ REMOVE EPDM ROOF SYSTEM WITH 3"-5" OF POLYISO INSULATION, TAPERED POLYISO INSULATION, ADHERED EPDM MEMBRANE, AND EPDM FLASHING.
- △ CUT AND REMOVE PORTION OF EPDM ROOF SYSTEM, INSULATION AND ROOF DECK AND STRUCTURE.
- △ REMOVE ALUMINUM STOREFRONT DOORS, SIDE LIGHTS, HARDWARE AND FRAMES.
- △ REMOVE 3'-6"±x7'-0"± HOLLOW METAL DOOR, FRAME AND HARDWARE.
- △ REMOVE BRICK WALL WITH WOOD FURRING AND GYPSUM BOARD FINISH.
- △ REMOVE 3-5/8" METAL STUD WITH GYPSUM BOARD FINISH.
- △ REMOVE CERAMIC TILE FLOORING.
- △ REMOVE FURRED WALL SYSTEM FROM EXISTING EXTERIOR MASONRY WALL.
- △ REMOVE METAL PAN CONCRETE FILLED STAIR AND RAILINGS.
- △ REMOVE VINYL COMPOSITE FLOORING.
- △ REMOVE 1'-0"±x1'-0"± ACOUSTIC CEILING TILE AND FRAMING.
- △ REMOVE 3"± CONCRETE PLANK CEILING.
- △ REMOVE CARPET TILE.
- △ REMOVE 4'-0"±x7'-0"± HOLLOW METAL DOOR, FRAME AND HARDWARE.
- △ SAWCUT AND REMOVE CONCRETE SLAB ON GRADE. COORDINATE WITH DRAWING SD101.
- △ REMOVE MECHANICAL EQUIPMENT ROOF CURB. COORDINATE WITH MECHANICAL REMOVALS.
- △ REMOVE MECHANICAL DUCT ROOF WORK. COORDINATE WITH MECHANICAL REMOVALS.
- △ REMOVE ANTENNA, GUIDE WIRES, AND ANCHORS.
- △ REMOVE PLUMBING VENT PIPES. COORDINATE WITH PLUMBING REMOVALS.
- △ REMOVE EXISTING MECHANICAL PIPING. COORDINATE WITH MECHANICAL REMOVALS.
- △ REMOVE CONCRETE BLOCK.
- △ REMOVE 3"± ELECTRICAL CONDUIT.
- △ REMOVE SOLAR TUBES.
- △ CUT AND REMOVE PORTION OF EPDM ROOF SYSTEM, INSULATION AND ROOF DECK.
- △ REMOVE EXISTING PLYWOOD FLOOR SHEATHING, FLOOR JOISTS AND BLOCKING. COORDINATE WITH DRAWING SD1014.
- △ REMOVE PORTION OF BRICK/CMU WALL.
- △ REMOVE 6'-4"±x7'-4" PORTION OF BRICK WALL.
- △ REMOVE WOOD BUILT SLOPING ROOF AND EPDM ROOF.



ARCHITECTURE ENGINEERING PLANNING
231 Main Street, Boscawen, Maine 04005, (11) 207-283-0199, (F) 207-283-4283
www.oakpoint.com



DESIGNED BY: TGB
DRAWN BY: DEM
CHECKED BY: TGB
PROJECT: 21502.10

UNIVERSITY OF NEW ENGLAND
PORTLAND CAMPUS
STEVEN AVENUE ARMORY
718 STEVENS AVE
PORTLAND, MAINE 04103
(1) 207-283-0171

RENOVATIONS TO THE
STEVENS AVENUE ARMORY

REMOVAL KEYNOTES

SCALE: AS NOTED
DATE: 05-24-16

DWG. **AD001**